



841 Sun Gro Dr. Elizabeth City, NC 27909
252-335-9503 phone | www.barnhillcontracting.com
NC General Contractors License No. 3194

January 27, 2023

Re: Bid Date: February 23, 2023
Hyde County Airport
Engelhard, NC
Quotations Requested

Ladies & Gentlemen:

**** ATTENTION** Please be sure to contact the Estimator listed below.**

Barnhill Contracting Company will be bidding on the following project on **February 23rd, 2023**. We are most interested in receiving a quote from your company on this project:

County:
Hyde County, NC

Project
Hyde County Airport

Contact James C. Spivey, jspivey@barnhillcontracting.com, at (252) 335-9503 / FAX (252) 335-7452 in our Elizabeth City Office, located at 841 Sun Gro Drive, Elizabeth City, North Carolina 27909

Pre-Bid Meeting ~ Wednesday, February 8th 2023, at 10:00 AM
(Due to social distancing standards, this meeting will be held in a virtual manner utilizing conference call and online meeting tools. Please email the estimator for pre-bid meeting details)

The combined MBE/WBE goal for this project is 3%. This project includes the following opportunities for making the goal:

- **Hauling (Millings, Asphalt, Stone & Plant Stock)**
- **Pavement Markings**
- **Milling**
- **Miscellaneous Concrete**
- **Storm Drain/Pipe Installation**
- **Erosion Control**
- **Crack Repair**
- **Seeding & Mulching**
- **Airfield Lighting/Signage/Markings**

We will accept quotes on any portions of this project, large or small. Where practical, we will work to break down or combine portions of work in an effort to encourage your participation.

Please note: Any subcontracts **may** require a bond. Please check with the above listed estimator. If you need assistance with obtaining bonding, lines of credit, or insurance required by the owner or Barnhill, please do not hesitate to contact us. We would appreciate if you could contact us a minimum of 5 days prior to bid day when possible.

Please feel free to contact us if you need assistance in obtaining necessary equipment, supplies, materials, or related services. Joint check and or quick pay agreements can be arranged to help with cash flow issues.

We will be glad to accept collect calls regarding this project. The bid for this project goes in at 1:30 PM on Thursday, February 23rd, 2023, so we ask that all bids be in to us *as soon as possible*, preferably by **12:00 Noon on Tuesday, February 21st, 2023 and no later than 5:00 PM on Tuesday, February 21st, 2023** to allow us sufficient time for compiling our tabulations.

For hauling operations, we will need to know how many of your own hauling units will be available for this project. We will need this on your written quote prior to bid time and this will be made a part of any subcontract. If you have any interest in this project, we would appreciate your advising us of the items you may be interested in (please do not forget to put your name and phone number on returned bid sheet), and return the enclosed sheet to us.

We would appreciate hearing from you at your earliest convenience. If you need additional information or help, you may note it on the bid sheet. (Collect calls will be accepted.).

By submitting a quote, it is understood that you have read and understand the specifications on the project. Plans may be viewed in our office at the address listed above.

“The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C. §§ 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively ensure that any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award. In accordance with other related nondiscrimination authorities, bidders and contractors will also not be discriminated against on the grounds of sex, age, disability, low-income level, creed/religion, or limited English proficiency in consideration for an award.”

The lowest responsible subcontractor at the time each bid is turned in will be awarded those items, if we get that job.

Yours very truly,

BARNHILL CONTRACTING COMPANY

James C. Spivey

James C. Spivey
Project Manager

JCS/cre

SPECIFICATIONS
and
CONTRACT DOCUMENTS
FOR

- SCH. I: RUNWAY 11-29 REHABILITATION
AND TAXIWAY TURNAROUNDS;**
- SCH. II: EXTENSION OF RUNWAY 11;**
- SCH. III: PARKING LOT AND ENTRY ROAD
REHABILITATION**
- SCH. IV-A: PAPI REPLACEMENT**
- SCH. IV-B: WIND CONE REPLACEMENT**

**HYDE COUNTY AIRPORT
ENGELHARD, NORTH CAROLINA**

**PREPARED FOR:
HYDE COUNTY BOARD OF COMMISSIONERS**

**IN COOPERATION WITH:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION –
DIVISION OF AVIATION
and
FEDERAL AVIATION ADMINISTRATION**

Engineer:
TALBERT & BRIGHT, INC.
Engineering and Planning Consultants
4810 Shelley Drive
Wilmington NC 28405
(910) 763-5350

TBI No. 2702-1802
January 2023
NC Engineering License No. C-0713



Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
1	C-100	Contractor Quality Control Program (CQCP)		LS	1		
2	C-102	Temporary Seeding and Mulching		Acre	13		
3	C-102	Temporary Silt Fence, Installation and Removal		LF	11,640		
4	C-102	Temporary Silt Fence Stone Outlet		Each	16		
5	C-102	Temporary Construction Entrance		Each	1		
6	C-102	Temporay Rock Pipe Inlet Protection		Each	2		
7	C-102	Riprap Pipe Outlet Protection		Each	2		
8	C-102	Excelsior Matting		SY	5,090		
9	C-105	Mobilization		LS	1		
10	C-105	Engineer's / RPR Field Office		Month	6		
11	P-101	Crack Cleaning and Filling		LF	50,000		
12	P-101	Bituminous Pavement Repair (Full Depth)		SF	1,000		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
13	P-101	Bituminous Pavement Milling (Constant 0.5" Depth)		SY	52,250		
14	P-101	Bituminous Pavement Milling (Variable Depth)		SY	555		
15	P-101	Shoulder Preparation		SY	2,200		
16	P-152	Shoulder Grading		SY	31,000		
17	P-152	Unclassified Excavation		CY	40		
18	P-152	Borrow Embankment		CY	13,900		
19	P-152	Borrow Bridge Lift		CY	10,500		
20	P-152	Undercut Excavation		CY	10,500		
21	P-152	Non-Woven Geotextile Fabric		SY	15,750		
22	P-209	Crushed Aggregate Base Course		CY	1,620		
23	P-401	Bituminous Leveling Course		Ton	6,300		
24	P-401	Bituminous Surface Course		Ton	9,750		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
25	P-602	Emulsified Asphalt Prime Coat		Gal	2,160		
26	P-603	Emulsified Asphalt Tack Coat		Gal	12,930		
27	P-620	Surface Preparation		SF	58,930		
28	P-620	Permanent Pavement Marking (First Application) - White Paint with Rust Inhibitor		SF	53,500		
29	P-620	Permanent Pavement Marking (Final Application) - White Paint with Rust Inhibitor with Type III Beads		SF	53,500		
30	P-620	Permanent Pavement Marking (First Application) - Yellow Paint		SF	2,630		
31	P-620	Permanent Pavement Marking (Final Application) - Yellow Paint with Type III Beads		SF	2,630		
32	D-701	18 Inch Reinforced Concrete Pipe, Class IV		LF	256		
33	D-701	Post Installation Pipe Video Inspection and Report		LS	1		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
34	D-752	Concrete Flared End Section (18 Inch)		Each	4		
35	T-901	Seeding		Acre	9		
36	T-901	Watering		1,000 gal	332		
37	T-904	Sodding (Bermuda)		SY	6,160		
38	T-908	Mulching		Acre	9		
39	L-108	Trenching for Direct Buried Cable		LF	2,880		
40	L-108	L-824 Underground Cable, 1/C, No. 8 AWG, 5 kV, Type C, Installed in Trench or Conduit, Including Connections/Terminations		LF	3,230		
41	L-108	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed, Including Ground Rods and Connections/Terminations		LF	2,830		
42	L-108	Supplemental Ground Rod, Including #6 AWG Counterpoise, Trenching, and All Connections		Each	80		
43	L-110	1 Way 4 Inch PVC Concrete Encased Duct		LF	150		
44	L-115	Electrical Junction Cans, L-867(D), Class 1A, 16" Diameter, 24" Deep, with 1/2" Galvanized Steel Cover and Gasket Secured with Stainless Steel Bolts, Installed in Turf, Complete with Incidentals. Align and Level as Required		Each	6		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
45	L-125	Runway Light Demolition and Removal		LS	1		
46	L-125	Medium Intensity Quartz Runway Threshold/End Light, Type L-861E, Stake Mounted, Including Ground Rod and Connectors, Installed Complete		Each	6		
47	L-125	Medium Intensity Quartz Runway Threshold/End Light, Type L-861E, Base Mounted, Including Ground Rod and Connectors, Installed Complete		Each	2		
48	L-125	Medium Intensity LED Taxiway Edge Light, Type L-861T(L), Stake Mounted, Including Ground Rod and Connectors, Installed Complete		Each	52		
49	L-125	Medium Intensity LED Taxiway Edge Light, Type L-861T(L), Base Mounted, Including Ground Rod and Connectors, Installed Complete		Each	16		
50	L-125	New LED Guidance Sign, L-858(L), Size 2, Style 2, Class 1, Mode 2, Two Module, Installed Complete on New Concrete Base		Each	4		
51	L-125	Raise Stake Mounted Runway or Taxiway Lights		Each	43		
52	L-125	Raise Base Mounted Runway or Taxiway Lights		Each	9		

Total - Schedule I: Runway 11-29 Rehabilitation and Taxiway Turnarounds (Base Bid)

Contract Time: See Project Special Provisions

Liquidated Damages: See Project Special Provisions

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule II: Extension of Runway 11 (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
1	C-100	Contractor Quality Control Program (CQCP)		LS	1		
2	C-102	Temporary Seeding and Mulching		Acre	3		
3	C-102	Temporary Silt Fence, Installation and Removal		LF	810		
4	C-102	Temporary Silt Fence Stone Outlet		Each	4		
5	C-102	Excelsior Matting		SY	660		
6	C-105	Mobilization		LS	1		
7	P-152	Unclassified Excavation		CY	685		
8	P-152	Borrow Embankment		CY	4,400		
9	P-152	Borrow Bridge Lift		CY	4,700		
10	P-152	Undercut Excavation		CY	4,700		
11	P-152	Non-Woven Geotextile Fabric		SY	7,000		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule II: Extension of Runway 11 (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
12	P-209	Crushed Aggregate Base Course		CY	780		
13	P-401	Bituminous Surface Course		Ton	800		
14	P-602	Emulsified Asphalt Prime Coat		Gal	1,040		
15	P-603	Emulsified Asphalt Tack Coat		Gal	350		
16	P-620	Surface Preparation		SF	9,420		
17	P-620	Permanent Pavement Marking (First Application) - White Paint with Rust Inhibitor		SF	9,420		
18	P-620	Permanent Pavement Marking (Final Application) - White Paint with Rust Inhibitor with Type III Beads		SF	9,420		
19	T-901	Seeding		Acre	2		
20	T-901	Watering		1,000 gal	58		
21	T-904	Sodding (Bermuda)		SY	940		
22	T-908	Mulching		Acre	2		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule II: Extension of Runway 11 (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
23	L-108	Electrical Demolition and Removal		LS	1		
24	L-108	Trenching for Direct Buried Cable		LF	870		
25	L-108	L-824 Underground Cable, 1/C, No. 8 AWG, 5 kV, Type C, Installed in Trench or Conduit, Including Connections/Terminations		LF	870		
26	L-108	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed, Including Ground Rods and Connections/Terminations		LF	870		
27	L-108	Supplemental Ground Rod, Including #6 AWG Counterpoise, Trenching, and All Connections		Each	11		
28	L-125	Medium Intensity Quartz Runway Edge Light, Type L-861, Stake Mounted, Including Ground Rod and Connectors, Installed Complete		Each	3		
29	L-125	Medium Intensity Quartz Runway Threshold/End Light, Type L-861E, Stake Mounted, Including Ground Rod and Connectors, Installed Complete		Each	6		
30	L-125	Medium Intensity Quartz Runway Threshold/End Light, Type L-861E, Base Mounted, Including Ground Rod and Connectors, Installed Complete		Each	2		
31	L-125	Change Globe On Existing Medium Intensity Quartz Runway Edge Light, Base Mounted		Each	2		

Total - Schedule II: Extension of Runway 11 (Base Bid)

Contract Time: See Project Special Provisions
Liquidated Damages: See Project Special Provisions

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
1	C-100	Contractor Quality Control Program (CQCP)		LS	1		
2	C-102	Temporary Seeding and Mulching		Acre	2		
3	C-102	Temporary Silt Fence, Installation and Removal		LF	1,470		
4	C-105	Mobilization		LS	1		
5	P-101	Pavement Removal (2", Close to Apron)		SY	175		
6	P-101	Bituminous Pavement Milling (Constant 2" Depth)		SY	4,075		
7	P-101	Bituminous Pavement Milling (Variable Depth)		SY	40		
8	P-152	Shoulder Grading		SY	1,300		
9	P-209	Crushed Aggregate Base Course		CY	415		
10	PSP-42	Bituminous Surface Course (NCDOT Type S9.5C)		Ton	525		
11	P-602	Emulsified Asphalt Prime Coat		Gal	1,265		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
12	P-620	Surface Preparation		SF	1,600		
13	P-620	Permanent Pavement Marking (First Application) - White Paint with Rust Inhibitor		SF	1,600		
14	PSP-44	Accessible Parking Sign		Each	1		
15	D-705	12 inch Geocomposite Stripdrain, Installed		LF	2,150		
16	D-705	4" PVC Collector Pipe		LF	350		
17	D-705	Outfall Pipe Cleanout		Each	10		
18	D-705	Outfall Pipe Endwall		Each	10		
19	T-901	Seeding		Acre	2		
20	T-901	Watering		1,000 gal	85		
21	T-904	Sodding (Bermuda)		SY	950		
22	T-908	Mulching		Acre	2		

Total - Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)**Contract Time:** See Project Special Provisions**Liquidated Damages:** See Project Special Provisions

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule IV-A: PAPI Replacement

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
1	C-105	Mobilization		LS	1		
2	P-610	Concrete Walkway		LS	1		
3	T-901	Seeding		Acre	1		
4	T-901	Watering		1,000 gal	18		
5	T-908	Mulching		Acre	1		
6	PSP-39	Vault Connection		LS	1		
7	L-108	Trenching for Direct Buried Cable		LF	4,100		
8	L-108	2 - 1/C, No. 4 AWG Underground Cable, 600V, Type USE and 1/C No. 4 Ground, Installed in Trench		LF	4,340		
9	L-108	No. 4/0 AWG Ground Loop, Complete with No. 2 AWG Ground Wire to Handhole and Units, Ground Rods, Exothermic Welds, and Other Incidentals Necessary for a Complete Installation, Installed in Trench		LF	340		
10	L-108	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed, Including Ground Rods and Connections/Terminations		LF	4,600		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule IV-A: PAPI Replacement

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
11	L-108	Supplemental Ground Rod, Including #6 AWG Counterpoise, Trenching, and Connectors		Each	2		
12	L-110	1-2" HDPE Conduit, Directionally Drilled		LF	205		
13	L-115	Electrical Junction Cans, L-867(D), Class 1A, 16" Diameter, 24" Deep, with 1/2" Galvanized Steel Cover and Gasket Secured with Stainless Steel Bolts, Installed in Turf, Complete with Incidentals. Align and Level as Required		Each	2		
14	L-125	Existing PAPI Systems Demolition and Removal		LS	1		
15	L-125	New L-881(L) LED PAPI (2 Unit), Style A, Class 1, Installed, Including Wiring Between Units, Interlock Relay, Conduits, Handholes, Foundation, Aiming Device Kit, and Flight Check Adjustments		Each	2		

Total - Schedule IV-A - Base Bid

Contract Time: See Project Special Provisions

Liquidated Damages: See Project Special Provisions

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
1	C-105	Mobilization		LS	1		
2	T-901	Seeding		Acre	1		
3	T-901	Watering		1,000 gal	18		
4	T-908	Mulching		Acre	1		
5	PSP-39	Vault Connection		LS	1		
6	L-107	L-807(L) Primary Wind Cone, Style 1-B, Size 2 with L-810 Obstruction Light, Installed Including Foundation, Isolation Transformer, Conduits and Base Can, Including Removal of Existing Wind Cone and Foundation		LS	1		
7	L-107	Painting of Existing Segmented Circle		LS	1		
8	L-107	Repair/Replacement of Segmented Circle Sections		Each	10		

Hyde County Airport

TBI No. 2702-1802

Schedule I: Runway 11-29 Rehabilitation & Taxiway Turnarounds (Base Bid)

Schedule II: Extension of Runway 11 (Base Bid)

Schedule III: Parking Lot and Entry Road Rehabilitation (Base Bid)

Schedule IV-A: PAPI Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Schedule IV-B: Wind Cone Replacement (Add Alternate)

Item	Spec.	Description	Unit Price in Words	Unit	Quantity	Unit Price	Ext. Total
9	L-108	Trenching for Direct Buried Cable		LF	1,230		
10	L-108	2 - 1/C, No. 4 AWG Underground Cable, 600V, Type USE and 1/C No. 4 Ground, Installed in Trench		LF	1,350		
11	L-108	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed, Including Ground Rods and Connections/Terminations		LF	1,350		
12	L-108	Supplemental Ground Rod, Including #6 AWG Counterpoise, Trenching, and Connectors		Each	1		
13	L-115	Electrical Junction Cans, L-867(D), Class 1A, 16" Diameter, 24" Deep, with 1/2" Galvanized Steel Cover and Gasket Secured with Stainless Steel Bolts, Installed in Turf, Complete with Incidentals. Align and Level as Required		Each	2		

Total - Schedule IV-B: Wind Cone Replacement (Add Alternate)**Contract Time:** See Project Special Provisions**Liquidated Damages:** See Project Special Provisions