

ADDENDUM TO
SPECIFICATIONS ENTITLED
"SPECIFICATIONS FOR
EAST MECKLENBURG HIGH SCHOOL
PARTIAL ROOF REPLACEMENT PROJECT
CHARLOTTE, NORTH CAROLINA"

ADDENDUM NO. 1

March 27, 2023

The Specifications contained in the project manual entitled "Specifications for East Mecklenburg High School, Partial Roof Replacement Project, Charlotte, North Carolina" are amended as follows:

SECTION 070000 – PREPARATION FOR REROOFING

1. Reference Part 3 – EXECUTION, add the following sentence to 3.1 PREPARATION, GENERAL:

- F. Prior to commencement of any work, remove patches or other obstructions over drain leaders. Contractor is responsible for clearing any obstructions within drain leader assemblies. Contractor to include within bid pricing from licensed plumbing subcontractor accordingly to clear any obstructions.

2. Reference Part 3 – EXECUTION, add the following new Section 3.4:

3.4 ABANDONED CURBS AND EQUIPMENT

- A. Contractor to field verify all abandoned equipment with Charlotte-Mecklenburg Schools prior to deletion.
 - B. Fill void with polyisocyanurate insulation and extend modified bitumen flashings over existing opening.
 - C. Contractor to install new 24 gauge sheet metal curb caps after equipment has been removed and discarded.

Nothing herein is to be interpreted or construed as changing any provisions of the specifications except as specifically stated herein.

END OF ADDENDUM