




1 RAMP AND STAIR FOUNDATION PLAN  
1/4" = 1'-0"

### WOOD STAIR AND RAMP FOUNDATION PLAN NOTES

1. FOOTINGS SHALL BE CENTERED ON WOOD POST CENTERLINES UNLESS OTHERWISE DIMENSIONED. SEE PLAN.
2. REFER TO SITE DRAWINGS FOR ACTUAL FINISHED ELEVATIONS. REFERENCED FINISHED EXTERIOR GRADE ELEVATION WILL BE 0'-0".
3. PROVIDE MIN. 4" OF WASH STONE (#57) BELOW ALL FOUNDATION ELEMENTS, TYP.
4. ALL DIMENSIONS SHOWN ARE TO CENTERLINE OF POST, TYP. UNLESS NOTED OTHERWISE. CONTRACTOR TO VERIFY DIMENSIONS PRIOR TO CONSTRUCTION, TYP.
5. REFER TO DETAILS ON SHEET S-4 FOR ALL WOOD POST FOOTING REQUIREMENTS, TYP.
6. ALL POST TO BE SUPPORTED BY EMBED FOOTINGS, UNLESS NOTED OTHERWISE ON PLAN. IN LOCATIONS NOTED ON PLAN AS NON-EMBED FOOTINGS, POST MAY BE SUPPORTED BY SPREAD FOOTING. REF. TO PLAN FOR WOOD POST FOOTING TYPE BY LOCATION, TYP.
7. REFER TO ARCHITECTURAL DRAWINGS FOR WOOD POST LOCATIONS, TYP.

### WOOD POST FOOTING KEY



DRYE-McGLAMERY  
ENGINEERING, PLLC  
NC FIRM LICENSE #P-1305  
PO BOX 1558  
RALEIGH, NORTH CAROLINA 27619  
PHONE: 704.960.0180



### RAMP AND STAIR FOUNDATION PLAN

Modular Office Relocation for  
NCDOT Highway Division 5  
Bridge Maintenance Office  
5650 CORNWALL ROAD  
OXFORD, NORTH CAROLINA 27565

STATE: CONSTRUCTION  
ID# 22-24690-01A

EQUIPMENT NUMBER:  
1320-0008-3222

REVISIONS	
NO.	DATE

DATE ISSUED: 9/5/2023  
DRAWN BY: DJM  
CHECKED BY: HWD

SHEET NO.

S-3