



City of Raleigh

**Neuse River Resource Recovery Facility (RRF) Roof
Replacements, Filter and Blower Buildings**

Construction Documents Project Manual

Revised 100% Issued for Construction

March 31, 2026


HDR Project No. 10444408



This page intentionally left blank.

00 01 07
SEALS AND SIGNATURES

Owner Name: City of Raleigh
Facility or Site Name: Neuse River Resource Recovery Facility (RRF)
Project Name: Neuse River RRF Roof Replacements, Filter and Blower Buildings
Project or Contract Designation: 10444408
Engineer: HDR Engineering, Inc. of the Carolinas

Joshua Hooker, PE License No. 040012 	The seal and signature to the left applies to the following Specifications divisions and sections of this project manual: • Division 02 • Division 03 • Division 05
Paul Forrest, RA License No. 13400 	The seal and signature to the left applies to the following Specifications divisions and sections of this project manual: • Division 06 • Division 07

Engineer's and Architect's seal and signature does not apply to the documents that comprise Division 00, Bidding and Contracting Requirements.

It is a violation of applicable laws and regulations governing professional licensing and registration for any person, unless acting under the direction of the licensed and registered design professional(s) indicated above, to alter in any way the Specifications in this project manual.

END OF SEALS AND SIGNATURES

This page intentionally left blank.

TABLE OF CONTENTS

<u>Document</u>	<u>Title</u>

00010	Table of Contents

BIDDING REQUIREMENTS

00100	Advertisement for Bids
00200	Instruction to Bidders
00409	Bidder's Checklist
00410	Bid Form
00430	Bid Bond
00440	Information for Bidders Regarding Compliance with the City of Raleigh's MWBE Program • Acknowledgment of MWBE Policy • Identification of Certified MWBE Participation • Affidavit A – Listing of Good Faith Effort • Affidavit B - Intent to Perform Contract with Own Workforce • Affidavit C – Portion of the Work to be Performed by Certified MWBE Businesses • Affidavit D – Good Faith Effort • Affidavit E – Certified Subcontractor Payment Form • Request to Change a Certified MWBE Subcontractor
00441	Contractor's Certificates: Affidavit of Organization and Authority and Sworn Statement
00442	City of Raleigh Contractor's Poor Performance Policy
00443	Non-Collusive Affidavit
00444	Notice to Contractor Regarding Intrusion Beyond Project Limits

CONTRACT REQUIREMENTS

00510	Notice of Award
00520	Agreement between Owner and Contractor for Construction Contract
00550	Notice to Proceed
00610	Performance Bond
00615	Payment Bond
00617	Affidavit
00618	Page for Attaching Certificate of Insurance
00620	Contractor's Application for Payment
00625	Certificate of Substantial Completion
00634	Page for Attaching Power of Attorney
00700	Standard General Conditions of the Construction Contract (EJCDC, 2018)
00800	Supplementary Conditions
00805	Procedures for Reporting NC Sales Tax Expenditures on City of Raleigh Contracts

<u>Document</u>	<u>Title</u>
00810	Rules Implementing Mediated Settlement Conferences in NC Public Construction Projects
00940	Work Change Directive(s)
00941	Change Order(s)
00942	Field Order(s)
-	RRD Wastewater Environmental Management System Memorandum of Understanding

TECHNICAL SPECIFICATIONS

DIVISION 01 – GENERAL REQUIREMENTS

01 11 00	Summary of Work
01 31 19	Project Meetings
01 33 00	Submittal Procedures
01 35 43.13	Environmental Procedures for Hazardous Materials
01 41 50	Health and Safety Requirements
01 50 00	Temporary Facilities
01 57 05	Temporary Controls
01 60 00	Product Requirements
01 70 00	Execution Requirements
01 74 00	Cleaning

DIVISION 02 - EXISTING CONDITIONS

02 41 00	Demolition

DIVISION 03 - CONCRETE

03 00 05	Concrete
03 15 19	Anchorage to Concrete

DIVISION 05 - METALS

05 50 00	Metal Fabrications

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00	Rough Carpentry

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 54 25	Fully Adhered TPO Roofing
07 72 33	Roof Hatches

END OF DOCUMENT

ADVERTISEMENT FOR BIDS
POSTED: FEBRUARY 27, 2026
CITY BID NUMBER: 274-RRR

Project: Neuse River RRF Roof Replacements, Filter & Blower Buildings

Owner: City of Raleigh, North Carolina, Raleigh Water, One Exchange Plaza, Suite 620, Raleigh, NC 27601.
Contact: Dan Williams, dan.williams@raleighnc.gov

Engineer: HDR, 555 Fayetteville Street, Suite 900, Raleigh, NC 27601

Sealed Bids will be received until 2:00 pm, Wednesday, April 1, 2026, at the Neuse River Resource Recovery Facility Administration Building, 8500 Battle Bridge Road, Raleigh, NC 27610, at which time and place bids will be publicly opened and read aloud for the construction of the Neuse River RRF Roof Replacements, Filter & Blower Buildings project.

After Bids are opened, the Owner shall evaluate them in accordance with the methods and criteria set forth in the Instructions to Bidders. The Owner/City Council reserves the right to waive any informality or to reject any or all Bids. Unless all Bids are rejected, Award will be made to the lowest responsible and responsive Bidder, taking into consideration quality, performance and the time specified in the Bid Form for the performance of the Contract.

A Mandatory Pre-Bid Meeting will be held at 10:00 am, Monday, March 16, 2026 at the Neuse River Resource Recovery Facility Administration Building, 8500 Battle Bridge Road, Raleigh, NC 27610 with a site visit to follow.

Requirements for pre-bid submittals of an "or-equal" are required within 10 days of the issuance of the Advertisement for Bids and in accordance with Section 00200, Instructions to Bidders.

The Project consists generally of the following major items:

At the NRRRF Blower Building & Filter Building #1:

- Removal of existing curbs and roofing materials
- Installation of new roofing materials
- Removal and reinstallation of lightning protection features
- Misc. work

Bidding Documents may be examined at Owner's/Engineer's office and at: ConstructConnect, online; McGraw Hill Dodge Company, online; Construction Journal, online; and NC Institute of Minority Economic Development (a.k.a. The Institute), online.

Complete Bidding Documents may be obtained by registering at the office of the Owner. Electronic documents will be provided at no cost.

With each request for Bidding Documents supply the following information: Company name, contact person, street address, phone number, and email address for Bidding point of contact; N. C. contractor's license with limitation and classification; indicate if the firm will be a Prime bidder, Supplier or Sub-Contractor.

Bidders will be required to show evidence that they are licensed to perform the work in the Bidding Documents as required by North Carolina General Statute, Chapter 87 and the Instruction to Bidders.

Bid Security in the amount of five percent (5%) of the Bid must accompany each Bid and shall be subject to the conditions provided in the Instruction to Bidders.

Pursuant to General Statutes of North Carolina Sections 143-128.2 and 143-131, and in accordance with City policy, the City of Raleigh encourages and provides equal opportunity for certified Minority and Woman-Owned Business Enterprise (MWBE) businesses to participate in all aspects of the City's contracting and procurement programs to include Professional Services; Goods and Other Services; and Construction. The prime contractor will be required to identify participation of MWBE businesses in their Bid, and how that participation will be achieved.

Furthermore, the City's goal is to contract or sub-contract fifteen percent (15%) of the contract amount to certified MWBEs on construction projects over \$300,000, or with contracts that include \$100,000 or more in state funding.

City of Raleigh

Janet Cowell, Mayor

END OF DOCUMENT

INSTRUCTIONS TO BIDDERS
TABLE OF ARTICLES

	Page
Article 1 – Defined Terms	1
Article 2 – Copies of Bidding Documents	2
Article 3 – Qualifications of Bidders	2
Article 4 – Examination of Bidding Documents, Other Related Data, and Site	4
Article 5 – Pre-Bid Conference	6
Article 6 – Site and Other Areas	6
Article 7 – Interpretations and Addenda	6
Article 8 – Bid Security	7
Article 9 – Contract Times	7
Article 10 – Liquidated Damages.....	7
Article 11 – “Or-Equal” Items	7
Article 12 – Subcontractors, Suppliers and Others.....	8
Article 13 – Preparation of Bid	8
Article 14 – Basis of Bid; Comparison of Bids	9
Article 15 – Submittal of Bid	10
Article 16 – Modification and Withdrawal of Bid	10
Article 17 – Opening of Bids	111
Article 18 – Bids to Remain Subject to Acceptance	111
Article 19 – Evaluation of Bids and Award of Contract	111
Article 20 – Contract Security and Insurance	12
Article 21 – Signing of Agreement	12
Article 22 – Sales and Use Tax	12

ARTICLE 1 – DEFINED TERMS

1.01 Terms used in these Instructions to Bidders have the meanings indicated in the General Conditions and Supplementary Conditions. Additional terms used in these Instructions to Bidders have the meanings indicated below:

- A. *Issuing Office* – The office from which the Bidding Documents are to be issued and which registers plan holders.

ARTICLE 2 – COPIES OF BIDDING DOCUMENTS

- 2.01 Complete sets of the Bidding Documents in the number and for the deposit sum, if any, stated in the Advertisement For Bids may be obtained by registering with the Issuing Office as identified in the advertisement.
- 2.02 Complete sets of Bidding Documents shall be used in preparing Bids; neither Owner nor Engineer assumes any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
- 2.03 Owner and Engineer, in making copies of Bidding Documents available on the above terms, do so only for the purpose of obtaining Bids for the Work and do not authorize or confer a license for any other use.
- 2.04 Plan rooms (including construction information subscription services, and electronic and virtual plan rooms) may distribute the Bidding Documents, or make them available for examination. Those prospective bidders that obtain an electronic (digital) copy of the Bidding Documents from a plan room are encouraged to register as plan holders from the Bidding Documents Website or Issuing Office. Owner is not responsible for omissions in Bidding Documents or other documents obtained from plan rooms, or for a Bidder's failure to obtain Addenda from a plan room.
- 2.05 *Electronic Documents*
 - A. When the Bidding Requirements indicate that electronic (digital) copies of the Bidding Documents are available, such documents will be made available to the Bidders as Electronic Documents in the manner specified.
 - 1. Bidding Documents will be provided in Adobe PDF (Portable Document Format) (.pdf) that is readable by Adobe Acrobat Reader. It is the intent of the Engineer and Owner that such Electronic Documents are to be exactly representative of the paper copies of the documents. However, because the Owner and Engineer cannot totally control the transmission and receipt of Electronic Documents nor the Contractor's means of reproduction of such documents, the Owner and Engineer cannot and do not guarantee that Electronic Documents and reproductions prepared from those versions are identical in every manner to the paper copies.
 - B. Unless otherwise stated in the Bidding Documents, the Bidder may use and rely upon complete sets of Electronic Documents of the Bidding Documents, described in Paragraph 2.05.A above. However, Bidder assumes all risks associated with differences arising from transmission/receipt of Electronic Documents versions of Bidding Documents and reproductions prepared from those versions and, further, assumes all risks, costs, and responsibility associated with use of the Electronic Documents versions to derive information that is not explicitly contained in printed paper versions of the documents, and for Bidder's reliance upon such derived information.

ARTICLE 3 – QUALIFICATIONS OF BIDDERS

- 3.01 Bidders are notified that relevant Articles of Chapter 87 of the General Statutes of North Carolina, will be observed in receiving and awarding contracts. Bidders for this Project must be properly licensed for the Work.

- 3.02 To demonstrate Bidder's qualifications to perform the Work prior to award, within 5 days of Owner's request, Bidder shall submit written evidence such as financial data, previous experience, present commitments, and such other data as may be called for below.
- A. Evidence of Bidder's authority to do business in the state where the Project is located.
 - B. Bidder's state contractor license number.
 - C. Official name of Bidder and length of time the organization has been in business under present name.
 - D. Address, phone and fax numbers of main place of business. Address and phone numbers of company office that will manage the Project if different than above.
 - E. Officers of the company. Name and resume of designated project manager and field superintendent. Number of regular employees of the organization.
 - F. Latest financial statement showing assets and liabilities of the company.
 - G. Name and home office address of the Surety proposed and the name and address of the responsible local claim agent.
 - H. Listing of completed projects of similar size and type in the last 5 years. Provide name and phone number of project owner representative.
 - I. Existing work commitments.
 - J. List of work to be subcontracted. Name and addresses of subcontractors.
 - K. Names and addresses of major material Suppliers.
 - L. Statement that bidder is capable of completing the project within the stated time.
 - M. Safety record of company for the last 5 years showing any violations, etc.
 - N. List of all claims/resolutions/final judgements for the last 10 years.
 - O. Failure or refusal to furnish information requested shall constitute a basis for disqualification of Bidder and the withholding of the Bid Bond.
- 3.03 The apparent Low Bidder shall submit within 72 hours of the Bid Date the following Affidavits:
- A. Affidavit C, Portion of the Work to be Performed by Certified MWBE Businesses.
 - B. Affidavit D, Good Faith Efforts.
 - C. Failure or refusal to furnish information requested shall constitute a basis for disqualification of Bidder and the withholding of the Bid Bond.

- 3.04 Bidder is advised to carefully review those portions of the Bid Form requiring Bidder's representations and certifications.

ARTICLE 4 – EXAMINATION OF BIDDING DOCUMENTS, OTHER RELATED DATA, AND SITE

4.01 *Subsurface and Physical Conditions*

A. The Supplementary Conditions identify:

1. Those reports known to Owner of explorations and tests of subsurface conditions at or contiguous to the Site.
2. Those drawings known to Owner of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities).

- B. Copies of reports and drawings referenced in Paragraph 4.01.A will be made available by Owner to any Bidder on request. Those reports and drawings are not part of the Contract Documents, but the "technical data" contained therein upon which Bidder is entitled to rely as provided in Paragraph 5.03 of the General Conditions has been identified and established in Paragraph 5.03 of the Supplementary Conditions. Bidder is responsible for any interpretation or conclusion Bidder draws from any "technical data" or any other data, interpretations, opinions, or information contained in such reports or shown or indicated in such drawings.

4.02 *Underground Facilities*

- A. Information and data shown or indicated in the Bidding Documents with respect to existing Underground Facilities at or contiguous to the Site is based upon information and data furnished to Owner and Engineer by owners of such Underground Facilities, including Owner, or others.

4.03 *Hazardous Environmental Condition*

- A. The Supplementary Conditions identify any reports and drawings known to Owner relating to a Hazardous Environmental Condition identified at the Site.

- B. Copies of reports and drawings referenced in Paragraph 4.03.A will be made available by Owner to any Bidder on request. Those reports and drawings are not part of the Contract Documents, but the "technical data" contained therein upon which Bidder is entitled to rely as provided in Paragraph 5.06 of the General Conditions has been identified and established in Paragraph 5.06 of the Supplementary Conditions. Bidder is responsible for any interpretation or conclusion Bidder draws from any "technical data" or any other data, interpretations, opinions, or information contained in such reports or shown or indicated in such drawings.

- 4.04 Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders with respect to subsurface conditions, other physical conditions, and Underground Facilities, and possible changes in the Bidding Documents due to differing or unanticipated subsurface or physical conditions appear in Paragraphs 5.03, 5.04, and 5.05 of the General Conditions. Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders with respect to a Hazardous Environmental Condition at the Site, if any, and possible changes in the Contract Documents due to any Hazardous Environmental Condition uncovered or revealed at the Site which was not shown or indicated in the Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work, appear in Paragraph 5.06 of the General Conditions.

- 4.05 On request, Owner will provide Bidder access to the Site to conduct such examinations, investigations, explorations, tests, and studies as Bidder deems necessary for submission of a Bid. Bidder shall fill all holes and clean up and restore the Site to its former condition upon completion of such explorations, investigations, tests, and studies. Bidder shall comply with all applicable Laws and Regulations relative to excavation and utility locates.
- 4.06 Reference is made to Article 8 of the Supplementary Conditions for the identification of the general nature of other work that is to be performed at the Site by Owner or others (such as utilities and other prime contractors) that relates to the Work contemplated by these Bidding Documents. On request, Owner will provide to each Bidder for examination access to or copies of contract documents (other than portions thereof related to price) for such other work.
- 4.07 Paragraph 7.13.G of the General Conditions indicates that if an Owner safety program exists, it will be noted in the Supplementary Conditions.
- 4.08 It is the responsibility of each Bidder before submitting a Bid to:
- A. Examine and carefully study the Bidding Documents, and the other related data identified in the Bidding Documents, including any Addenda;
 - B. Visit the Site and become familiar with and satisfy Bidder as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work;
 - C. Become familiar with and satisfy Bidder as to all federal, state, and local Laws and Regulations that may affect cost, progress, and performance of the Work;
 - D. Carefully study all: (1) reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities) that have been identified in Paragraph 5.03 of the Supplementary Conditions as containing reliable Technical Data, and (2) reports and drawings of Hazardous Environmental Conditions, if any, at the Site that have been identified in the Paragraph 5.06 of the Supplementary Conditions as containing reliable Technical Data;
 - E. Consider the information known to Bidder; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Bidding Documents; and the Site-related reports and drawings identified in the Bidding Documents, with respect to the effect of such information, observations, and documents on (1) the cost, progress, and performance of the Work; (2) the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including applying any specific sequences of construction expressly required by the Bidding Documents; and (3) Bidder's safety precautions and programs;
 - F. Agree at the time of submitting its Bid that no further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of its Bid for performance of the Work at the price(s) bid and within the times required, and in accordance with the other terms and conditions of the Bidding Documents;
 - G. Become aware of the general nature of the work to be performed by Owner and others at the Site that relates to the Work as indicated in the Bidding Documents;

- H. Promptly give Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Bidder discovers in the Bidding Documents and confirm that the written resolution thereof by Engineer is acceptable to Bidder; and
- I. Determine that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work.
- J. The site shall be inspected only in the company of an authorized representative of the Owner with appointments made through the Owner's project representative. The representative's contact information for this project is Dan Williams, dan.williams@raleighnc.gov.

4.09 The submission of a Bid will constitute an incontrovertible representation by Bidder that Bidder has complied with every requirement of this Article 4, that without exception the Bid is premised upon performing and furnishing the Work required by the Bidding Documents and applying any specific sequences of construction that may be shown or indicated or expressly required by the Bidding Documents, that Bidder has given Engineer written notice of all conflicts, errors, ambiguities, and discrepancies that Bidder has discovered in the Bidding Documents and the written resolutions thereof by Engineer are acceptable to Bidder, and that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the Work.

ARTICLE 5 – PRE-BID CONFERENCE

5.01 A mandatory Pre-Bid Conference will be held at 10:00 am, Monday, March 16, 2026 at the Neuse River Resource Recovery Facility Administration Building, 8500 Battle Bridge Road, Raleigh, NC 27610. Representatives of Owner and Engineer will be present to discuss the Project. Bidders are required to attend and participate in the conference. Engineer will transmit to all prospective Bidders of record such Addenda as Engineer considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be binding or legally effective.

ARTICLE 6 – SITE AND OTHER AREAS

6.01 The Site is identified in the Bidding Documents. Easements for permanent structures or permanent changes in existing facilities are to be obtained and paid for by Owner unless otherwise provided in the Bidding Documents. The Owner has obtained the temporary easements shown for construction and limited staging and laydown area as indicated on the Drawings; however, all additional lands and access thereto required for temporary construction facilities, construction equipment, or storage of materials and equipment to be incorporated in the Work are to be obtained and paid for by Contractor with agreements being in writing and a copy of the agreement provided to the City. All permits, regulatory approvals and fees associated with obtaining the additional area shall be the full responsibility of the Contractor.

ARTICLE 7 – INTERPRETATIONS AND ADDENDA

7.01 All questions about the meaning or intent of the Bidding Documents are to be submitted to Engineer in writing only. Interpretations or clarifications considered necessary by Engineer, in response to such questions, will be issued by Addenda to all plan holders registered with the Issuing Office. Questions received less than 7 working days prior to the date for opening of Bids may not be answered. Only questions answered by Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect. Owner's email address is dan.williams@raleighnc.gov.

- 7.02 Addenda may be issued to clarify, correct, or change the Bidding Documents as deemed advisable by Owner or Engineer.
- 7.03 Submittal with questions shall include the project name, City Bid Number, the person's name submitting the question, firm, telephone number, and email address.
- 7.04 Addenda, when issued, will be on file at the offices of the Owner and Engineer and the NC Interactive Purchasing System (IPS) at least 24 hours before Bids are opened. It shall be the Bidder's responsibility to make inquiry as to the Addenda issued. All such Addenda shall become part of the Contract Documents and all Bidders shall be bound by such Addenda, whether or not received by the Bidders.

ARTICLE 8 – BID SECURITY

- 8.01 A Bid must be accompanied by Bid security made payable to Owner in an amount of 5 percent of Bidder's maximum Bid price (determined by adding the base bid and all alternatives) and in the form of a certified check, bank money order, or a Bid Bond (on the form attached) issued by a surety meeting the requirements of Paragraphs 6.01 of the General Conditions.
- 8.02 The Bid security of the Successful Bidder will be retained until such Bidder has executed the Contract Documents, furnished the required contract security and met the other conditions of the Notice of Award, whereupon the Bid security will be returned. If the Successful Bidder fails to execute and deliver the Contract Documents and furnish the required contract security within 15 days after the Notice of Award, Owner may consider Bidder to be in default, annul the Notice of Award, and the Bid security of that Bidder will be forfeited. Such forfeiture shall be Owner's exclusive remedy if Bidder defaults. The Bid security of other Bidders whom Owner believes to have a reasonable chance of receiving the award may be retained by Owner until the earlier of 7 days after the Effective Date of the Agreement or the end of the Bid holding period, whereupon Bid security furnished by such Bidders will be returned.
- 8.03 Bid security of other Bidders whom Owner believes do not have a reasonable chance of receiving the award will be returned within 7 days after the Bid opening.

ARTICLE 9 – CONTRACT TIMES

- 9.01 The number of days within which, or the dates by which, the Work is to be substantially completed, ready for final payment, and Milestones (if any) are set forth in Section 00520, Agreement.

ARTICLE 10 – LIQUIDATED DAMAGES

- 10.01 Provisions for liquidated damages, if any, are set forth in Section 00520, Agreement.

ARTICLE 11 – “OR-EQUAL” ITEMS

- 11.01 The Contract, if awarded, will be on the basis of materials and equipment specified or described in the Bidding Documents, or those “or-equal” materials and equipment approved by Engineer and identified by Addendum. The materials and equipment described in the Bidding Documents establish a standard of required type, function and quality to be met by any proposed “or-equal” item. No item of material or equipment will be considered by Engineer as an “or-equal” unless written request for approval has been submitted by Bidder and has been received by Engineer within 10 days of the issuance of the Advertisement for Bids or invitation to Bidders. Each such request shall conform to the requirements of Paragraph 7.05 and 7.06 of the General Conditions

and related Supplementary Conditions. The burden of proof of the merit of the proposed item is upon Bidder. Engineer's decision of approval or disapproval of a proposed item will be final. If Engineer approves any proposed item, such approval will be set forth in an Addendum issued to all prospective Bidders. Bidders shall not rely upon approvals made in any other manner.

Applications for review of "or-equals" materials or equipment shall be by Bidders only.

- 11.02 All prices that Bidder sets forth in its Bid will be based on the presumption that the Contractor will furnish the materials and equipment specified or described in the Bidding Documents, as supplemented by Addenda. Any assumptions regarding the possibility of post-Bid approvals of "or-equal" requests are made at Bidder's sole risk.

ARTICLE 12 – SUBCONTRACTORS, SUPPLIERS AND OTHERS

- 12.01 If the Supplementary Conditions require the identity of certain Subcontractors, Suppliers, individuals, or entities to be submitted to Owner in advance of a specified date prior to the Effective Date of the Agreement, the apparent Successful Bidder, and any other Bidder so requested, shall within five days after Bid opening submit to Owner a list of all such Subcontractors, Suppliers, individuals, or entities proposed for those portions of the Work for which such identification is required. Such list shall be accompanied by an experience statement with pertinent information regarding similar projects and other evidence of qualification for each such Subcontractor, Supplier, individual, or entity if requested by Owner. If Owner or Engineer, after due investigation, has reasonable objection to any proposed Subcontractor, Supplier, individual, or entity, Owner may, before the Notice of Award is given, request apparent Successful Bidder to submit a substitute, without an increase in the Bid.
- 12.02 If apparent Successful Bidder declines to make any such substitution, Owner may declare the Bid as non-responsive and award the Contract to the next lowest Bidder that proposes to use acceptable Subcontractors, Suppliers, individuals, or entities. Declining to make requested substitutions will not constitute grounds for forfeiture of the Bid security of any Bidder. Any Subcontractor, Supplier, individual, or entity so listed and against which Owner or Engineer makes no written objection prior to the giving of the Notice of Award will be deemed acceptable to Owner and Engineer subject to revocation of such acceptance after the Effective Date of the Agreement as provided in Paragraph 7.07 of the General Conditions.
- 12.03 Contractor shall not be required to employ any Subcontractor, Supplier, individual, or entity against whom Contractor has reasonable objection.
- 12.04 The Contractor shall not award work to Subcontractor(s) in excess of the limits stated in Supplementary Conditions 7.07.

ARTICLE 13 – PREPARATION OF BID

- 13.01 The Bid Form is included with the Bidding Documents. Additional copies may be obtained from the Issuing Office. To bid the project the Bidder should be registered with the Issuing Office.
- 13.02 All blanks on the Bid Form shall be completed in ink and the Bid Form signed in ink. Erasures or alterations shall be initialed in ink by the person signing the Bid Form. A Bid price shall be indicated for each item listed therein. In the case of optional alternatives the words "No Bid," "No Change," or "Not Applicable" may be entered. Bid forms shall not be conditional, limited, or restricted in any way.

- 13.03 A Bid by a corporation shall be executed in the corporate name by the president or a vice-president or other corporate officer accompanied by evidence of authority to sign. The corporate seal shall be affixed and attested by the secretary or an assistant secretary. The corporate address and state of incorporation shall be shown.
- 13.04 A Bid by a partnership shall be executed in the partnership name and signed by a partner (whose title must appear under the signature), accompanied by evidence of authority to sign. The official address of the partnership shall be shown.
- 13.05 A Bid by a limited liability company shall be executed in the name of the firm by a member and accompanied by evidence of authority to sign. The state of formation of the firm and the official address of the firm shall be shown.
- 13.06 A Bid by an individual shall show the Bidder's name and official address.
- 13.07 A Bid by a joint venture shall be executed by each joint venturer in the manner indicated on the Bid Form. The official address of the joint venture shall be shown.
- 13.08 All names shall be printed in ink below the signatures.
- 13.09 The Bid shall contain an acknowledgment of receipt of all Addenda, the numbers of which shall be filled in on the Bid Form.
- 13.10 Postal and e-mail addresses and telephone number for communications regarding the Bid shall be shown.
- 13.11 The Bid shall contain evidence of Bidder's authority and qualification to do business in the state where the Project is located. Bidder's state contractor license number, if any, shall also be shown on the Bid Form.

ARTICLE 14 – BASIS OF BID; COMPARISON OF BIDS

14.01 *Lump Sum*

- A. When the Bid Form is set up for Lump Sum bidding, Bidders shall submit a Bid on a lump sum basis as set forth in the Bid Form.
- B. When the Bid Form includes Alternate(s), Bidders shall submit a Bid on a lump sum basis for the base Bid and include a separate price for each alternate described in the Bidding Documents as provided for in the Bid Form. The price for each alternate will be the amount added to or deleted from the base Bid if Owner selects the alternate.
- C. In the comparison of Bids, alternatives will be applied in the same order of priority as listed in the Bid Form to the extent that project funds are available.

14.02 *Unit Price*

- A. Bidders shall submit a Bid on a unit price basis for each item of Work listed in the Bid schedule.
- B. The total of all estimated prices will be the sum of the products of the estimated quantity of each item and the corresponding unit price. The final quantities and Contract Price will be determined in accordance with Paragraph 13.03 of the General Conditions.

- C. Discrepancies between the multiplication of units of Work and unit prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum.
- D. When the Bid Form includes Alternate(s), Bidder shall submit a Bid on a unit price basis for the base Bid and include a separate price for each alternate described in the Bidding Documents as provided for in the Bid Form. The price for each alternate will be the amount added to or deleted from the base Bid if Owner selects the alternate.
- E. In the comparison of Bids, alternatives will be applied in the same order of priority as listed in the Bid Form to the extent that project funds are available.

14.03 Allowances

- A. When the Bid Form includes cash allowances, the Bid price shall include such amounts as the Bidder deems proper for Contractor's overhead, costs, profit, and other expenses on account of cash allowances, if any, named in the Contract Documents, in accordance with Paragraph 13.02.B of the General Conditions.

ARTICLE 15 – SUBMITTAL OF BID

- 15.01 The Owner, at the location and time indicated in the Advertisement for Bids, will receive sealed Bids. Bids received after the indicated time and date shall not be considered.
- 15.02 With each copy of the Bidding Documents, a Bidder may be furnished one separate unbound copy of the Bid Form and the Bid Bond Form. The unbound copy of the Bid Form is to be completed and submitted with the Bid security and all attachments as outlined in Article 8 of the Bid Form. The complete list of required bid documents can also be found in the attached Bidder's Checklist. The completed checklist shall be the first page of all bids submitted.
- 15.03 A Bid shall be submitted no later than the date and time prescribed and at the place indicated in the Advertisement For Bids and shall be enclosed in a plainly marked package with the Project title, City Bid Number, and project name as applicable, the name and address of Bidder, and shall be accompanied by the Bid security and other required documents. If a Bid is sent by mail or other delivery system, the sealed envelope containing the Bid shall be enclosed in a separate package plainly marked on the outside with the notation "BID ENCLOSED." A mailed Bid shall be addressed to Dan Williams, City of Raleigh, North Carolina, Raleigh Water, One Exchange Plaza, Suite 620, Raleigh, NC 27601. The Bidder shall be fully responsible for timely delivery at the location designated for receipt of the Bids.

ARTICLE 16 – MODIFICATION AND WITHDRAWAL OF BID

- 16.01 A Bid may be modified or withdrawn by an appropriate document duly executed in the same manner that a Bid must be executed and delivered to the place where Bids are to be submitted prior to the date and time for the opening of Bids. Modifications shall indicate only the amount to be added to or deducted from the Bidder's Bid amount as submitted on the Bid Form.
- 16.02 No bid may be withdrawn after the Bid opening for a period of time as indicated in the Bid Form except in accordance with the provisions of N.C. General Statutes 143-129.1.

ARTICLE 17 – OPENING OF BIDS

- 17.01 Bids will be opened at the time and place indicated in the Advertisement For Bids and, unless obviously non-responsive, read aloud publicly. An abstract of the amounts of the base Bids and major alternates, if any, will be made available to Bidders after the opening of Bids.

ARTICLE 18 – BIDS TO REMAIN SUBJECT TO ACCEPTANCE

- 18.01 All Bids will remain subject to acceptance for the period of time stated in the Bid Form, but Owner may, in its sole discretion, release any Bid and return the Bid security prior to the end of this period.

ARTICLE 19 – EVALUATION OF BIDS AND AWARD OF CONTRACT

- 19.01 Owner reserves the right to reject any or all Bids, including without limitation, nonconforming, nonresponsive, unbalanced, or conditional Bids. Owner further reserves the right to reject the Bid of any Bidder whom it finds, after reasonable inquiry and evaluation, to not be responsible. Owner also reserves the right to waive all informalities not involving price, time, or changes in the Work and to negotiate contract terms with the Successful Bidder when the lowest responsible Bid is in excess of the funds available.
- 19.02 More than one Bid for the same Work from an individual or entity under the same or different names will not be considered. Reasonable grounds for believing that any Bidder has an interest in more than one Bid for the Work may be cause for disqualification of that Bidder and the rejection of all Bids in which that Bidder has an interest.
- 19.03 In evaluating Bids, Owner will consider whether or not the Bids comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Form or prior to the Notice of Award.
- 19.04 In evaluating Bidders, Owner will consider the qualifications of Bidders and may consider the qualifications and experience of Subcontractors, Suppliers, and other individuals or entities proposed for those portions of the Work for which the identity of Subcontractors, Suppliers, and other individuals or entities must be submitted as provided in the Supplementary Conditions.
- 19.05 Owner may conduct such investigations as Owner deems necessary to establish the responsibility, qualifications, and financial ability of Bidders, proposed Subcontractors, Suppliers, individuals, or entities proposed for those portions of the Work in accordance with the Contract Documents.
- 19.06 If the Contract is to be awarded, Owner will award the Contract to the Bidder whose Bid is in the best interests of the Project.
- 19.07 In determining the lowest responsible Bidder, Owner may take into consideration the past performance of Bidder on construction contracts with particular concern given to completion times, quality of work, safety record, cooperation with other contractors, and cooperation with owner.
- 19.08 In determining the responsive Bidder, Owner shall take into consideration bidder's compliance with the requirements of G.S. 143-128.2(c). Failure of the low bidder to furnish affidavit(s) and documentation as required by the Bid Form for compliance with G.S. 143-128.2(c) may constitute a basis for disqualification of the Bid.

- 19.09 Owner reserves the right to reject Bid as non-responsible if the evidence submitted by, or investigation of, such Bidder fails to satisfy Owner that such Bidder is properly qualified to carry out the obligations of the Agreement and to complete the Work described therein.
- 19.10 Should the Owner adjudge that the apparent low Bidder is not the lowest responsible Bidder by virtue of the above information, said apparent low Bidder will be so notified and his Bid security shall be returned.
- 19.11 If the Contract is to be awarded, the Owner reserves the right to award contracts to the lowest responsive, responsible bidder in the manner described above.

ARTICLE 20 – CONTRACT SECURITY AND INSURANCE

- 20.01 Article 6 of the General Conditions, as may be modified by the Supplementary Conditions, sets forth Owner's requirements as to performance and payment bonds and insurance. When the Successful Bidder delivers the executed Agreement to Owner, it shall be accompanied by such bonds.

ARTICLE 21 – SIGNING OF AGREEMENT

- 21.01 When Owner issues a Notice of Award to the Successful Bidder, it shall be accompanied by the required number of unsigned counterparts of the Agreement along with the other Contract Documents which are identified in the Agreement as attached thereto. Within 15 consecutive calendar days thereafter, Successful Bidder shall sign and deliver the required number of counterparts of the Agreement and attached documents to Owner. Within 90 consecutive calendar days thereafter, Owner shall deliver one fully signed counterpart to Successful Bidder with a complete set of the Drawings with appropriate identification.
- 21.02 In case of failure of Owner to execute the Agreement in the appropriate time, Bidder shall have the right to withdraw bid.
- 21.03 In case of failure of Bidder to execute the Agreement, Owner may at his option consider the Bidder in default, in which case Bid security accompanying Bid shall be retained by the Owner.
- 21.04 Applicable laws, ordinances, and the rules and regulations of authorities having jurisdiction over construction of the Project shall apply to the contract throughout.

ARTICLE 22 – SALES AND USE TAX

- 22.01 The Owner is exempt from sales and use taxes on materials and equipment to be incorporated in the Work. Said taxes shall not be included in the Bid. Refer to Paragraph 7.10 of the Supplementary Conditions for additional information.

END OF DOCUMENT

BIDDER'S CHECKLIST

This checklist shall be included as the first page of the submitted bidding documents. As outlined in Article 7 of the Bid Form section, the following items shall be included with the fully executed Section 00410 Bid Form:

	A.	Required Bid security in the form of a Bid Bond (EJCDC No. C-430) or Certified Check (circle type of security provided); Bid Bond shall include an executed Power of Attorney.
	B.1.	Acknowledgement of MWBE Policy
	B.2.	Identification of Certified MWBE Participation
	B.3.	Affidavit A, Listing of Good Faith Effort; or Affidavit B, Intent to Perform Contract with Own Workforce
	C.	Contractor's Certificates, Affidavit of Organization and Authority of Sworn Statement
	D.	City of Raleigh – Contractor's Poor Performance Policy
	E.	Non-Collusive Affidavit
	F.	Notice to Contractor Regarding Intrusions Beyond Project Limits
	G.	Evidence of authority to do business in the state of the Project (i.e., copy of contractor's license)
	H.	RRD Memorandum of Understanding

BID FORM

PROJECT: Neuse River Resource Recovery Facility (RRF) Roof Replacements, Filter and Blower Bldgs.

CITY BID NO.: 274-RRR

BID FROM: _____

TABLE OF CONTENTS

	Page
Article 1 – Bid Recipient	1
Article 2 – Bidder’s Acknowledgements	1
Article 3 – Bidder’s Representations	2
Article 4 – Bidder’s Certification.....	3
Article 5 – Basis of Bid.....	3
Article 6 – Time of Completion	5
Article 7 – Attachments to This Bid.....	5
Article 8 – Defined Terms	6
Article 9 – Bid Submittal	6

ARTICLE 1 – BID RECIPIENT

1.01 This Bid is submitted to:

Dan Williams
City of Raleigh, Raleigh Water
8500 Battle Bridge Road
Raleigh, North Carolina 27610

1.02 The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an Agreement with Owner in the form included in the Bidding Documents to perform all Work as specified or indicated in the Bidding Documents for the prices and within the times indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.

ARTICLE 2 – BIDDER’S ACKNOWLEDGEMENTS

2.01 Bidder accepts all of the terms and conditions of the Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. This Bid will remain subject to acceptance for 120 days after the Bid opening, or for such longer period of time that Bidder may agree to in writing upon request of Owner.

ARTICLE 3 – BIDDER’S REPRESENTATIONS

3.01 In submitting this bid, bidder represents that:

- A. Bidder has examined and carefully studied the Bidding Documents, other related data identified in the Bidding Documents, and the following Addenda, receipt of which is hereby acknowledged:

No. _____, dated _____

No. _____, dated _____

No. _____, dated _____

No. _____, dated _____

No. _____, dated _____

- B. Bidder has visited the Site and become familiar with and is satisfied as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work.
- C. Bidder is familiar with and is satisfied as to all Laws and Regulations that may affect cost, progress, and performance of the Work.
- D. Bidder has carefully studied all: (1) reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities) that have been identified in Supplemental Conditions - 5.02 as containing reliable Technical Data, and (2) reports and drawings of Hazardous Environmental Conditions, if any, at the Site that have been identified in SC-5.06 as containing reliable Technical Data.
- E. Bidder has considered the information known to Bidder; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Bidding Documents; and the Site-related reports and drawings identified in the Bidding Documents, with respect to the effect of such information, observations, and documents on (1) the cost, progress, and performance of the Work; (2) the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including applying the specific sequences of construction expressly required by the Bidding Documents; and (3) Bidder’s safety precautions and programs.
- F. Based on the information and observations referred to in Paragraph 3.01.E above, Bidder does not consider that further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of this Bid for performance of the Work at the price(s) bid and within the times required, and in accordance with the other terms and conditions of the Bidding Documents.
- G. Bidder is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Bidding Documents.
- H. Bidder has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Bidder has discovered in the Bidding Documents, and the written resolution thereof by Engineer is acceptable to Bidder.
- I. The Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work for which this Bid is submitted.

ARTICLE 4 – BIDDER’S CERTIFICATION

4.01 Bidder certifies that:

- A. This Bid is genuine and not made in the interest of or on behalf of any undisclosed individual or entity and is not submitted in conformity with any collusive agreement or rules of any group, association, organization, or corporation;
1. Bidder has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid;
 2. Bidder has not solicited or induced any individual or entity to refrain from bidding; and
 3. Bidder has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for the Contract. For the purposes of this Paragraph 4.01.A:
 - a. “corrupt practice” means the offering, giving, receiving, or soliciting of any thing of value likely to influence the action of a public official in the bidding process;
 - b. “fraudulent practice” means an intentional misrepresentation of facts made (a) to influence the bidding process to the detriment of Owner, (b) to establish bid prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;
 - c. “collusive practice” means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish bid prices at artificial, non-competitive levels; and
 - d. coercive practice” means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the execution of the Contract.

ARTICLE 5 – BASIS OF BID

5.01 Bidder will complete the Work in accordance with the Contract Documents for the following price(s):

A. For all Work, a Lump Sum for the following Work Items:

1. Filter Building #1	\$
2. Blower Building	\$
The Total Contract for the Lump Sum Price of:	\$
\$ _____ Dollars	

- 5.02 Bidders are hereby notified that GS 143-128(d), requires all bidders on single prime projects to identify on their Bid form the contractors they have selected for the subdivisions for branches of work for (1) HVAC, (2) Plumbing, (3) Electrical, and (4) General. Accordingly, bidder shall list below applicable selected contractors for the following branches of work (write “N/A” if not applicable or self-performed).

HVAC	_____	_____
	Name	License No.
Plumbing	_____	_____
	Name	License No.
Electrical	_____	_____
	Name	License No.
General	_____	_____
	Name	License No.

- A. Bidder acknowledges that the rights of the Owner and the recommendations of the Engineer are not to be questioned in the Award of Contracts.
- B. Bidder acknowledges that it is the intention of the Mayor and City Council to let contracts on a basis of the Bids received in accordance with GS 143-129 and in such manner as they deem to be for the best interests of the Owner.
- C. Bidder acknowledges that the Owner reserves the right to accept or reject any or all bids and to waive any informalities in the bidding.
- D. Bidder acknowledges that should the total bid exceed the funds available to construct the project, the Owner reserves the right to reduce the scope of work from the project by deleting certain lump sum or unit price bid items prior to awarding the contract to bring the project within the funds available.
- E. Bidder acknowledges that if this contract is awarded, Bidder must, with every pay request, furnish to the Public Utilities Director of the City of Raleigh an accurate itemized statement of North Carolina Sales Taxes paid on materials, supplies, equipment, and other items charged to this contract, and otherwise fully comply with the "Procedure for Reporting North Carolina Sales Tax Expenditures.". A sales tax form must be submitted even if there is no sales tax incurred.
- F. Bidder agrees to begin work within 10 days from the date of the Notice to Proceed.
- G. Bidder agrees that should the Owner reduce the scope of work by 25% or less of the Total Bid price prior to award of the contract, the lump sum and the unit price on all bid items shall remain unchanged.
- H. Bidder agrees that in the case of failure on his part to execute the said Contract and the Bonds within 15 consecutive calendar days after written notice being given of the award of the Contract, the check, cash or Bid Bond accompanying this Bid shall be paid into the funds of the Owner's Account set aside for this Project, as liquidated damages for such failure; otherwise the check, cash or Bid Bond accompanying this Bid shall be returned to the Bidder.
- I. Bidder agrees to provide all necessary tools, machinery, equipment, apparatus, and all other means necessary to do all the work and will furnish all labor, materials and all else required to complete such Contract as may be entered into, in the manner prescribed in and in accordance with the terms of the Specifications and Contract and in accordance with the true intent and meaning thereof, and in accordance with the Plans and/or Drawings and the requirements of the Engineers under them, in a first class manner.

ARTICLE 6 – TIME OF COMPLETION

- 6.01 Bidder agrees that the Work will be substantially complete within 180 calendar days after the date when the Contract Times commence to run as provided in Paragraph 4.01 of the General Conditions, and will be completed and ready for final payment in accordance with Paragraph 15.06.B of the General Conditions within [210] calendar days after the date when the Contract Times commence to run.
- 6.02 Bidder accepts the provisions of the Agreement as to liquidated damages in the event of failure to complete the Work within the Contract Times. This amount is agreed upon as the proper measure of liquidated damages the Owner will sustain, per day, by the failure of the undersigned to complete the work, within the stipulated time, and it is not to be construed, in any sense, as a penalty.

ARTICLE 7 – ATTACHMENTS TO THIS BID

- 7.01 The following documents are submitted with and made a condition of this Bid:
- A. Required Bid security in the form of a Bid Bond or Certified Check (Section 00430);
 - B. In accordance with GS 143-128.2(c), Bidder shall identify on its bid the minority businesses that it will use on the project and the total dollar value of the bid that will be performed by the minority businesses and list the good faith efforts (Affidavit A) made to solicit participation. A Bidder that will perform all of the work with its own workforce may submit an Affidavit B to that effect in lieu of the affidavit A required above.
 - 1. Nondiscrimination Agreement (Section 00440);
 - 2. Use of MWBE Businesses (Section 00440);
 - 3. Identification of Minority Business Participation (Section 00440), and;
 - 4. Affidavit A, Listing of Good Faith Effort, or Affidavit B, Intent to Perform Contract with Own Workforce (Section 00440).
 - C. Contractor's Certificates, Affidavit of Organization and Authority of Sworn Statement (Section 00441);
 - D. City of Raleigh – Contractor's Poor Performance Policy (Section 00442);
 - E. Non-Collusive Affidavit (Section 00443);
 - F. Notice to Contractor Regarding Intrusions Beyond Project Limits (Section 00444);
 - G. Evidence of authority to do business in the state of the Project (i.e., copy of contractor's license);
- 7.02 Submit the Bidder's Checklist as provided in the bidding documents with the bid submittal. The Checklist shall be completed and included as the first page of the submittal.
- 7.03 After the bid opening the Owner will consider all bids and alternates and determine the lowest responsible, responsive bidder. Upon notification of being the apparent low Bidder, the Bidder shall then file within 72 hours of the notification of being the apparent lowest bidder, the following:
- A. An Affidavit (C) that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the goal established by the Owner and indicated in the Instruction to Bidders, paragraph Minority Participation Goals. This affidavit shall give rise to the presumption that the bidder has made the required good faith effort; or,

- B. Affidavit (D) of its good faith effort to meet the goal. The document must include evidence of all good faith efforts that were implemented, including any advertisements, solicitations and other specific actions demonstrating recruitment and selection of minority businesses for participation in the contract.

7.04 Bidder understands that if this Bid is accepted by the Owner, Bidder shall not substitute for the subcontractors named in the Bid Documents except as allowed in the Supplementary Conditions.

ARTICLE 8 – DEFINED TERMS

8.01 The terms used in this Bid with initial capital letters have the meanings stated in the Instructions to Bidders, the General Conditions, and the Supplementary Conditions.

ARTICLE 9 – BID SUBMITTAL

9.01 Bidder's License

- A. Number: _____
- B. Classification: _____
- C. Limitation: _____
- D. Employer's Tax ID No.: _____
- E. Business Address: _____
- F. Phone No.: _____ Fax No.: _____
- G. Contact Person: _____ E-mail Address: _____
- H. Phone No. w/ Ext.: _____

9.02 This Bid is submitted by:

If Bidder is:

An Individual

Name (typed or printed): _____

By: _____

(Individual's signature)

Doing business as: _____

A Partnership

Partnership Name: _____

The Organization and Internal Affairs of the Partnership are governed by the laws of the State of: _____

By: _____

(Signature of general partner -- attach evidence of authority to sign)

Name (typed or printed): _____

Title (typed or printed): _____

Attest: _____

(Signature of Corporate Secretary)

A Corporation

Corporation Name: _____ (SEAL)

State of Incorporation: _____

Type (General Business, Professional, Service, Limited Liability): _____

By: _____

(Signature -- attach evidence of authority to sign)

Name (typed or printed): _____

Title (typed or printed): _____

(CORPORATE SEAL)

Attest: _____

(Signature of Corporate Secretary)

Date of Qualification to do business in North Carolina is ____/____/____.

Limited Liability Company - LLC

Name of LLC: _____

Name of State under whose Laws the Limited Liability Company was formed:

By: _____

(Signature of Manager)

Name (typed or printed): _____

Title (typed or printed): _____

BID BOND (PENAL SUM FORM)

Bidder Name: Address <i>(principal place of business)</i> :	Surety Name: Address <i>(principal place of business)</i> :
Owner Name: City of Raleigh Address <i>(principal place of business)</i> : 222 W. Hargett Street Raleigh, NC 27601	Bid Project: Neuse River RRF Roof Replacements, Filter & Blower Buildings Bid Due Date:
Bond Penal Sum: Date of Bond:	
Surety and Bidder, intending to be legally bound hereby, subject to the terms set forth in this Bid Bond, do each cause this Bid Bond to be duly executed by an authorized officer, agent, or representative.	
Bidder	Surety
_____ <i>(Full formal name of Bidder)</i>	_____ <i>(Full formal name of Surety) (corporate seal)</i>
By: _____ <i>(Signature)</i>	By: _____ <i>(Signature) (Attach Power of Attorney)</i>
Name: _____ <i>(Printed or typed)</i>	Name: _____ <i>(Printed or typed)</i>
Title: _____	Title: _____
Attest: _____ <i>(Signature)</i>	Attest: _____ <i>(Signature)</i>
Name: _____ <i>(Printed or typed)</i>	Name: _____ <i>(Printed or typed)</i>
Title: _____	Title: _____
<i>Notes: (1) Note: Addresses are to be used for giving any required notice. (2) Provide execution by any additional parties, such as joint venturers, if necessary.</i>	

1. Bidder and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to pay to Owner upon default of Bidder the penal sum set forth on the face of this Bond. Payment of the penal sum is the extent of Bidder's and Surety's liability. Recovery of such penal sum under the terms of this Bond will be Owner's sole and exclusive remedy upon default of Bidder.
2. Default of Bidder occurs upon the failure of Bidder to deliver within the time required by the Bidding Documents (or any extension thereof agreed to in writing by Owner) the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents.
3. This obligation will be null and void if:
 - 3.1. Owner accepts Bidder's Bid and Bidder delivers within the time required by the Bidding Documents (or any extension thereof agreed to in writing by Owner) the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents, or
 - 3.2. All Bids are rejected by Owner, or
 - 3.3. Owner fails to issue a Notice of Award to Bidder within the time specified in the Bidding Documents (or any extension thereof agreed to in writing by Bidder and, if applicable, consented to by Surety when required by Paragraph 5 hereof).
4. Payment under this Bond will be due and payable upon default of Bidder and within 30 calendar days after receipt by Bidder and Surety of written notice of default from Owner, which notice will be given with reasonable promptness, identifying this Bond and the Project and including a statement of the amount due.
5. Surety waives notice of any and all defenses based on or arising out of any time extension to issue Notice of Award agreed to in writing by Owner and Bidder, provided that the total time for issuing Notice of Award including extensions does not in the aggregate exceed 120 days from the Bid due date without Surety's written consent.
6. No suit or action will be commenced under this Bond prior to 30 calendar days after the notice of default required in Paragraph 4 above is received by Bidder and Surety, and in no case later than one year after the Bid due date.
7. Any suit or action under this Bond will be commenced only in a court of competent jurisdiction located in the state in which the Project is located.
8. Notices required hereunder must be in writing and sent to Bidder and Surety at their respective addresses shown on the face of this Bond. Such notices may be sent by personal delivery, commercial courier, or by United States Postal Service registered or certified mail, return receipt requested, postage pre-paid, and will be deemed to be effective upon receipt by the party concerned.
9. Surety shall cause to be attached to this Bond a current and effective Power of Attorney evidencing the authority of the officer, agent, or representative who executed this Bond on behalf of Surety to execute, seal, and deliver such Bond and bind the Surety thereby.
10. This Bond is intended to conform to all applicable statutory requirements. Any applicable requirement of any applicable statute that has been omitted from this Bond will be deemed to be included herein as if set forth at length. If any provision of this Bond conflicts with any applicable statute, then the provision of said statute governs and the remainder of this Bond that is not in conflict therewith continues in full force and effect.
11. The term "Bid" as used herein includes a Bid, offer, or proposal as applicable.

INFORMATION FOR BIDDERS REGARDING COMPLIANCE WITH THE CITY OF RALEIGH'S MINORITY AND WOMEN-OWNED BUSINESS ENTERPRISE (MWBE) PROGRAM

Policy

In accordance with North Carolina law, the City of Raleigh encourages and provides an equal opportunity for Certified Minority and Women-Owned Business Enterprises (MWBE) to participate in all aspects of the City's contracting and procurement programs.¹ The prime contractor or a first-tier subcontractor on a construction manager at risk (CMAR) project (collectively, "Bidder") shall be required to identify participation of MWBE businesses in its proposal, and document how that participation will be achieved. Bidders are subject to the City's MWBE subcontracting requirements (including good faith efforts as applicable), regardless if a Bidder is itself a Certified MWBE.²

The City has an aspirational goal of 15% of the total contract amount to be performed by MWBE businesses in contracts awarded by the City for: (i) construction and building projects of \$300,000 or more; and (ii) construction and building projects of \$100,000 or more that have any state funding.

Definitions

Certified Minority Business (MWBE)

A business which:

- a. At least fifty-one percent (51%) is owned by one or more Minority Persons or Socially and Economically Disadvantaged Individuals; or in the case of a corporation, in which at least fifty-one percent (51%) of the stock is owned by one or more Minority Persons or Socially and Economically Disadvantaged Individuals;
- b. The management and daily business operations are controlled by one or more Minority Persons or Socially and Economically Disadvantaged Individuals; and
- c. Is certified in one of the MWBE categories as defined by the NC Department of Administration/Historically Underutilized Business (HUB) and the NC Department of Transportation/Disadvantaged Business Enterprise (DBE).

Minority Person

A person who is a citizen or lawful permanent resident of the United States and who is:

- a. Black, that is, a person having origins in any of the black racial groups in Africa;
- b. Hispanic, that is, a person of Spanish or Portuguese culture with origins in Mexico, South or Central America, or the Caribbean Islands, regardless of race;
- c. Asian American, that is, a person having origins in any of the original peoples of the Far East, Southeast Asia, Asia, the Indian subcontinent, or the Pacific Islands;
- d. American Indian, that is, a person having origins in any of the original peoples of North America; or
- e. Non-minority Female.

Socially and Economically Disadvantaged Individual

Socially disadvantaged individuals are those who have been subjected to racial or ethnic prejudice or cultural bias because of their identity as a member of a group without regard to their individual qualities. Economically disadvantaged individuals are those socially disadvantaged individuals whose ability to compete in the free enterprise system has been impaired due to diminished capital and credit opportunities as compared to others in the same business area who are not socially disadvantaged.³

¹ See, N.C.G.S. §§ 143-128.2, 143-128.4, 143-129, and 143-131.

² See, City of Raleigh SOP 505-2.

³ See, 15 U.S.C. 637.

Bidder Responsibilities

Bidders agree to comply with all the terms and conditions of the City of Raleigh's Minority and Women-Owned Business Enterprise (MWBE) Program. Bidders must use good faith efforts (if applicable) to meet participation goals through the award of subcontracts to certified MWBE businesses consistent with City policy and North Carolina law.

Pre-Bid Opening

The City's Solicitation Documents include forms that: (a) capture information about MWBEs and any other subcontractors or suppliers that a Bidder intends to use on a contract ("Identification of MWBE Participation") and (b) affidavits to be completed by the Bidder.

Identification of MWBE Participation

The "Identification of MWBE Participation" must be completed by the Bidder on the City's form and submitted with its bid. If the project work is to be self-performed by the Bidder, the Bidder must so designate by checking the appropriate box on the form. For all Bidders which will not be self-performing the project work, the "Identification of MWBE Participation" form must be completed in its entirety. The Bidder must list on the City's form all MWBE businesses which will be construction subcontractors, vendors, or suppliers (collectively, "Subcontractors") on the project, and the total dollar value of its bid that will be performed by MWBEs. The failure to complete the "Identification of MWBE Participation" form in its entirety, or the failure to submit a completed "Identification of MWBE Participation" form with its bid, will render the bid non-responsive and the Bidder's bid will not be considered for award. The City will only credit MWBE participation for those Subcontractors listed on the "Identification of MWBE Participation" form.

Affidavit A: Listing of Good Faith Efforts

If the Bidder intends to subcontract any portion of the project work on a contract, an Affidavit A must be properly executed and submitted with its bid, listing the good faith efforts the Bidder made to achieve MWBE subcontracting goals for the contract prior to submitting its bid. The Affidavit A must be completed using the City's form. A minimum of fifty (50) good faith efforts points is required, the failure to achieve at least 50 points is grounds for rejection of a bid.

Affidavit B: Intent to Perform Contract with Own Workforce

In lieu of an Affidavit A, a Bidder that intends to perform 100% of the project work on a contract with its own current workforce may submit an Affidavit B with its bid. In submitting an Affidavit B, a Bidder certifies that the Bidder does not customarily subcontract elements of this type of project, and normally performs, has the capability to perform, and will perform all elements of the project work on the contract with its own current workforce. The Affidavit B must be completed using the City's form.

The failure to submit a properly executed Affidavit A or Affidavit B with a bid will render the bid non-responsive and the bid will not be considered for award.

Bid Opening

At the project bid opening, the total MWBE participation for each bid will be recorded. Upon being named the apparent low bidder, the Bidder must comply with the following:

- a. If the Bidder submitted an Affidavit B with its bid indicating its intent to perform 100% of the project work on the contract with its own current workforce, then the Bidder is not required to resubmit its Affidavit B or to submit any additional affidavits (i.e., Affidavit C or Affidavit D). The City, in its discretion, may request that the Bidder submit additional information or documentation, including, but not limited to, information relating to the Bidder's subcontracting history and its ability to perform all elements of the project work on the contract with its own current workforce.

- b. If the Bidder submitted an Affidavit A with its bid and the amount of MWBE participation as a percentage of the total contract price meets or exceeds the applicable goal, then the Bidder must submit to the City an Affidavit C within three (3) business days after being notified by City Staff that it is the apparent low bidder. The Bidder must complete the Affidavit C in its entirety using the City's form.
- c. If the Bidder submitted an Affidavit A with its bid and the amount of MWBE participation as a percentage of the total contract price does not meet the applicable goal, then the Bidder must submit an Affidavit D to the City within three (3) business days after being notified by City Staff that it is the apparent low bidder. The Bidder must complete Affidavit D in its entirety on the City's form. In conjunction with the Affidavit D, the Bidder must include supplemental documentation of the good faith efforts made to meet the applicable goal. The City, in its discretion, may request that the Bidder submit additional information or documentation, including, but not limited to, information or documentation relating to any good faith efforts claimed by the Bidder, and completion of the City's Good Faith Negotiation Form and Solicitation Form. Good faith efforts can be demonstrated using, among other factors, the following:
 - i. Attending pre-solicitation or pre-bid meetings that are scheduled by the City to inform MWBE firms of contracting, subcontracting, and supply opportunities.
 - ii. Advertising in general circulation, trade association, or minority-focus media concerning subcontracting opportunities.
 - iii. Providing written notice, to a reasonable number of specific MWBE firms that their interest in the contract is being solicited, at least 10 days before bids are due, to allow MWBE firms time to participate.
 - iv. Following up initial solicitation of interest by contacting MWBE firms to determine with certainty whether the MWBE firms are interested.
 - v. Identifying and selecting portions of the work to be performed by MWBE firms in order to increase the likelihood of MWBE participation (including where appropriate, breaking down contracts into economically feasible units to facilitate MWBE participation).
 - vi. Providing interested MWBE firms with equal access to plans, specifications, and requirements of the contract.
 - vii. Negotiating fairly with interested MWBE firms, not rejecting MWBE firms as unqualified without sound reasons based on a thorough investigation of their capabilities.
 - viii. Using the services of the City's MWBE office; available minority community organizations; minority contractors' groups; local, state, and federal minority business offices; and other organizations that provide assistance in the recruitment and placement of MWBE firms.
 - ix. Assisting interested MWBE firms in need of equipment, loan capital, lines of credit or joint pay agreements to secure loans, supplies or letters of credit, including waiving credit that is ordinarily required.
 - x. Assisting interested MWBE firms in obtaining bonding, insurance, or providing alternatives to bonding or insurance for Subcontractors.
 - xi. Negotiating joint venture and partnership arrangements with minority businesses to increase the opportunities for minority participation when possible.
 - xii. Provide for quick pay agreements and policies to enable minority contractors and suppliers to meet cash flow demands.

For each unmet MWBE participation goal, for which an Affidavit D is submitted, a Bidder must earn at least fifty (50) good faith efforts points. The failure to achieve at least fifty (50) points is grounds for rejection of a bid. All

actions necessary to earn good faith efforts points must occur prior to bid opening. In determining whether a Bidder has made good faith efforts, the City will evaluate the efforts made by the Bidder and will determine compliance with regard to quantity, intensity, and results of these efforts prior to recommendation of award.

Post-Award

Payment

For purposes of this section the word "Contractor" means both the prime contractor and the CMAR for CMAR projects. The Contractor must submit a completed **Payment Affidavit - Subcontractor / Supplier Utilization Form** with each payment application, including periodic payments and final payment. Payment applications will not be processed by the City until a completed Payment Affidavit – Subcontractor/ Supplier Utilization Form is submitted. Within seven (7) days of receipt by the Contractor of a periodic or final payment from the City, the Contractor must pay each first-tier Subcontractor based on work completed or services provided under each subcontract. If the Contractor has made a quick pay commitment with any MWBE Subcontractor, they must comply with the provisions of their quick pay commitment.

Changing a Certified MWBE Subcontractor

If the situation arises that it becomes necessary to terminate, replace, or reduce the work of a MWBE Subcontractor counted toward a committed MWBE subcontracting goal, the Contractor must submit a completed **Request to Change MWBE Subcontractor** form to the applicable department project manager and the City's MWBE Program Manager. Any change in the work of a MWBE Subcontractor, including its termination and/or replacement, must first be approved by the City based upon good cause shown. Any further explanation or detail to the City in addition to what is identified in the Request to Change MWBE Subcontractor form must be on company letterhead. Good faith efforts shall apply to the selection of any substitute Subcontractor.

ACKNOWLEDGMENT OF MWBE POLICY
[PURSUANT TO N.C.G.S. § 143-128.2]

The City's policy is to encourage bidders in the participation of MWBE businesses. A presentation of that policy has been made at the pre-bid or pre-proposal conference. By submission of a bid or proposal in response to this solicitation, the Bidder consents to all the terms and conditions of the City of Raleigh Minority and Women-Owned Business Enterprise (MWBE) Policy. A copy of the policy may be provided upon request by the Business Engagement & Opportunities Division, or online at www.raleighnc.gov.

Bidder recognizes that the City of Raleigh encourages and provides equal opportunity for MWBE businesses to participate in all aspects of the City's contracting and procurement. The City's MWBE participation aspirational goal is at least fifteen percent (15%) of the total contract amount to MWBEs on construction projects of \$300,000 or more and building related contracts of \$100,000 or more that include any State funding. The Bidder on the subject Contract/Proposal must document good faith efforts to provide meaningful participation by MWBEs in the performance of the Contract. Bidder agrees that the City may reject a bid for MWBE Policy violations, including but not limited to, providing inaccurate information or for failure to provide required MWBE documentation.

The Prime Contractor will be required to identify participation of MWBE businesses and how that participation will be achieved. Bidder must identify anticipated subcontractors, including any Minority & Women-Owned Businesses, intended to be used. Bidder further agrees, if awarded a Contract, it will, upon request, submit to the City, the proper affidavit identifying the workforce actually utilized on the Contract. All MWBE related bid documents have been provided to the Bidder. MWBE information provided by the Bidder is subject to the NC Public Records Act. Bidder acknowledges that the City must be notified of any change of subcontractors, suppliers, or subconsultants.

To the extent permitted by North Carolina law, the Bidder for themselves, their agents, officials, directors, officers, members, representatives, employees, and contractors agree not to discriminate in any manner or in any form based on actual or perceived age, mental or physical disability, sex, religion, creed, race, color, sexual orientation, gender identity or expression, familial or marital status, economic status, veteran status or national origin in connection with this Contract/Proposal or its performance. The Bidder agrees to conform with the provisions and intent of Raleigh City Code §4-1004 in all matters related to this Contract/Proposal. This provision is incorporated herein for the benefit of the City of Raleigh and its residents and may be enforced by an action for specific performance, injunctive relief, or any other remedy available at law or equity. This section shall be binding on the successors and assigns of all parties with reference to the subject matter of the Contract/Proposal.

I have read and understand the City of Raleigh's MWBE policy.

Signature

Printed Name and Title

Company

Date

IDENTIFICATION OF MWBE PARTICIPATION

Formal Contracts & Construction Contracts Equal or Exceeding \$300,000

This Identification of MWBE Participation Form is for the purpose of capturing information regarding the utilization of MWBEs and other subcontractors and suppliers on Formally Bid City Contracts and Construction Contracts equal or exceeding \$300,000. MWBE participation is encouraged for all City of Raleigh contracting opportunities. Please refer to the City's MWBE Policy for any contract specific requirements.

Copy this Form as needed.

BIDDER NAME			
PROJECT NAME			
PROJECT NUMBER		CITY DEPARTMENT	
CONTRACT TYPE	☐ Construction ☐ Services ☐ Other _____ *		
☐ PRIME IS MWBE	Classification: _____ ☐ Certified with NCHUB ☐ Certified with NCDOT-DBE	BID SUBMITTAL DATE	

MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

*For Professional Services Contracts, please use the Identification of MWBE Participation for Professional Services Form

☐ WORK TO BE SELF-PERFORMED

Check this box only if you intend to perform 100% of the work on this Project/Contract with your own current work forces, and you normally perform and have the capability to perform all elements of this work on this Project/Contract with your own current work forces.

MWBE SUBCONTRACTORS

Complete the chart below for all MWBE subcontractors that you intend to use on this Project/Contract regardless of dollar amount.

Company Name	MWBE Classification	Description of Services	Percentage of Total Contract*	Total Projected Utilization (\$)*

MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

*If the proposal is subject to an RFQ process, you may enter "N/A".

Total Estimated MWBE Utilization*

\$ _____

Total Proposal Amount*

\$ _____

Percent Estimated MWBE Utilization*

_____ %

(Total Estimated MWBE Utilization divided by Total Bid Amount)

*If the proposal is subject to an RFQ process, you may enter "N/A".

AFFIDAVIT A
Listing of Good Faith Efforts (GFE)

Affidavit of _____
(Name of Bidder)

Project Name			
Project Number			
Total Project Bid		Bid Submittal Date	

Total Available GFE Points: 155		Minimum Number GFE Points Required: 50	
POINTS	GOOD FAITH EFFORT (GFE)		
☐	10	Contacted MWBE businesses that reasonably could have been expected to submit a quote and that were known to the contractor or available on State or local government-maintained lists, at least 10 days before the bid date and notified them of the nature and scope of the work to be performed.	
☐	10	Made construction plans, specifications and requirements available for review by prospective MWBE businesses or provided these documents at least 10 days before bids are due.	
☐	15	Broken down or combined elements of work into economically feasible units to facilitate MWBE business participation.	
☐	10	Worked with MWBE businesses trade, community, or contractor organizations identified by the MWBE Office and included in the bid documents that provide assistance in recruitment of MWBE businesses.	
☐	10	Attended pre-bid meetings schedule by the public owner.	
☐	20	Provided assistance in getting required bonding or insurance or provided alternatives to bonding or insurance for subcontractors.	
☐	15	Negotiated in good faith with interested MWBE businesses and did not reject them as unqualified without sound reasons based on their capabilities. Any rejection of a MWBE business based on lack of qualification should have the reasons documented in writing.	
☐	25	Provided assistance to MWBE businesses in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisted MWBE businesses in obtaining the same unit pricing with the bidder's suppliers in order to help MWBE businesses in establishing credit.	
☐	20	Negotiated joint venture and partnership arrangements with MWBE businesses in order to increase opportunities for MWBE businesses participation on a public construction or repair project when possible.	
☐	20	Provided quick pay agreements and policies to enable MWBE business contractors and suppliers to meet cash flow demands.	
Total GFE Points _____			

The undersigned certifies the preceding representation is a true and accurate statement of Good Faith Efforts made toward the participation of MWBE businesses in the performance of this Project/Contract. Failure to provide accurate and truthful information is a violation of the City of Raleigh MWBE Policy and may result in the sanctions prescribed therein.

This the ____ of _____, 20____

Signature

Printed Name/Title

AFFIDAVIT B
Intent to Perform Contract with Own Workforce

Affidavit of _____
(Name of Bidder)

Project Name			
Total Project Bid		Bid Submittal Date	
Project Number			
☐ PRIME IS MWBE	Classification: _____	☐ Certified with NCHUB ☐ Certified with NCDOT-DBE	

*MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

The Bidder hereby certifies having read and understood the City of Raleigh MWBE Policy, and affirms that it is the intent of the Bidder to **perform 100% of the work** required for the above-named Contract.

In making this certification, the Bidder states that the Bidder does not customarily subcontract elements of this type project, and normally performs and has the capability to perform and will perform **all elements of work on this project** with the Bidder's own current work forces; and

The Bidder agrees to provide any additional information or documentation requested by the City of Raleigh in support of the above statement. If additional scopes of work are added after the Bidder has been awarded the Contract, then the Bidder agrees to make a Good Faith Effort to utilize Minority and Women-Owned Business Enterprises (MWBEs), as applicable, where possible.

The undersigned hereby certifies that he or she has read this certification and is authorized to bind the Bidder to the commitments herein contained.

Date: _____ Name of Authorized Officer: _____

Signature: _____

Title: _____

State of North Carolina, County of _____

Subscribed and sworn to before me this _____ day of _____ 20__

Notary Public _____ My commission expires _____

SEAL

AFFIDAVIT C
MWBE SUBCONTRACTOR UTILIZATION COMMITMENT

This affidavit is to be provided by the Prime Contractor within three (3) business days after notification by the City of being the apparent lowest, responsible, responsive bidder (LRRB) if the portion of the work to be performed by MWBE Businesses equals or exceeds fifteen percent (15%) of the total contract price. *Copy this Form as needed.*

SECTION 1. PROJECT INFORMATION

Project Name			
Project Number		City Department	
Project Manager			
Phone Number		Email Address	
Bidder		Contact Name	
Phone Number		Email Address	
☐ PRIME IS MWBE Classification: _____ ☐ Certified with NCHUB ☐ Certified with NCDOT-DBE		Bid Submittal Date	
Prime to Perform	\$ _____	Prime to Perform	_____ %

Total Base Bid Amount \$ _____

Total Contract Amount (including Contingency) \$ _____

Total MWBE Subcontractor / Supplier Utilization \$ _____

Percent MWBE Subcontractor Utilization (Total MWBE \$ divided by Total Base Bid) _____ %

SECTION 2. MWBE SUBCONTRACTORS

Complete the chart below for all MWBE subcontractors to be used on this Project/Contract regardless of dollar amount.

Company Name	Contact Information (Name, Email, Phone)	MWBE Classification	Description of Services	Percentage of Total Contract	Total Projected Utilization (\$)

*MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

Letters of Intent Submitted Upon Notice from the City

Within three (3) Business Days after receiving a request from the City (or within such longer time as may be communicated by the City in writing), Bidders must submit a separate Letter of Intent for each MWBE listed on Affidavit C. Each Letter of Intent must be executed by both the MWBE and the Bidder. The City shall not count proposed MWBE utilization for which it has not received a Letter of Intent by this deadline.

Adding Subcontractors or Suppliers After Submitting This Form

Nothing in this Affidavit shall be deemed to preclude you from entering into subcontracting arrangements after submission of this form. However, per the City of Raleigh MWBE Policy, you must comply with the following:

- You must maintain the level of MWBE participation proposed on this Affidavit throughout the duration of the Contract, except as may be otherwise specifically allowed by the City.
- If you need to terminate or replace a MWBE, you must complete a Request to Change a MWBE Subcontractor Form.
- If the scope of work on the Contract increases, or if you elect to subcontract any portion of work not identified on this form as subcontracted, then you must comply with City of Raleigh MWBE Policy, including Good Faith Efforts.
- A Letter of Intent must also be submitted for each MWBE you add subsequent to contract award.

Signature

Your signature below indicates that the undersigned firm certifies and agrees that:

- a. You have complied with all provisions of the City of Raleigh MWBE Policy;
- b. The information provided is a true and accurate statement of MWBE businesses intended to be used as subcontractors, subconsultants, or suppliers in the performance of this Project/Contract; and
- c. Failure to provide accurate and truthful information or to properly document such compliance in the manner and within the time periods established by the City of Raleigh MWBE Policy shall constitute a violation of the City of Raleigh MWBE Policy and may result in the sanctions prescribed therein, including rejection of your bid.

This the ____ of _____, 20 ____

Signature

Printed Name/Title

AFFIDAVIT D
GOOD FAITH EFFORTS (GFE) AND STATEMENT OF GFE COMPLIANCE

This affidavit is to be provided by the Prime Contractor within three (3) business days after notification by the City of being the apparent lowest, responsible, responsive bidder (LRRB) if the Bidder has not fully met the established MWBE Goal (15%) for this Project. The Bidder must document it has met the GFE requirements by completing this Form. GFE Points will be calculated independently by the City.

SECTION 1. PROJECT INFORMATION

Project Name			
Project Number		City Department	
Project Manager			
Phone Number		Email Address	
Bidder		Contact Name	
Phone Number		Email Address	
☐ PRIME IS MWBE Classification: _____ ☐ Certified with NCHUB ☐ Certified with NCDOT-DBE		Bid Submittal Date	
Prime to Perform	\$ _____	Prime to Perform	_____ %

Total Base Bid Amount \$ _____

Total Contract Amount (including Contingency) \$ _____

Total MWBE Subcontractor / Supplier Utilization \$ _____

Percent MWBE Subcontractor Utilization (Total MWBE \$ divided by Total Base Bid) _____ %

SECTION 2. MWBE SUBCONTRACTORS

Complete the chart below for all MWBE subcontractors to be used on this Project/Contract regardless of dollar amount.

Company Name	Contact Information (Name, Email, Phone)	MWBE Classification	Description of Services	Percentage of Total Contract	Total Projected Utilization (\$)

*MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

SECTION 3. GOOD FAITH EFFORTS

Below is a list of Good Faith Efforts as defined in the City's MWBE Policy. To the left of each item is the number of points assigned to that item. Please place an "X" in the first column for each item you are claiming credit. Please provide any documentation, if available. Failure to achieve the minimum number of GFE points stated in the box below may constitute grounds for rejection of your bid.

NOTE: All actions necessary to earn GFE Points must be undertaken prior to Bid Opening.

Total Available GFE Points: 155		Minimum Number GFE Points Required: 50
POINTS	GOOD FAITH EFFORT (GFE)	
☐	10	Contacted MWBE businesses that reasonably could have been expected to submit a quote and that were known to the contractor or available on State or local government-maintained lists, at least 10 days before the bid date and notified them of the nature and scope of the work to be performed.
☐	10	Made the construction plans, specifications and requirements available for review by prospective MWBE businesses or providing these documents to them at least 10 days before the bids are due.
☐	15	Broken down or combined elements of work into economically feasible units to facilitate MWBE business participation.
☐	10	Worked with MWBE businesses trade, community, or contractor organizations identified by the MWBE Office and included in the bid documents that provide assistance in recruitment of MWBE businesses.
☐	10	Attended pre-bid meetings schedule by the public owner.
☐	20	Provided assistance in getting required bonding or insurance or provided alternatives to bonding or insurance for subcontractors.
☐	15	Negotiated in good faith with interested MWBE businesses and did not reject them as unqualified without sound reasons based on their capabilities. Any rejection of a MWBE business based on lack of qualification should have the reasons documented in writing.
☐	25	Provided assistance to MWBE businesses in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisted MWBE businesses in obtaining the same unit pricing with the bidder's suppliers in order to help MWBE businesses in establishing credit.
☐	20	Negotiated joint venture and partnership arrangements with MWBE businesses in order to increase opportunities for MWBE businesses participation on a public construction or repair project when possible.
☐	20	Provided quick pay agreements and policies to enable MWBE business contractors and suppliers to meet cash flow demands.
Total GFE Points (Claimed by Bidder) _____		Total GFE Points (Assessed by City) _____

Letters of Intent Submitted Upon Notice from the City

Within three (3) Business Days after receiving a request from the City (or within such longer time as may be communicated by the City in writing), Bidders must submit a separate Letter of Intent for each MWBE listed on this Affidavit D. Each Letter of Intent must be executed by both the MWBE and the Bidder. The City shall not count proposed MWBE utilization for which it has not received a Letter of Intent by this deadline.

Adding Subcontractors or Suppliers After Submitting This Form

Nothing in this Affidavit shall be deemed to preclude you from entering into subcontracting arrangements after submission of this form. However, per the City of Raleigh MWBE Policy, you must comply with the following:

- You must maintain the minimum level of MWBE participation proposed on this Affidavit throughout the duration of the Contract, except as may be otherwise specifically allowed by the City.
- If you need to terminate or replace a MWBE, you must complete a Request to Change a MWBE Subcontractor Form.
- If the scope of work on the Contract increases, or if you elect to subcontract any portion of work not identified on this form as subcontracted, then you must comply with City of Raleigh MWBE Policy, including Good Faith Efforts.
- A Letter of Intent must also be submitted for each MWBE you add subsequent to contract award.

Signature

Your signature below indicates that the undersigned firm certifies and agrees that:

- a. You have complied with all provisions of the City of Raleigh MWBE Policy;
- b. The information provided is a true and accurate statement of Certified MWBE businesses intended to be used as subcontractors, subconsultants, or suppliers in the performance of this Project/Contract; and
- c. Failure to provide accurate and truthful information or to properly document such compliance in the manner and within the time periods established by the City of Raleigh MWBE Policy shall constitute a violation of the City of Raleigh MWBE Policy and may result in the sanctions prescribed therein, including rejection of your bid.

This the ____ of _____, 20 ____

Signature

Printed Name/Title

Letter of Intent

In accordance with City of Raleigh MWBE Policy, within three (3) Business Days after receiving a request from the City (or within such longer time as may be communicated by the City in writing), a Bidder must submit a separate Letter of Intent for each MWBE subcontractor listed on Affidavit C or Affidavit D, as may be applicable.

Project Name	
Project Number	

Section 1: TO BE COMPLETED BY THE BIDDER

Name of Bidder					
Address					
Contact Person					
Telephone		E-mail		Fax	

If the Bidder has entered into a Quick Pay Agreement, in association with this Letter of Intent and as defined in the City's MWBE Policy, please attach a copy of the executed Agreement with the undersigned MWBE.

Identify in complete detail the scope of work to be performed or item(s) to be supplied by the MWBE.

Cost of Work to be Performed by MWBE \$ _____

Section 2: TO BE COMPLETED BY MWBE SUBCONTRACTOR

Name of MWBE					
Address					
Contact Person					
Telephone		E-mail		Fax	

Upon execution of a Prime Contract with the City for the above referenced project, the Bidder certifies that it intends to utilize the MWBE listed above, and that the description, cost and percentage of work to be performed by the MWBE as described above is accurate. The MWBE firm certifies that it has agreed to provide such work/supplies for the amount stated above.

BIDDER	_____	_____
	Signature	Date

	Print Name and Title	
MWBE	_____	_____
	Signature	Date

	Print Name and Title	

CONTRACT SUBCONTRACTOR IDENTIFICATION FORM*Building Project/Construction Contracts*(This form **MUST** be submitted within 30 days after award of the Contract)

This Final Subcontractor Identification Form is to provide a list of all subcontractors that the Contractor will use in the performance of the Contract with the City, in accordance with NCGS §143-128.2. *Copy this Form as needed.*

CONTRACTOR NAME			
PROJECT NAME			
PROJECT NUMBER		CITY DEPARTMENT	
☐ PRIME IS MWBE	Classification: _____ ☐ Certified with NCHUB ☐ Certified with NCDOT-DBE	CONTRACT AWARD DATE	

MWBE Classifications: American Indian (AI), Asian American (AA), Black/African American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

☐ **WORK TO BE SELF-PERFORMED**

Check this box **only** if you intend to perform 100% of the work on this Project/Contract with your own current work forces, and you normally perform and have the capability to perform all elements of this work on this Project/Contract with your own current work forces.

ALL CONTRACT SUBCONTRACTORS

Complete the chart below for **all** subcontractors that will be used on this Contract regardless of dollar amount.

Company Name	Contact	Description of Service/Trade	Total (\$)
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	
	Name:		
☐ Certified MWBE ☐ Registered Raleigh SCS	E-mail:	Address:	

Certification must be with NCHUB or the NCDOT-DBE. Proof of Certification may be required upon request by the City.

Total Contract Amount

\$ _____

Total MWBE Utilization

\$ _____

Percent MWBE Utilization

(Total MWBE Utilization divided by Total Contract Amount)

_____ %

APPENDIX E - CERTIFIED SUBCONTRACTOR / SUPPLIER PAYMENT APPLICATION FORM

Contractors must submit this form with each request for payment from the City of Raleigh, including any invoice or request for final payment. Requests for payment are limited to work that has been completed and approved for all subcontractors and suppliers in connection with the Contract. Copy this form as needed. The Contractor on the Prime Contract (i.e., Prime) is responsible for collecting and submitting this Appendix E from all subsequent lower tier contractors.

Section 1: PROJECT INFORMATION

Project Name		Contractor Name	
Total Contract Amount	\$	Pay App #/Contract ID #	
Total MWBE Sub (\$/%)	\$	Invoice Amount	\$
Payment Period	___/___/20___ through ___/___/20___		City Department
FINAL PAYMENT ☐ Check only when submitting Final Pay Request.		Project Completion Date	

Section 2: PAYMENTS TO SUBCONTRACTORS

Complete the chart below for all MWBE subcontractors used on the Project/Contract regardless of dollar amount.

Company Name	MWBE Classification	Work Performed	Percentage of Total Contract	Percent of Subcontract Completed	Payment this Period	Cumulative Payments to Date

*MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

Section 3: PAYMENTS TO SUPPLIERS

All suppliers providing goods under City contracts must be listed on the Sales Tax Statement submitted with each pay request. The City may request, on a case-by-case basis, that the Contractor require certain suppliers to be registered in the Raleigh Supplier Connection System and may withhold payment of any amounts due the Contractor in the event the Contractor fails to comply with such request.

The undersigned certifies the preceding chart is a true and accurate statement of all payments that have been made to subcontractors on this Project/Contract, and that all Suppliers providing goods under this contract have been listed in the Sales Tax Statements submitted to the City in connection with this Payment Appendix E. If no subcontractors or suppliers are listed on the preceding chart or Sales Tax Statements, the undersigned certifies that no subcontractors or suppliers were used in performing the Project/Contract for the payment period indicated. Failure to provide accurate and truthful information is a violation of the City of Raleigh MWBE Policy and may result in the sanctions prescribed therein.

This _____ day of _____ 20____

Signature

Print Name and Title

To be completed by City for FINAL PAYMENT

Total Paid to Contractor	\$	Proposed MWBE Amount	\$	MWBE Commitment: _____%
☐ Prime Contractor MWBE				
Total Paid to Subcontractors	\$	Total to MWBE Subcontractors	\$	MWBE Final: _____%

REQUEST TO CHANGE A MWBE SUBCONTRACTOR

Contractors must submit this form for **any request** to change any MWBE subcontractor or supplier in connection with the Contract. The Contractor on the Prime Contract (i.e. prime) is responsible for collecting and submitting this form from all subsequent lower tier contractors.

PROJECT NAME			
PROJECT MANAGER		CONTRACT NUMBER	
PRIME CONTRACTOR		CONTACT NAME	
PHONE NUMBER		E-MAIL ADDRESS	
DATE OF CHANGE		CITY DEPARTMENT	

SECTION 1: PREVIOUS REQUESTS FOR CHANGE

☐ **NO PREVIOUS REQUEST FOR THIS PROJECT/CONTRACT.**

Complete the chart below for all previous Requests to Change a MWBE Subcontractor.

Date of Request	Subcontractor's Company Name	MWBE Classification	Request Approved: Y/N	Work Performed

MWBE Classifications: American Indian (AI), Asian American (AA), Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

Section 2: CURRENT MWBE SUBCONTRACTOR INFORMATION

CURRENT MWBE SUBCONTRACTOR			
SERVICE PROVIDED			
PERCENT OF TOTAL CONTRACT	_____ %	PERCENT OF SUBCONTRACT COMPLETE	_____ %
TOTAL AMOUNT OF SUBCONTRACT	\$ _____	TOTAL AMOUNT PAID TO DATE	\$ _____

Section 3: PROPOSED ACTION (SELECT ONE)

☐ **WORK TO BE SELF-PERFORMED**

Check this box **only** if the work previously performed by the above MWBE subcontractor will be performed with your own current work forces, and you normally perform and have the capability to perform all elements of this work on this Project/Contract with your own current work forces.

☐ **REPLACE MWBE SUBCONTRACTOR**

Section 4: REASON FOR CHANGE (SELECT AT LEAST ONE)

- ☐ The listed MWBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract.
- ☐ The listed MWBE is bankrupt or insolvent.
- ☐ The listed MWBE fails or refuses to perform the subcontract or furnish the listed materials.

- ☐ The work performed by the listed subcontractor is unsatisfactory according to industry standards and is not in accordance with the plans and specifications.
- ☐ The subcontractor is substantially delaying or disrupting the progress of the work.
- ☐ Other - explain in detail on company letter head and attach to this Request.

Section 5: NEW SUBCONTRACTOR INFORMATION (IF APPLICABLE)

Complete the information below for the new MWBE subcontractor requested to be changed on the Project/Contract.

Company Name	Contact Person	MWBE Classification	Work to be Performed	Amount of Subcontract	Subcontractor's Percentage of Total Contract

MWBE Classifications: American Indian (AI), Asian American (AA,) Black/African-American (B), Hispanic (H), Non-Minority Female (NMF), Socially/Economic Disadvantaged (D)

If new subcontractor(s) is not MWBE, attach documentation of Good Faith Efforts (Affidavit A).

This the ____ of _____, 20____

Signature _____ Printed Name/Title _____

TO BE COMPLETED BY CITY

SIGNATURE:

Original Total Contract Amount: \$_____

Original Total MWBE Participation _____ %

PRINT NAME:

New Total Contract Amount: \$_____

New Total MWBE Participation _____ %

DATE:

Contract Amount Impact Increase \$_____ Decrease \$_____ No Change ☐

MWBE Participation Change Increase _____ % Decrease _____ % No Change ☐

☐ APPROVED

☐ REJECTED

NOTES:



Minority and Women-owned Business Enterprise Program (MWBE)

Explanation of Affidavit A

A Listing of the Good Faith Effort (GFE)

Company has made a good faith effort to recruit minority businesses in accordance with N.C. Gen. Stat. § 143-128.2 and represents that it has performed the following (**check all that apply; note that a minimum of fifty (50) points must be achieved**):

Examples of ways to satisfy requirements are given for each criterion below:

- ☐ 1. (10 points) Contacted minority businesses that reasonably could have been expected to submit a quote and that were known to the contractor or available on State or local government maintained lists, at least 10 days before the bid date and notified them of the nature and scope of the work to be performed.
 - *Provide a list of potential bidders with proof of acknowledged responses (i.e. quotes)*
 - *Provide confirmation of notification at least 10 days before bid date*
 - *Newspaper/trade ads do not qualify as GFE notification*
- ☐ 2. (10 points) Made the construction plans, specifications and requirements available for review by prospective minority businesses, or provided these documents to them at least 10 days before the bids are due.
 - *Provide confirmation of notification at least 10 days before bid date*
 - *Include in the notice that plan specs are available in office/online (location/link) and at no cost to MWBEs*
 - *Newspaper/trade ads do not qualify as GFE notification*
- ☐ 3. (15 points) Broke down or combined elements of work into economically feasible units to facilitate minority participation.
 - *Provide confirmation of solicitation that include subcontracting opportunities (i.e. itemize or group trades such as flooring/trim or divide one sub does flooring and another sub does trim)*
- ☐ 4. (10 points) Worked with minority trade, community, or contractor organizations identified by the Office of Historically Underutilized Businesses and included in the bid documents that provide assistance in recruitment of minority businesses.
 - *Obtain letter or other documentation from one of these organizations indicating that you are working with them in the recruitment of minority businesses – NCMWBE Coordinators Network, The Institute, NCIEDI or HCAC.*
 - *A list of organizations can be found at www.raleighnc.gov/mwbe*

- ❑ 5. (10 points) Attended pre-bid meetings scheduled by the public owner.
 - ***Attendance is recorded (make sure you sign-in)***
- ❑ 6. (20 points) Provided assistance in getting required bonding or insurance or provided alternatives to bonding or insurance for subcontractors.
 - ***Include one of the following statements in solicitation to MWBEs as it applies:***
 - ***Bonds are not required for this project***
 - ***Bidder will assist in procuring bonds or insurance if necessary***
- ❑ 7. (15 points) Negotiated in good faith with interested minority businesses and did not reject them as unqualified without sound reasons based on their capabilities. Any rejection of a minority business based on lack of qualification should have the reasons documented in writing.
 - ***“MWBE Solicitation Form” is attached to the Explanation Affidavit A Form***
 - ***Provide completed MWBE Solicitation Form to document the following:***
 - ***Did not receive low quotes from MWBEs***
 - ***Bidder accepted other low quotes from MWBEs***
 - ***Written reasons for rejection of any low quotes from MWBEs***
- ❑ 8. (25 points) Provided assistance to an otherwise qualified minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisted minority businesses in obtaining the same unit pricing with the bidder’s suppliers in order to help minority businesses in establishing credit.
 - ***Indicate in solicitation the following are available: equipment, loan capital, lines of credit, or joint pay agreements for qualified MWBEs or any other needs.***
 - ***Document recent history of doing joint pay agreements such as “in the recent past, we have done joint pay agreements (lines of credit, waiving of credit, etc.) with the following MWBEs (x company, y company, z company) and intend to offer the same on this project for qualified MWBEs”***
 - ***Provide letter from vendor/supplier indicating that they will give the same pricing to MWBEs quoting to you as vendor/supplier gives directly to you***
- ❑ 9. (20 points) Negotiated joint venture and partnership arrangements with minority businesses in order to increase opportunities for minority business participation on a public construction or repair project when possible.
 - ***Indicate in solicitation that opportunities to negotiate joint venture and partnership arrangements are available***
- ❑ 10. (20 points) Provided quick pay agreements and policies to enable minority contractors and suppliers to meet cash flow demands.
 - ***Indicate in solicitation that quick pay agreements are available for certified MWBEs to include payment terms (i.e., Net 30).***
 - ***Document recent history of doing quick pay agreements such as “in the recent past, we have done quick pay agreements with the following MWBE’s (x company, y company, z company) and intend to offer the same on this project for qualified MWBE’s”***

SOLICITATION FORM

Copy this Form as needed to document MWBE contacts.

The Bidder must make the required contacts no less than ten (10) Days before Bid Opening to receive credit for this Good Faith Effort. All contacts must be verifiable with supporting documentation reflecting the methods and content of the solicitation. All documentation must be submitted with this form.

A Bidder must submit this Solicitation Form within the time specified in the City Solicitation Documents. If no time period is specified in the City Solicitation Documents, the Bidder must submit this form within three (3) Business Days after the City requests it.

SECTION 1. PROJECT INFORMATION

Project Name			
Project Number		City Department	
Bidder		Number MWBEs Contacted	

SECTION 2. SOLICITATION INFORMATION

If "No" is checked for "Selected" below, the Bidder must document the reasons for rejecting each bid submitted by a MWBE on the Good Faith Negotiation Form.

MWBE FIRM		CONTACT PERSON	
SCOPE OF WORK			
INITIAL CONTACT	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
FOLLOW-UP	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
RESPONSE	☐ No Response	☐ Not Bidding	☐ Bidding (\$_____) ☐ Other (Explain)
SELECTED	☐ Yes	☐ No (Explain)	

MWBE FIRM		CONTACT PERSON	
SCOPE OF WORK			
INITIAL CONTACT	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
FOLLOW-UP	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
RESPONSE	☐ No Response	☐ Not Bidding	☐ Bidding (\$_____) ☐ Other (Explain)
SELECTED	☐ Yes	☐ No (Explain)	

MWBE FIRM		CONTACT PERSON	
SCOPE OF WORK			
INITIAL CONTACT	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
FOLLOW-UP	DATE: ____/____/20____	METHOD (select all used):	☐ Email ☐ Telephone ☐ Fax ☐ In-Person ☐ Mail
RESPONSE	☐ No Response	☐ Not Bidding	☐ Bidding (\$_____) ☐ Other (Explain)
SELECTED	☐ Yes	☐ No (Explain)	

CONTRACTOR'S CERTIFICATES
AFFIDAVIT OF ORGANIZATION AND AUTHORITY
AND
SWORN STATEMENT

STATE OF _____)

COUNTY _____)
OF _____

_____ being the first duly sworn on oath deposes and says that the Bidder on the attached Bid is organized as indicated below and that all statements herein made are made on behalf of such Bidder and that this deponent is authorized to make them.

(Fill Out Applicable Paragraph)

1. CORPORATION:

The Bidder is a Corporation organized and existing under the laws of the State of _____ and its President is _____ ; its Secretary is _____ , and it does have a corporate seal. The President is authorized to sign construction contracts and bids for the Company by action of its Board of Directors taken _____ a certified copy of which is hereto attached. (Strike out last sentence if not applicable.)

2. PARTNERSHIP:

The Bidder is a partnership consisting of _____ and _____ , partners doing business under the name of: _____

3. SOLE TRADER:

The Bidder is an individual and if operating under a trade name, such trade name is as follows: _____

4. ADDRESS:

The business address of the Bidder is as follows: _____

Its phone number is _____

Bidder
By: _____

Subscribed and sworn to before me this _____ day of _____, 20 ____ .
Co.

Notary Public

My Commission Expires:

CITY OF RALEIGH
CONTRACTOR'S POOR PERFORMANCE POLICY

RESOLUTION NO. (1992) 790

A RESOLUTION TO REGULATE THE PARTICIPATION IN CITY CONSTRUCTION PROJECTS BY CONTRACTORS WHO MAY NOT BE CAPABLE OF TIMELY AND PROPER COMPLETION OF CITY PROJECTS.

WHEREAS, the City of Raleigh wishes to minimize cost and inconvenience to the citizenry caused by the failure of contractors to complete projects in a timely manner in accordance with approved project schedules; and

WHEREAS, North Carolina law allows cities to award bids to responsible bidders and the inability to complete work on time is one indication of a lack of responsibility.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF RALEIGH:

Section 1. That the City Manager may disqualify bidders from participation in bidding and award of contracts for city construction projects based on the following conditions existing simultaneously:

- A. The dollar value of the work completed is less than the dollar value of the work which should have been completed on the basis of the contractor's approved progress schedule by more than twenty percent of the current contract amount. The dollar amount of the work completed will be the total estimate to date shown in the latest partial pay estimate. The current contract amount will be the contract estimate plus accumulated overruns and less accumulated underruns shown in the latest partial pay estimate.
- B. The percentage of the work completed is less than the percentage of contract time elapsed on the work by more than twenty percent. The percentage of work completed will be the dollar value of the work completed as defined above divided by the current contract amount as defined above. The percentage of contract time elapsed will be the number of calendar days elapsed as shown in the latest partial pay estimate divided by the total contract time in calendar days.

Section 2. The City Manager shall not include any late days which are caused by the City in any of his calculations directed at determining bid status.

Section 3. All City construction project specifications shall contain a specific provision clearly outlining the policies set out in this Resolution, including the criteria for determining whether a contractor is behind schedule, and the specifications shall clearly state the City's intent to enforce the provisions of this Resolution.

Section 4. The terms of this Resolution shall apply only to contracts for which the specifications for bidders are issued after the effective date of this Resolution.

Section 5. Any contractor who wishes to contest the decision of the City Manager declaring ineligibility may appeal to the City Council by delivering a notice of appeal to the City Clerk no later than ten days after receipt of the City Manager's decision. The notice of appeal shall clearly set out the reasons why the Contractor believes that the terms of this Resolution have been inappropriately applied or the equitable arguments for not applying this Resolution's terms. When considering an appeal the City Council shall consider, among other things, the report of the City manager, the notice of appeal, and the contractor's current status on any other current City contracts and its performance on any other contracts to which the contractor and the City have been parties to within the two calendar years immediately preceding the filing of the notice of appeal.

Section 6. Bidders so disqualified shall remain disqualified for any period in which they are still in conflict with the schedule provisions of this section.

Section 7. This Resolution is effective upon adoption.

ADOPTED: 10/6/92

EFFECTIVE: 10/6/92

I have read and understand the City of Raleigh's policy as stated above.

Signature

Printed Name

Title

Date

NON-COLLUSIVE AFFIDAVIT

State of _____)
)ss.
County of _____)

First being duly sworn deposes and says that:

- (1) He is the _____
(Owner, Partner, Officer, Representative or Agent)
of _____ the Bidder that has submitted the attached Bid;
- (2) He is fully informed respecting the preparation and contents of the attached Bid and of all pertinent circumstances respecting such Bid;
- (3) Such Bid is genuine and is not a collusive or sham Bid;
- (4) Neither the said Bidder nor any of its officers, partners, owners, agents, representatives, employees or parties in interest, including this affiant, have in any way colluded, conspired, connived or agreed, directly or indirectly, with any other Bidder, firm, or person to submit a collusive or sham Bid in connection with the Contract for which the attached Bid has been submitted; or to refrain from bidding in connection with such Contract; or have in any manner, directly or indirectly, sought by agreement or collusion, or communication, or conference with any Bidder, firm, or person to fix the price or prices in the attached Bid or of any other Bidder, or to fix any overhead, profit, or cost elements of the Bid price or the Bid price of any other Bidder, or to secure through any collusion, conspiracy, connivance, or unlawful agreement any advantage against (Recipient), or any person interested in the proposed Contract;
- (5) The price or prices quoted in the attached Bid are fair and proper and are not tainted by any collusion, conspiracy, connivance, or unlawful agreement on the part of the Bidder or any other of its agents, representatives, owners, employees or parties in interest, including this affidavit.

BY _____

PRINTED OR TYPED NAME _____

ITS _____
(Title)

Subscribed and sworn to before me this _____ day of _____, 20_____.

Notary Public My commission expires _____

END OF AFFIDAVIT

NOTICE TO CONTRACTOR REGARDING INTRUSIONS BEYOND PROJECT LIMITS

The Contractor and Owner hereby acknowledge that the Owner has acquired permanent and temporary easements on private property for the construction of the Project (the "Easements"), and that the Easements, together with public street rights-of-way (and previously acquired easements) comprise the sole areas where the Contractor is allowed to work on the Project, or to use for mobilization, access, staging, storage, and other purposes associated with the Project.

ANY OCCUPANCY OF OR INTRUSIONS ONTO PRIVATE PROPERTY OUTSIDE THE EASEMENTS OR RIGHTS-OF-WAY OWNED OR CONTROLLED BY THE CITY WILL CONSTITUTE A TRESPASS UPON PRIVATE PROPERTY AND MAY RESULT IN SERIOUS LEGAL CONSEQUENCES FOR THE CITY OF RALEIGH.

The Contractor shall be solely responsible for any intrusions onto private property outside the Easements or rights-of-way owned or controlled by the City. The Contractor hereby agrees to save, defend, hold harmless, and indemnify the City from all actions, claims, and liabilities , arising from such actions including, but not limited to, the payment of attorney's fees.

The only exception to the above stated limitations on the Contractor's work area will be in those instances where the Contractor has independently negotiated and secured agreements for temporary work and/or access privileges from Property Owners. These independently negotiated agreements must be in writing, and a copy of any such agreement shall be provided to the City in advance of any use or occupancy of private property pursuant to the agreement. The terms of any independently negotiated agreement shall clearly express to the Property Owner that the Contractor is seeking such use, occupancy, or access independently from the City of Raleigh and its Contract with the City of Raleigh, and that the Contractor shall be solely responsible for activities carried out on such areas.

I have read and understand the City of Raleigh's policy as stated above.

Signature

Printed Name

Title

Date

NOTICE OF AWARD

Date of Issuance:

Owner: City of Raleigh

Owner's Project No.:

Engineer:

Engineer's Project No.:

Project: Neuse River RRF Roof Replacements,
Filter & Blower Buildings

Contract Name:

Bidder:

Bidder's Address:

You are notified that Owner has accepted your Bid dated **[date]** for the above Contract, and that you are the Successful Bidder and are awarded a Contract for: **[Describe Work, alternates, or sections of Work awarded]**

The Contract Price of the awarded Contract is **[\$[Contract Price]**. Contract Price is subject to adjustment based on the provisions of the Contract, including but not limited to those governing changes, Unit Price Work, and Work performed on a cost-plus-fee basis, as applicable.

[Number of copies sent] unexecuted counterparts of the Agreement accompany this Notice of Award, and one copy of the Contract Documents accompanies this Notice of Award, or has been transmitted or made available to Bidder electronically.

☐ Drawings will be delivered separately from the other Contract Documents.

You must comply with the following conditions precedent within 15 days of the date of receipt of this Notice of Award:

1. Deliver to Owner **[number of copies sent]** counterparts of the Agreement, signed by Bidder (as Contractor).
2. Deliver with the signed Agreement(s) the Contract security (such as required performance and payment bonds) and insurance documentation, as specified in the Instructions to Bidders and in the General Conditions, Articles 2 and 6.
3. Other conditions precedent (if any): **[Describe other conditions that require Successful Bidder's compliance]**

Failure to comply with these conditions within the time specified will entitle Owner to consider you in default, annul this Notice of Award, and declare your Bid security forfeited.

Within **90** days after you comply with the above conditions, Owner will return to you one fully signed counterpart of the Agreement, together with any additional copies of the Contract Documents as indicated in Paragraph 2.02 of the General Conditions.

Owner: **City of Raleigh**

By (signature): _____

Name (printed): _____

Title: _____

City of Raleigh

00510-1

Notice of Award

EJCDC® C-510, Notice of Award.

Copyright© 2018 National Society of Professional Engineers, American Council of Engineering Companies,
and American Society of Civil Engineers. All rights reserved.

Copy: Engineer

AGREEMENT

INSTRUCTIONS TO CONTRACTORS AND REQUIREMENTS AS TO FORM FOR CITY OF RALEIGH, NC AGREEMENTS

DO NOT REMOVE FROM AGREEMENT

Please observe the following in executing the attached Contract:

1. The Owner may enter into an Agreement with three types of legal entities.
 - (a) If the Agreement is with an individual, that individual should sign the Agreement exactly as his name is set out. If the Agreement is with an individually-owned business, the Agreement should be with the individual owner, and not the named business.
 - (b) Execution on behalf of a corporation should be by an authorized corporate officer, with a second corporate officer signing to attest, with the corporate seal affixed. An official other than a corporate officer should attach documentation of their authority to execute and bind the company.
 - (c) If the Agreement is with a partnership, a general partner may execute unless an authorized partner is designated to execute. Documentation of such authorization should be attached.
2. After signing the Agreement, the appropriate notary's acknowledgement, either in the corporate form or individual/partnership form should be completed.
3. The Performance and Payment Bonds should be attached to the Agreement package. They should be signed by the Agree mentor, and his signature should be acknowledged with the appropriate acknowledge form. Next, the Bonds, in approved form, must be signed by the authorized agent of the Surety Company issuing the Bonds, and an executed Power of Attorney document authorizing the agent to sign must accompany the Bond Documents.
4. The Agreement should not be dated, except by the last person executing the Agreement, normally the City Clerk.
5. The Bid Form and all other documents submitted with the Bid shall be included with the Agreement and as noted in Article 9.
6. Page 00510 -1: Complete the Acceptance of Notice section on this page.
7. Pages 00520-3 through 00520-13: Complete in entirety.
8. Section 00610, 00615, 00617, and 00618: Complete in entirety.

9. Section 00618: Certificate of Insurance, Article 5 of the General and Supplementary Conditions requires the Certificate of Insurance to have those named as Additional Insured in each policy issued.
10. Most Certificates of Insurance state under the cancellation clause that "the issuing company will endeavor to mail 30 days written notice to the ..." and "but failure to mail such notice shall impose no obligation or liability of any kind upon the Company, its agents or representatives. Direct Notice of Cancellation endorsement is to be attached to corresponding Certificates of Insurance. With regard to expiration, cancellation, reduction, restriction, or any other change, certificates shall state:

"Should any of the following described policies be canceled before expiration date or be due to expire within thirty (30) days, the insurer shall mail thirty (30) days prior written notice to named certificate holder."
11. Four copies of the Contract are sent to the Contractor. The original and duplicates should be signed and returned to the Owner for signature, after which two duplicates will be returned to the Contractor. One copy may be retained by the Contractor and the other is for the use of the Bonding Company(s).
12. Failure to fully complete all four sets of the Contract Documents will cause delays in the approval by the Owner and therefore delay the issuance of the Notice to Proceed.

**AGREEMENT
BETWEEN OWNER AND CONTRACTOR
FOR CONSTRUCTION CONTRACT**
CITY CONTRACT NO. [enter number]
CITY PURCHASE ORDER NO. [enter number]

THIS AGREEMENT is by and between The City of Raleigh (Owner) and [Contractor's Name] (Contractor).

Owner and Contractor hereby agree as follows:

ARTICLE 1 – WORK

Contractor shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows:

At the NRRRF Blower Building & Filter Building #1:

- Removal of existing curbs and roofing materials
- Installation of new roofing materials
- Removal and reinstallation of lightning protection features
- Misc. work

ARTICLE 2 – THE PROJECT

The Project for which the Work under the Contract Documents may be the whole or only a part is generally described as follows: Neuse River Resource Recovery Facility (RRF) Roof Replacements, Filter and Blower Buildings.

ARTICLE 3 – ENGINEER

The Project has been designed by HDR. However, the Owner shall act as the Engineer and Resident Project Representative, assume all duties and responsibilities, and have the rights and authority assigned to Engineer in the Contract Documents in connection with the completion of the Work in accordance with the Contract Documents.

ARTICLE 4 – CONTRACT TIMES

4.01 *Time of the Essence*

- A. All time limits for Milestones, if any, Substantial Completion, and completion and readiness for final payment as stated in the Contract Documents are of the essence of the Contract.

4.02 *Days to Achieve Substantial Completion and Final Payment*

- A. The Work will be substantially completed within 180 days after the date when the Contract Times commence to run as provided in Paragraph 4.01 of the General Conditions, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions within 210 after the date when the Contract Times commence to run.

4.03 Liquidated Damages

- A. Contractor and Owner recognize that time is of the essence as stated in Paragraph 4.01 above and that Owner will suffer financial loss if the Work is not completed within the times specified in Paragraph 4.02 above, plus any extensions thereof allowed in accordance with Article 11 of the General Conditions. The parties also recognize the delays, expense, and difficulties involved in proving in a legal or arbitration proceeding the actual loss suffered by Owner if the Work is not completed on time. Accordingly, instead of requiring any such proof, Owner and Contractor agree that as liquidated damages for delay (but not as a penalty):
1. *Substantial Completion*: Contractor shall pay Owner \$500 for each day that expires after the time specified in Paragraph 4.02 above for Substantial Completion until the Work is substantially complete.
 2. *Completion of Remaining Work*: After Substantial Completion, if Contractor shall neglect, refuse, or fail to complete the remaining Work within the Contract Times or any proper extension thereof granted by Owner, Contractor shall pay Owner \$500 for each day that expires after the time specified in Paragraph 4.02 above for completion and readiness for final payment until the Work is completed and ready for final payment.
 3. Liquidated damages for failing to timely attain Milestones, Substantial Completion, and final completion are not additive, and will not be imposed concurrently.
- B. If Owner recovers liquidated damages for a delay in completion by Contractor, then such liquidated damages are Owner's sole and exclusive remedy for such delay, and Owner is precluded from recovering any other damages, whether actual, direct, excess, or consequential, for such delay, except for special damages (if any) specified in this Agreement.

ARTICLE 5 – CONTRACT PRICE

- 5.01 Owner shall pay Contractor for completion of the Work in accordance with the Contract Documents an amount in current funds equal to the sum of the amounts determined pursuant to Paragraphs 5.01.A, 5.01.B, 5.01.C, and 5.01 D below:

The Contract Price shall not exceed the Total Contract amount of insert written out Contract Price here Dollars [insert Contract Price in numerical form here] unless changed by a duly authorized amendment or change order.

- A. For all Work, a Lump Sum for the following Work Items:

Filter Building #1	\$
Blower Building	\$
The Total Contract for the Lump Sum Price of:	\$

\$ _____

Dollars

All specific cash allowances are included in the above price in accordance with Paragraph 13.02 of the General Conditions.

B. For all Work, at the prices stated in Contractor's Bid, attached hereto as an exhibit.

ARTICLE 6 – PAYMENT PROCEDURES

6.01 *Submittal and Processing of Payments*

A. Contractor shall submit Applications for Payment in accordance with Article 15 of the General Conditions. Applications for Payment will be processed by Engineer as provided in the General Conditions.

6.02 *Progress Payments; Retainage*

A. Owner shall make progress payments on account of the Contract Price on the basis of Contractor's Applications for Payment on or about the 25th day of each month during performance of the Work as provided in Paragraph 6.02.A.1 below. All such payments will be measured by the schedule of values established as provided in Paragraph 2.05 of the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no schedule of values, as provided in the General Requirements.

1. Prior to Final Completion, progress payments will be made in an amount equal to the percentage indicated in the Supplemental Conditions but, in each case, less the aggregate of payments previously made and less such amounts as Engineer may determine or Owner may withhold, including but not limited to liquidated damages, in accordance with Paragraph 15.01 of the General Conditions.

6.03 *Final Payment*

A. Upon final completion and acceptance of the Work in accordance with Paragraph 15.06 of the General Conditions, Owner shall pay the remainder of the Contract Price as recommended by Engineer as provided in said Paragraph 15.06.

ARTICLE 7 – INTEREST

7.01 Once a Progress or Final Payment Application has been submitted by the contractor, recommended by the Engineer, and Approved by the Owner, if payment is not made, the Contractor will be due interest beginning on the 46th day following Owner acceptance at a

rate of 1% per month or fraction thereof in accordance with NC General Statute 143-134.1(a).

ARTICLE 8 – CONTRACTOR’S REPRESENTATIONS

8.01 *In order to induce Owner to enter into this Agreement, Contractor makes the following representations:*

- A. Contractor has examined and carefully studied the Contract Documents and the other related data identified in the Bidding Documents.
- B. Contractor has visited the Site and become familiar with and is satisfied as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work.
- C. Contractor is familiar with and is satisfied as to all federal, state, and local Laws and Regulations that may affect cost, progress, and performance of the Work.
- D. Contractor has carefully studied all: (1) reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities), if any, that have been identified in Paragraph SC-5.03 of the Supplementary Conditions as containing reliable "technical data," and (2) reports and drawings of Hazardous Environmental Conditions, if any, at the Site that have been identified in Paragraph SC-5.06 of the Supplementary Conditions as containing reliable "technical data."
- E. Contractor has considered the information known to Contractor; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Contract Documents; and the Site-related reports and drawings identified in the Contract Documents, with respect to the effect of such information, observations, and documents on (1) the cost, progress, and performance of the Work; (2) the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, including any specific means, methods, techniques, sequences, and procedures of construction expressly required by the Contract Documents; and (3) Contractor's safety precautions and programs.
- F. Based on the information and observations referred to in Paragraph 8.01.E above, Contractor does not consider that further examinations, investigations, explorations, tests, studies, or data are necessary for the performance of the Work at the Contract Price, within the Contract Times, and in accordance with the other terms and conditions of the Contract Documents.
- G. Contractor is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Contract Documents.
- H. Contractor has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Contractor has discovered in the Contract Documents, and the written resolution thereof by Engineer is acceptable to Contractor.
- I. The Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.

ARTICLE 9 – CONTRACT DOCUMENTS

9.01 Contents

A. The Contract Documents consist of the following (as attached to this Agreement):

1. This Agreement (pages 00520-1 to 00520-_____, inclusive).
2. Performance bond (pages 00610-1 to 00610-_____, inclusive).
3. Payment bond (pages 00615-1 to 00615-_____, inclusive).
4. Affidavit (page 00617)
5. Certificate of Insurance (pages 00618-1 to 00618-_____, inclusive).
6. General Conditions (pages 00700-1 to 00700-_____, inclusive).
7. Supplementary Conditions (pages 00800-1 to 00800-_____, inclusive).
8. Specifications as listed in the table of contents (pages 00010-1 to 00010-_____) of the Project Manual.
9. Drawings consisting of [number of drawing sheets] sheets with each sheet bearing the following general title: [Project sheet title].
10. Addenda as follows: [1 through xx or N/A]
11. Exhibits to this Agreement (enumerated as follows):
 - a. Contractor's Bid (Sections 00410 and 00430).
 - b. Documentation submitted by Contractor prior to Notice of Award (City of Raleigh Bid Documentation; Sections 00440, 00441, 00442, 00443, and 00444).
 - c. Notice of Award (Section 00510).
12. The following which may be delivered or issued on or after the Effective Date of the Agreement and are not attached hereto:
 - a. Notice to Proceed (Section 00550).
 - b. Work Change Directives (Section 00940).
 - c. Change Orders (Section 00941).
 - d. Field Orders (Section 00942).
 - e. Warranty Bonds, if any.

B. The documents listed in Paragraph 9.01.A are part of this Agreement, and if not physically attached, are incorporated fully to this Agreement by reference (**except as expressly noted otherwise above**).

- C. There are no Contract Documents other than those listed above in this Article 9.
- D. The Contract Documents may only be amended, modified, or supplemented as provided in the Contract.

ARTICLE 10 – MISCELLANEOUS

10.01 *Terms*

- E. Terms used in this Agreement will have the meanings stated in the General Conditions and the Supplementary Conditions.

10.02 *Assignment of Contract*

- A. No assignment by a party hereto of any rights under or interests in the Contract will be binding on another party hereto without the written consent of the party sought to be bound; and, specifically but without limitation, moneys that may become due and moneys that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.

10.03 *Successors and Assigns*

- A. Owner and Contractor each binds itself, its partners, successors, assigns, and legal representatives to the other party hereto, its partners, successors, assigns, and legal representatives in respect to all covenants, agreements, and obligations contained in the Contract Documents.

10.04 *Severability*

- A. Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon Owner and Contractor, who agree that the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.

10.05 *Contractor's Certifications*

- A. Contractor certifies that it has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for or in executing the Contract. For the purposes of this Paragraph 10.05:
 - 1. "corrupt practice" means the offering, giving, receiving, or soliciting of any thing of value likely to influence the action of a public official in the bidding process or in the Contract execution;
 - 2. "fraudulent practice" means an intentional misrepresentation of facts made (a) to influence the bidding process or the execution of the Contract to the detriment of Owner, (b) to establish Bid or Contract prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;

3. "collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish Bid prices at artificial, non-competitive levels; and
4. "coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the execution of the Contract.

10.06 *Right to Audit Clause*

- A. Contractor's, subcontractors' and sub-subcontractors' "records" shall upon reasonable notice be open to inspection and subject to audit and/or reproduction during normal business working hours. Such audits may be performed by a City's representative or an outside representative engaged by City. The City or its designee may conduct such audits or inspections throughout the term of this Contract and for a period of three years after final payment or longer if required by law. City's representatives may (without limitation) conduct verifications such as counting employees at the Construction Site, witnessing the distribution of payroll, verifying information and amounts through interviews and written confirmations with Contractor employees, field and agency labor, subcontractors, and vendors.
- B. Such records shall include (hard copy, as well as computer readable data if it can be made available): written policies and procedures; time sheets; payroll registers; payroll records; cancelled payroll checks; subcontract files (including proposals of successful and unsuccessful bidders, bid recaps, negotiation notes, etc.); original bid estimates; estimating work sheets; correspondence; Change Order files (including documentation covering negotiated settlements); back charge logs and supporting documentation; invoices and related payment documentation; general ledger information detailing cash and trade discounts earned, insurance rebates and dividends; and any other Contractor records which may have a bearing on matters of interest to the City in its sole discretion in connection with the Contractor's dealings with the City, including but not limited to:
 1. Compliance with Contract requirements for deliverables;
 2. Compliance with Construction Documents;
 3. Compliance with City's business ethics expectations;
 4. Compliance with Contract provisions regarding the pricing of Change Orders;
 5. Accuracy of Contractor representations regarding the pricing of invoices; or
 6. Accuracy of Contractor representations related to claims submitted by the Contractor or any of its payees.
- C. Contractor shall require all payees (examples of payees include subcontractors, material suppliers, insurance carriers, etc.) to comply with the provisions of this article by including the requirements hereof in a written contract agreement between Contractor and payee. Contractor will ensure that all payees (including those entering into lump sum contracts) have the same right to audit provisions contained in this Contract.
- D. City's authorized representative or designee shall have reasonable access to the Contractor's facilities, shall be allowed to interview all current or former employees to

discuss matters pertinent to the performance of this Contract and shall be provided adequate and appropriate work space, in order to conduct audits in compliance with this article.

- E. If an audit, inspection or examination in accordance with this article, discloses overpricing or overcharges (of any nature) by the Contractor to the City in excess of one percent (1%) of the total contract billings, in addition to making adjustments for the overcharges, the reasonable actual cost of the City's audit shall be reimbursed to the City by the Contractor. Any adjustments and/or payments which must be made as a result of any such audit or inspection of the Contractor's invoices and/or records shall be made within a reasonable amount of time (not to exceed 90 days) from presentation of City's findings to Contractor.
- F. The Contractor agrees to maintain all information pertaining to billing for services performed under this Contract in accordance with state law for public records. The Contractor shall afford the City access to these records for audit at such intervals as may be desired by the City. The Contractor shall also preserve the records for a period of three (3) years after Final Payment (or, alternatively, for a period of three years after termination of this Contract), or longer if required by law, during which time the City shall have access for audit purposes.
- G. The rights established under this section shall survive the expiration or termination of this Contract, and shall not be deleted, circumvented, limited, confined, or restricted by contract or any other section, clause, addendum, attachment or subsequent amendment to this Contract or any of the other Contract Documents.

10.07 *Iran Divestment Act Certification*

- A. Contractor certifies that, as of the date listed below, it is not on the Final Divestment List as created by the State Treasurer pursuant to N.C.G.S. § 147-86.55, et seq. In compliance with the requirements of the Iran Divestment Act and N.C.G.S. § 147-86.59, Contractor shall not utilize in the performance of the contract any subcontractor that is identified on the Final Divestment List.

10.08 *E – Verify*

- A. Contractor shall comply with E-Verify, the federal E-Verify program operated by the United States Department of Homeland Security and other federal agencies, or any successor or equivalent program used to verify the work authorization of newly hired employees pursuant to federal law and as in accordance with N.C.G.S. §64-25 et seq. In addition, to the best of Contractor's knowledge, any subcontractor employed by Contractor as a part of this contract shall be in compliance with the requirements of E-Verify and N.C.G.S. §64-25 et seq.

10.09 *Companies Boycotting Israel Divestment Act Certification*

- A. Contractor certifies that it has not been designated by the North Carolina State Treasurer as a company engaged in the boycott of Israel pursuant to N.C.G.S. 147-86.81.

10.10 *Applicability of North Carolina Public Records Law*

- 10.11 Notwithstanding any other provisions of this Contract, this Contract and all materials submitted to the City by the Contractor are subject to the public records laws of the State of North Carolina and it is the responsibility of the Contractor to properly designate materials that may be protected from disclosure as trade secrets under North Carolina law as such and in the form required by law prior to the submission of such materials to the City. Contractor understands and agrees that the City may take any and all actions necessary to comply with federal, state, and local laws and/or judicial orders and such actions will not constitute a breach of the terms of this Contract. To the extent that any other provisions of this Contract conflict with this paragraph, the provisions of this section shall control.

THIS SPACE LEFT BLANK INTENTIONALLY

IN WITNESS WHEREOF, Owner and Contractor have signed this Agreement by digital signature, under seal, on the respective dates below. Counterparts have been delivered to Owner and Contractor. All portions of the Contract Documents have been signed or have been identified by Owner and Contractor or on their behalf. This Agreement shall be effective upon the date of the City's signature ("Effective Date").

OWNER:

CONTRACTOR:

CITY OF RALEIGH

****Name of Contractor****

a North Carolina municipal corporation

By: _____

By: _____

Name: _____

Name: _____

Title: Choose an item.

Title: _____

Date: _____

Date: _____

Attest: _____

Attest: _____

Title: **City Clerk (or designee)**

Title: _____

Address for giving notices:

Address for giving notices:

City of Raleigh

222 W. Hargett Street

Raleigh, North Carolina 27601

License No.: _____

This instrument has been pre-audited in the manner required by the Local Government Budget and Fiscal Control Act.

Chief Financial Officer (or designee)

NOTICE TO PROCEED

Owner: City of Raleigh Owner's Project No.: _____
Engineer: _____ Engineer's Project No.: _____
Contractor: _____ Contractor's Project No.: _____
Project: Neuse River RRF Roof Replacements, Filter & Blower Buildings
Contract Name: _____
Effective Date of Contract: _____

Owner hereby notifies Contractor that the Contract Times under the above Contract will commence to run on **[date Contract Times are to start]** pursuant to Paragraph 4.01 of the General Conditions.

On that date, Contractor shall start performing its obligations under the Contract Documents. No Work will be done at the Site prior to such date.

In accordance with the Agreement: **[Insert number of days and dates.]**

The number of days to achieve Substantial Completion is **[number of days, from Agreement]** from the date stated above for the commencement of the Contract Times, resulting in a date for Substantial Completion of **[date, calculated from commencement date above]**; and the number of days to achieve readiness for final payment is **[number of days, from Agreement]** from the commencement date of the Contract Times, resulting in a date for readiness for final payment of **[date, calculated from commencement date above]**.

Before starting any Work at the Site, Contractor must comply with the following:

[Note any access limitations, security procedures, or other restrictions]

Owner: City of Raleigh
By (signature): _____
Name (printed): _____
Title: _____
Date Issued: _____
Copy: Engineer

PERFORMANCE BOND

Contractor Name: [Full formal name of Contractor] Address <i>(as registered with Secretary of State, if applicable)</i> : [Address of Contractor]	Surety Name: [Full formal name of Surety] Address <i>(as registered with Secretary of State, if applicable)</i> : [Address of Surety]
Owner Name: City of Raleigh Mailing address: 222 W. Hargett Street Raleigh, NC 27601	Contract Description <i>(name and location)</i> : [Owner's project/contract name, and location of the project] Contract Price: [Amount from Contract] Effective Date of Contract: [Date from Contract]
Bond Bond Amount: [Amount] Date of Bond: [Date] <i>(Date of Bond cannot be earlier than Effective Date of Contract)</i> Modifications to this Bond form: ☐ None ☐ See Paragraph 16	
Surety and Contractor, intending to be legally bound hereby, subject to the terms set forth in this Performance Bond, do each cause this Performance Bond to be duly executed by an authorized officer, agent, or representative.	
Contractor as Principal	Surety
<i>(Full formal name of Contractor)</i> 	<i>(Full formal name of Surety) (corporate seal)</i>
By: <i>(Signature)</i>	By: <i>(Signature)(Attach Power of Attorney)</i>
Name: <i>(Printed or typed)</i>	Name: <i>(Printed or typed)</i>
Title:	Title:
Attest: <i>(Signature)</i>	Attest: <i>(Signature)</i>
Name: <i>(Printed or typed)</i>	Name: <i>(Printed or typed)</i>
Title:	Title:
<i>Notes: (1) Provide supplemental execution by any additional parties, such as joint venturers. (2) Any singular reference to Contractor, Surety, Owner, or other party is considered plural where applicable.</i>	

1. The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.
2. If the Contractor **satisfactorily** performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except when applicable to participate in a conference as provided in Paragraph 3.
3. If there is no Owner Default under the Construction Contract, the Surety's obligation under this Bond will arise after:
 - 3.1. The Owner first provides notice to the Contractor and the Surety that the Owner is considering declaring a Contractor Default. Such notice may indicate whether the Owner is requesting a conference among the Owner, Contractor, and Surety to discuss the Contractor's performance. If the Owner does not request a conference, the Surety may, within five (5) business days after receipt of the Owner's notice, request such a conference. If the Surety timely requests a conference, the Owner shall attend. Unless the Owner agrees otherwise, any conference requested under this Paragraph 3.1 will be held within ten (10) business days of the Surety's receipt of the Owner's notice. If the Owner, the Contractor, and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement does not waive the Owner's right, if any, subsequently to declare a Contractor Default;
 - 3.2. The Owner declares a Contractor Default, terminates the Construction Contract and notifies the Surety; and
 - 3.3. The Owner has agreed to pay the Balance of the Contract Price in accordance with the terms of the Construction Contract to the Surety or to a contractor selected to perform the Construction Contract.
4. Failure on the part of the Owner to comply with the notice requirement in Paragraph 3.1 does not constitute a failure to comply with a condition precedent to the Surety's obligations, or release the Surety from its obligations, except to the extent the Surety demonstrates actual prejudice.
5. When the Owner has satisfied the conditions of Paragraph 3, the Surety shall promptly and at the Surety's expense take one of the following actions:
 - 5.1. Arrange for the Contractor, with the consent of the Owner, to perform and complete the Construction Contract;
 - 5.2. Undertake to perform and complete the Construction Contract itself, through its agents or independent contractors;
 - 5.3. Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and a contractor selected with the Owners concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Paragraph 7 in excess of the Balance of the Contract Price incurred by the Owner as a result of the Contractor Default; or
 - 5.4. Waive its right to perform and complete, arrange for completion, or obtain a new contractor, and with reasonable promptness under the circumstances:

- 5.4.1 After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, make payment to the Owner; or
 - 5.4.2 Deny liability in whole or in part and notify the Owner, citing the reasons for denial.
- 6. If the Surety does not proceed as provided in Paragraph 5 with reasonable promptness, the Surety shall be deemed to be in default on this Bond seven days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Paragraph 5.4, and the Owner refuses the payment, or the Surety has denied liability, in whole or in part, without further notice, the Owner shall be entitled to enforce any remedy available to the Owner.
- 7. If the Surety elects to act under Paragraph 5.1, 5.2, or 5.3, then the responsibilities of the Surety to the Owner will not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety will not be greater than those of the Owner under the Construction Contract. Subject to the commitment by the Owner to pay the Balance of the Contract Price, the Surety is obligated, without duplication for:
 - 7.1. the responsibilities of the Contractor for correction of defective work and completion of the Construction Contract;
 - 7.2. additional legal, design professional, and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Paragraph 5; and
 - 7.3. liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- 8. If the Surety elects to act under Paragraph 5.1, 5.3, or 5.4, the Surety's liability is limited to the amount of this Bond.
- 9. The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price will not be reduced or set off on account of any such unrelated obligations. No right of action will accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, successors, and assigns.
- 10. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders, and other obligations.
- 11. Any proceeding, legal or equitable, under this Bond must be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and must be instituted within two years after a declaration of Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this paragraph are void or prohibited by law, the minimum periods of limitations available to sureties as a defense in the jurisdiction of the suit will be applicable.
- 12. Notice to the Surety, the Owner, or the Contractor must be mailed or delivered to the address shown on the page on which their signature appears.
- 13. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement will be deemed deleted therefrom and provisions conforming to such

statutory or other legal requirement will be deemed incorporated herein. When so furnished, the intent is that this Bond will be construed as a statutory bond and not as a common law bond.

14. Definitions

- 14.1. *Balance of the Contract Price*—The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made including allowance for the Contractor for any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.
 - 14.2. *Construction Contract*—The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and changes made to the agreement and the Contract Documents.
 - 14.3. *Contractor Default*—Failure of the Contractor, which has not been remedied or waived, to perform or otherwise to comply with a material term of the Construction Contract.
 - 14.4. *Owner Default*—Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
 - 14.5. *Contract Documents*—All the documents that comprise the agreement between the Owner and Contractor.
15. If this Bond is issued for an agreement between a contractor and subcontractor, the term Contractor in this Bond will be deemed to be Subcontractor and the term Owner will be deemed to be Contractor.
16. Modifications to this Bond are as follows: **None**

PAYMENT BOND

Contractor Name: [Full formal name of Contractor] Address <i>(as registered w/ Secretary of State, if applicable)</i> : [Address of Contractor]	Surety Name: [Full formal name of Surety] Address <i>(as registered w/ Secretary of State, if applicable)</i> : [Address of Surety]
Owner Name: City of Raleigh Mailing address: 222 W. Hargett Street Raleigh, NC 27601	Contract Description <i>(name and location)</i> : [Owner's project/contract name, and location of the project] Contract Price: [Amount, from Contract] Effective Date of Contract: [Date, from Contract]
Bond Bond Amount: [Amount] Date of Bond: [Date] <i>(Date of Bond cannot be earlier than Effective Date of Contract)</i> Modifications to this Bond form: ☐ None ☐ See Paragraph 18	
Surety and Contractor, intending to be legally bound hereby, subject to the terms set forth in this Payment Bond, do each cause this Payment Bond to be duly executed by an authorized officer, agent, or representative.	
Contractor as Principal	Surety
<i>(Full formal name of Contractor)</i>	<i>(Full formal name of Surety) (corporate seal)</i>
By: _____ <i>(Signature)</i>	By: _____ <i>(Signature)(Attach Power of Attorney)</i>
Name: _____ <i>(Printed or typed)</i>	Name: _____ <i>(Printed or typed)</i>
Title: _____	Title: _____
Attest: _____ <i>(Signature)</i>	Attest: _____ <i>(Signature)</i>
Name: _____ <i>(Printed or typed)</i>	Name: _____ <i>(Printed or typed)</i>
Title: _____	Title: _____
<i>Notes: (1) Provide supplemental execution by any additional parties, such as joint venturers. (2) Any singular reference to Contractor, Surety, Owner, or other party is considered plural where applicable.</i>	

1. The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to the Owner to pay for labor, materials, and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference, subject to the following terms.
2. If the Contractor promptly makes payment of all sums due to Claimants, and defends, indemnifies, and holds harmless the Owner from claims, demands, liens, or suits by any person or entity seeking payment for labor, materials, or equipment furnished for use in the performance of the Construction Contract, then the Surety and the Contractor shall have no obligation under this Bond.
3. If there is no Owner Default under the Construction Contract, the Surety's obligation to the Owner under this Bond will arise after the Owner has promptly notified the Contractor and the Surety (at the address described in Paragraph 13) of claims, demands, liens, or suits against the Owner or the Owner's property by any person or entity seeking payment for labor, materials, or equipment furnished for use in the performance of the Construction Contract, and tendered defense of such claims, demands, liens, or suits to the Contractor and the Surety.
4. When the Owner has satisfied the conditions in Paragraph 3, the Surety shall promptly and at the Surety's expense defend, indemnify, and hold harmless the Owner against a duly tendered claim, demand, lien, or suit.
5. The Surety's obligations to a Claimant under this Bond will arise after the following:
 - 5.1. Claimants who do not have a direct contract with the Contractor
 - 5.1.1. have furnished a written notice of non-payment to the Contractor, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were, or equipment was, furnished or supplied or for whom the labor was done or performed, within ninety (90) days after having last performed labor or last furnished materials or equipment included in the Claim; and
 - 5.1.2. have sent a Claim to the Surety (at the address described in Paragraph 13).
 - 5.2. Claimants who are employed by or have a direct contract with the Contractor have sent a Claim to the Surety (at the address described in Paragraph 13).
6. If a notice of non-payment required by Paragraph 5.1.1 is given by the Owner to the Contractor, that ~~is shall be~~ sufficient to satisfy a Claimant's obligation to furnish a written notice of non-payment under Paragraph 5.1.1.
7. When a Claimant has satisfied the conditions of Paragraph 5.1 or 5.2, whichever is applicable, the Surety shall promptly and at the Surety's expense take the following actions:
 - 7.1. Send an answer to the Claimant, with a copy to the Owner, within sixty (60) days after receipt of the Claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed; and
 - 7.2. Pay or arrange for payment of any undisputed amounts.
 - 7.3. The Surety's failure to discharge its obligations under Paragraph 7.1 or 7.2 will not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a Claim, except as to undisputed amounts for which the Surety and Claimant have reached agreement. If, however, the Surety fails to discharge its obligations under Paragraph 7.1 or 7.2, the Surety

shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs thereafter to recover any sums found to be due and owing to the Claimant.

8. The Surety's total obligation will not exceed the amount of this Bond, plus the amount of reasonable attorney's fees provided under Paragraph 7.3, and the amount of this Bond will be credited for any payments made in good faith by the Surety.
9. Amounts owed by the Owner to the Contractor under the Construction Contract will be used for the performance of the Construction Contract and to satisfy claims, if any, under any construction performance bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfying obligations of the Contractor and Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.
10. The Surety shall not be liable to the Owner, Claimants, or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for the payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligation to make payments to or give notice on behalf of Claimants, or otherwise have any obligations to Claimants under this Bond.
11. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders, and other obligations.
12. No suit or action will be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the state in which the project that is the subject of the Construction Contract is located or after the expiration of one year from the date (1) on which the Claimant sent a Claim to the Surety pursuant to Paragraph 5.1.2 or 5.2, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit will be applicable.
13. Notice and Claims to the Surety, the Owner, or the Contractor must be mailed or delivered to the address shown on the page on which their signature appears. Actual receipt of notice or Claims, however accomplished, will be sufficient compliance as of the date received.
14. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement will be deemed deleted here from and provisions conforming to such statutory or other legal requirement will be deemed incorporated herein. When so furnished, the intent is that this Bond will be construed as a statutory bond and not as a common law bond.
15. Upon requests by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor and Owner shall promptly furnish a copy of this Bond or shall permit a copy to be made.
16. Definitions
 - 16.1. *Claim*—A written statement by the Claimant including at a minimum:
 - 16.1.1. The name of the Claimant;
 - 16.1.2. The name of the person for whom the labor was done, or materials or equipment furnished;

- 16.1.3. A copy of the agreement or purchase order pursuant to which labor, materials, or equipment was furnished for use in the performance of the Construction Contract;
 - 16.1.4. A brief description of the labor, materials, or equipment furnished;
 - 16.1.5. The date on which the Claimant last performed labor or last furnished materials or equipment for use in the performance of the Construction Contract;
 - 16.1.6. The total amount earned by the Claimant for labor, materials, or equipment furnished as of the date of the Claim;
 - 16.1.7. The total amount of previous payments received by the Claimant; and
 - 16.1.8. The total amount due and unpaid to the Claimant for labor, materials, or equipment furnished as of the date of the Claim.
- 16.2. *Claimant*—An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials, or equipment for use in the performance of the Construction Contract. The term Claimant also includes any individual or entity that has rightfully asserted a claim under an applicable mechanic's lien or similar statute against the real property upon which the Project is located. The intent of this Bond is to include without limitation in the terms of "labor, materials, or equipment" that part of the water, gas, power, light, heat, oil, gasoline, telephone service, or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials, or equipment were furnished.
- 16.3. *Construction Contract*—The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and all changes made to the agreement and the Contract Documents.
- 16.4. *Owner Default*—Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.
- 16.5. *Contract Documents*—All the documents that comprise the agreement between the Owner and Contractor.
17. If this Bond is issued for an agreement between a contractor and subcontractor, the term Contractor in this Bond will be deemed to be Subcontractor and the term Owner will be deemed to be Contractor.
18. Modifications to this Bond are as follows: **None**

AFFIDAVIT

(To be attached to all Contracts)

STATE OF _____)
) SS
COUNTY OF _____)

_____ being first duly sworn on oath deposes and says that (s)he is _____

(attorney-in-fact or agent) of _____

(bonding company) surety on the attached Contract on _____

_____ executed by _____ (Contractor).

Affiant further deposes and says that no officer, official, or employee of the Owner has any direct or indirect interest, or is receiving any premium, commission, fee, or other thing of value on account of the same or the furnishing of the Bond, undertaking, contract of indemnity, guaranty, or suretyship in connection with the above-mentioned contract.

Signed _____

Subscribed and sworn to before me this _____ day of _____, A.D., 20_____.

(Notary Public, _____ County, _____)

My Commission Expires _____.

PAGE FOR ATTACHING
CERTIFICATE OF INSURANCE

Contractor's Application for Payment

Owner: _____ Engineer: _____ Contractor: _____ Project: _____ Contract: _____	Owner's Project No.: _____ Engineer's Project No.: _____ Contractor's Project No.: _____																																				
Application No.: _____ Application Date: _____																																					
Application Period: From _____ to _____																																					
<table border="1" style="width: 100%; border-collapse: collapse;"><tr><td style="width: 70%;">1. Original Contract Price</td><td style="width: 10%; text-align: center;">\$</td><td style="width: 20%; text-align: right;">-</td></tr><tr><td>2. Net change by Change Orders</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>3. Current Contract Price (Line 1 + Line 2)</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>4. Total Work completed and materials stored to date (Sum of Column G Lump Sum Total and Column J Unit Price Total)</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>5. Retainage</td><td></td><td></td></tr><tr><td> a. _____ X \$ _____ Work Completed</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td> b. _____ X \$ _____ Stored Materials</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td> c. Total Retainage (Line 5.a + Line 5.b)</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>6. Amount eligible to date (Line 4 - Line 5.c)</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>7. Less previous payments (Line 6 from prior application)</td><td></td><td></td></tr><tr><td>8. Amount due this application</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr><tr><td>9. Balance to finish, including retainage (Line 3 - Line 4)</td><td style="text-align: center;">\$</td><td style="text-align: right;">-</td></tr></table>		1. Original Contract Price	\$	-	2. Net change by Change Orders	\$	-	3. Current Contract Price (Line 1 + Line 2)	\$	-	4. Total Work completed and materials stored to date (Sum of Column G Lump Sum Total and Column J Unit Price Total)	\$	-	5. Retainage			a. _____ X \$ _____ Work Completed	\$	-	b. _____ X \$ _____ Stored Materials	\$	-	c. Total Retainage (Line 5.a + Line 5.b)	\$	-	6. Amount eligible to date (Line 4 - Line 5.c)	\$	-	7. Less previous payments (Line 6 from prior application)			8. Amount due this application	\$	-	9. Balance to finish, including retainage (Line 3 - Line 4)	\$	-
1. Original Contract Price	\$	-																																			
2. Net change by Change Orders	\$	-																																			
3. Current Contract Price (Line 1 + Line 2)	\$	-																																			
4. Total Work completed and materials stored to date (Sum of Column G Lump Sum Total and Column J Unit Price Total)	\$	-																																			
5. Retainage																																					
a. _____ X \$ _____ Work Completed	\$	-																																			
b. _____ X \$ _____ Stored Materials	\$	-																																			
c. Total Retainage (Line 5.a + Line 5.b)	\$	-																																			
6. Amount eligible to date (Line 4 - Line 5.c)	\$	-																																			
7. Less previous payments (Line 6 from prior application)																																					
8. Amount due this application	\$	-																																			
9. Balance to finish, including retainage (Line 3 - Line 4)	\$	-																																			
Contractor's Certification The undersigned Contractor certifies, to the best of its knowledge, the following: (1) All previous progress payments received from Owner on account of Work done under the Contract have been applied on account to discharge Contractor's legitimate obligations incurred in connection with the Work covered by prior Applications for Payment; (2) Title to all Work, materials and equipment incorporated in said Work, or otherwise listed in or covered by this Application for Payment, will pass to Owner at time of payment free and clear of all liens, security interests, and encumbrances (except such as are covered by a bond acceptable to Owner indemnifying Owner against any such liens, security interest, or encumbrances); and (3) All the Work covered by this Application for Payment is in accordance with the Contract Documents and is not defective.																																					
Contractor: _____																																					
Signature: _____ Date: _____																																					
Recommended by Engineer By: _____ Title: _____ Date: _____	Approved by Owner By: _____ Title: _____ Date: _____																																				
Approved by Funding Agency By: _____ Title: _____ Date: _____	By: _____ Title: _____ Date: _____																																				

Progress Estimate - Lump Sum Work

Contractor's Application for Payment

Owner: _____ Engineer: _____ Contractor: _____ Project: _____ Contract: _____						Owner's Project No.: _____ Engineer's Project No.: _____ Contractor's Project No.: _____		
Application No.: _____		Application Period: From _____ to _____		Application Date: _____				
A	B	C	D	E	F	G	H	I
Item No.	Description	Scheduled Value (\$)	Work Completed		Materials Currently Stored (not in D or E) (\$)	Work Completed and Materials Stored to Date (D + E + F) (\$)	% of Scheduled Value (G / C) (%)	Balance to Finish (C - G) (\$)
			(D + E) From Previous Application (\$)	This Period (\$)				
Original Contract								
			-			-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
Original Contract Totals		\$ -	\$ -	\$ -	\$ -	\$ -		\$ -

Progress Estimate - Lump Sum Work

Contractor's Application for Payment

Owner: _____ Engineer: _____ Contractor: _____ Project: _____ Contract: _____						Owner's Project No.: _____ Engineer's Project No.: _____ Contractor's Project No.: _____		
Application No.: _____		Application Period: From _____ to _____		Application Date: _____				
A	B	C	D	E	F	G	H	I
Item No.	Description	Scheduled Value (\$)	Work Completed		Materials Currently Stored (not in D or E) (\$)	Work Completed and Materials Stored to Date (D + E + F) (\$)	% of Scheduled Value (G / C) (%)	Balance to Finish (C - G) (\$)
			(D + E) From Previous Application (\$)	This Period (\$)				
Change Orders								
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
						-		-
Change Order Totals		\$ -	\$ -	\$ -	\$ -	\$ -		\$ -
Original Contract and Change Orders								
Project Totals		\$ -	\$ -	\$ -	\$ -	\$ -		\$ -

Progress Estimate - Unit Price Work

Contractor's Application for Payment

Owner:		Owner's Project No.:	
Engineer:		Engineer's Project No.:	
Contractor:		Contractor's Project No.:	
Project:			
Contract:			

Application No.:		Application Period:		From		to		Application Date:			
A	B	C	D	E	F	G	H	I	J	K	L
Bid Item No.	Description	Contract Information				Work Completed		Materials Currently Stored (not in G) (\$)	Work Completed and Materials Stored to Date (H + I) (\$)	% of Value of Item (J / F) (%)	Balance to Finish (F - J) (\$)
		Item Quantity	Units	Unit Price (\$)	Value of Bid Item (C X E) (\$)	Estimated Quantity Incorporated in the Work	Value of Work Completed to Date (E X G) (\$)				
Original Contract											
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		

Progress Estimate - Unit Price Work

Contractor's Application for Payment

Owner:		Owner's Project No.:	
Engineer:		Engineer's Project No.:	
Contractor:		Contractor's Project No.:	
Project:			
Contract:			

Application No.:		Application Period:		From		to		Application Date:			
A	B	C	D	E	F	G	H	I	J	K	L
Bid Item No.	Description	Contract Information				Work Completed		Materials Currently Stored (not in G) (\$)	Work Completed and Materials Stored to Date (H + I) (\$)	% of Value of Item (J / F) (%)	Balance to Finish (L - J) (\$)
		Item Quantity	Units	Unit Price (\$)	Value of Bid Item (C X E) (\$)	Estimated Quantity Incorporated in the Work	Value of Work Completed to Date (E X G) (\$)				
Change Orders											
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-		-
					-		-		-</		

Stored Materials Summary

Contractor's Application for Payment

Owner: _____						Owner's Project No.: _____							
Engineer: _____						Engineer's Project No.: _____							
Contractor: _____						Contractor's Project No.: _____							
Project: _____													
Contract: _____													
Application No.: _____		Application Period: From _____ to _____				Application Date: _____							
A	B	C	D	E	F	G	H	I	J	K	L	M	
Item No. (Lump Sum Tab) or Bid Item No. (Unit Price Tab)	Supplier Invoice No.	Submittal No. (with Specification Section No.)	Description of Materials or Equipment Stored	Storage Location	Application No. When Materials Placed in Storage	Materials Stored			Incorporated in Work			Materials Remaining in Storage (I-L) (\$)	
						Previous Amount Stored (\$)	Amount Stored this Period (\$)	Amount Stored to Date (G+H) (\$)	Amount Previously Incorporated in the Work (\$)	Amount Incorporated in the Work this Period (\$)	Total Amount Incorporated in the Work (J+K) (\$)		
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
								-			-	-	
Totals						\$	-	\$	-	\$	-	\$	-

APPENDIX E - CERTIFIED SUBCONTRACTOR PAYMENT FORM

****SUBMIT WITH EACH PAYMENT REQUEST AND FINAL PAYMENT****

City of Raleigh MWBE Report For Subcontractor Payments

Prime Contractor: _____

City of Raleigh Contract ID Number: _____

Total Contract Amount: \$ _____

City of Raleigh Project Manager Name: _____

Total MWBE Subcontractor Amount: \$_____ Total MWBE _____%

City of Raleigh Project Name: _____

Prime Contractor's Pay Application Number: _____

Thru Date:_____

Project Completed Date: _____

The Prime Contractor shall list below all payments for work completed by MWBEs including amounts requested for this pay application period.

[illegible]

MWBE Categories: American Indian (IA), Asian American (AA), Black African-American (B), Hispanic (H), Non-Minority (NMF), Socially and Economic Disadvantaged (D)

Date: _____

Submitted By: _____

Title: _____

Signature: _____

CERTIFICATE OF SUBSTANTIAL COMPLETION

Owner: **City of Raleigh** Owner's Project No.:
Engineer: Engineer's Project No.:
Contractor: Contractor's Project No.:
Project: Neuse River RRF Roof Replacements,
Filter & Blower Buildings
Contract Name:

This ☐ Preliminary ☐ Final Certificate of Substantial Completion applies to:

☐ All Work ☐ The following specified portions of the Work:

[Describe the portion of the work for which Certificate of Substantial Completion is issued]

Date of Substantial Completion: **[Enter date, as determined by Engineer]**

The Work to which this Certificate applies has been inspected by authorized representatives of Owner, Contractor, and Engineer, and found to be substantially complete. The Date of Substantial Completion of the Work or portion thereof designated above is hereby established, subject to the provisions of the Contract pertaining to Substantial Completion. The date of Substantial Completion in the final Certificate of Substantial Completion marks the commencement of the contractual correction period and applicable warranties required by the Contract.

A punch list of items to be completed or corrected is attached to this Certificate. This list may not be all-inclusive, and the failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

Amendments of contractual responsibilities recorded in this Certificate should be the product of mutual agreement of Owner and Contractor; see Paragraph 15.03.D of the General Conditions.

The responsibilities between Owner and Contractor for security, operation, safety, maintenance, heat, utilities, insurance, and warranties upon Owner's use or occupancy of the Work must be as provided in the Contract, except as amended as follows:

Amendments to Owner's Responsibilities: ☐ None ☐ As follows:

[List amendments to Owner's Responsibilities]

Amendments to Contractor's Responsibilities: ☐ None ☐ As follows:

[List amendments to Contractor's Responsibilities]

The following documents are attached to and made a part of this Certificate:

[List attachments such as punch list; other documents]

This Certificate does not constitute an acceptance of Work not in accordance with the Contract Documents, nor is it a release of Contractor's obligation to complete the Work in accordance with the Contract Documents.

Engineer

By *(signature)*: _____
Name *(printed)*: _____
Title: _____

PAGE FOR ATTACHING

POWER OF ATTORNEY

*Note: If the recorded POA from the Register of Deeds
is attached, page 00634-2 is not necessary.*

STATE OF NORTH CAROLINA
COUNTY OF _____

This is to certify that on the _____ day of _____, 20__, before me personally appeared before me to the undersigned Notary Public, _____ who, being first duly sworn, acknowledged the due execution of the foregoing instrument for the purpose therein stated.

Witness my hand and notarial seal this the _____ day of _____, 20__.

(SEAL)

Notary Public

My Commission Expires:

STATE OF NORTH CAROLINA
COUNTY OF _____

This is to certify that on the _____ day of _____, 20__, before me personally came _____, with whom I am personally acquainted, who, being by me duly sworn, says that (s)he is the President and _____ is the Secretary of _____, Incorporated, the corporation described in and which executed the foregoing instrument; that (s)he knows the common seal of said corporation; that the seal affixed to the foregoing instrument is said common seal, and the name of the corporation was subscribed thereto by the said Secretary and the said corporate seal was affixed, all by order of the Board of Directors of said corporation, and that the said instrument is the act and deed of said corporation.

Witness my hand and notarial seal this the _____ day of _____, 20__.

(SEAL)

Notary Public

My Commission Expires:

STATE OF NORTH CAROLINA
COUNTY OF _____

I, _____, a Notary Public duly commissioned and qualified to act in _____ County, State of _____, do hereby certify that _____, Attorney-in Fact for _____, a corporation, personally appeared before me this day, and being by me duly sworn, says that (s)he executed the foregoing and attached Payment and Performance Bonds, dated _____, 20__, for and in behalf of _____ as Surety and that his authority to execute and acknowledge said Bonds is contained in an instrument duly executed, acknowledged, and recorded in the Office of Register of Deeds of _____ County, State of _____, on the _____ day of _____, 20__, being recorded in Book Number _____, Page _____, of said Registry, and that the foregoing and attached Bonds were executed under and by virtue of the authority given by said instrument granting (him) (her) the said _____, Power of Attorney; and that the said _____, Attorney-in-Fact, acknowledged the due execution of the foregoing and annexed Bonds for the purpose therein expressed for and in behalf of said _____.

Witness my hand and notarial seal this the _____ day of _____, 20__.

(SEAL)

Notary Public

My Commission Expires:

00700
STANDARD GENERAL CONDITIONS
OF THE CONSTRUCTION CONTRACT

TABLE OF CONTENTS

	Page
Article 1—Definitions and Terminology.....	1
1.01 Defined Terms.....	1
1.02 Terminology	6
Article 2—Preliminary Matters	7
2.01 Delivery of Performance and Payment Bonds; Evidence of Insurance.....	7
2.02 Copies of Documents	7
2.03 Before Starting Construction	7
2.04 Preconstruction Conference; Designation of Authorized Representatives	8
2.05 Acceptance of Schedules	8
2.06 Electronic Transmittals	8
Article 3—Contract Documents: Intent, Requirements, Reuse.....	9
3.01 Intent.....	9
3.02 Reference Standards.....	9
3.03 Reporting and Resolving Discrepancies	10
3.04 Requirements of the Contract Documents.....	10
3.05 Reuse of Documents	11
Article 4—Commencement and Progress of the Work	11
4.01 Commencement of Contract Times; Notice to Proceed.....	11
4.02 Starting the Work.....	11
4.03 Reference Points	11
4.04 Progress Schedule	12
4.05 Delays in Contractor’s Progress	12
Article 5—Site; Subsurface and Physical Conditions; Hazardous Environmental Conditions	13
5.01 Availability of Lands	13
5.02 Use of Site and Other Areas.....	14
5.03 Subsurface and Physical Conditions.....	15

5.04	Differing Subsurface or Physical Conditions	16
5.05	Underground Facilities	17
5.06	Hazardous Environmental Conditions at Site	19
Article 6—Bonds and Insurance		21
6.01	Performance, Payment, and Other Bonds	21
6.02	Insurance—General Provisions	22
6.03	Contractor’s Insurance	24
6.04	Builder’s Risk and Other Property Insurance	25
6.05	Property Losses; Subrogation	25
6.06	Receipt and Application of Property Insurance Proceeds	27
Article 7—Contractor’s Responsibilities		27
7.01	Contractor’s Means and Methods of Construction	27
7.02	Supervision and Superintendence	27
7.03	Labor; Working Hours	27
7.04	Services, Materials, and Equipment	28
7.05	“Or Equals”	28
7.06	Substitutes	29
7.07	Concerning Subcontractors and Suppliers	31
7.08	Patent Fees and Royalties	32
7.09	Permits	33
7.10	Taxes	33
7.11	Laws and Regulations	33
7.12	Record Documents	33
7.13	Safety and Protection	34
7.14	Hazard Communication Programs	35
7.15	Emergencies	35
7.16	Submittals	35
7.17	Contractor’s General Warranty and Guarantee	38
7.18	Indemnification	39
7.19	Delegation of Professional Design Services	39
Article 8—Other Work at the Site		40
8.01	Other Work	40
8.02	Coordination	41

8.03	Legal Relationships.....	41
Article 9—Owner’s Responsibilities.....		42
9.01	Communications to Contractor	42
9.02	Replacement of Engineer.....	42
9.03	Furnish Data	42
9.04	Pay When Due.....	42
9.05	Lands and Easements; Reports, Tests, and Drawings.....	43
9.06	Insurance.....	43
9.07	Change Orders	43
9.08	Inspections, Tests, and Approvals.....	43
9.09	Limitations on Owner’s Responsibilities	43
9.10	Undisclosed Hazardous Environmental Condition.....	43
9.11	Evidence of Financial Arrangements.....	43
9.12	Safety Programs	43
Article 10—Engineer’s Status During Construction		44
10.01	Owner’s Representative.....	44
10.02	Visits to Site.....	44
10.03	Resident Project Representative.....	44
10.04	Engineer’s Authority	44
10.05	Determinations for Unit Price Work	45
10.06	Decisions on Requirements of Contract Documents and Acceptability of Work	45
10.07	Limitations on Engineer’s Authority and Responsibilities	45
10.08	Compliance with Safety Program.....	45
Article 11—Changes to the Contract		46
11.01	Amending and Supplementing the Contract	46
11.02	Change Orders	46
11.03	Work Change Directives.....	46
11.04	Field Orders.....	47
11.05	Owner-Authorized Changes in the Work.....	47
11.06	Unauthorized Changes in the Work.....	47
11.07	Change of Contract Price	47
11.08	Change of Contract Times.....	49
11.09	Change Proposals.....	49

11.10	Notification to Surety.....	50
Article 12—Claims.....		50
12.01	Claims	50
Article 13—Cost of the Work; Allowances; Unit Price Work		51
13.01	Cost of the Work	51
13.02	Allowances	55
13.03	Unit Price Work	55
Article 14—Tests and Inspections; Correction, Removal, or Acceptance of Defective Work		56
14.01	Access to Work.....	56
14.02	Tests, Inspections, and Approvals.....	56
14.03	Defective Work	57
14.04	Acceptance of Defective Work.....	58
14.05	Uncovering Work	58
14.06	Owner May Stop the Work	58
14.07	Owner May Correct Defective Work.....	59
Article 15—Payments to Contractor; Set-Offs; Completion; Correction Period		59
15.01	Progress Payments.....	59
15.02	Contractor’s Warranty of Title	62
15.03	Substantial Completion.....	62
15.04	Partial Use or Occupancy	63
15.05	Final Inspection	64
15.06	Final Payment.....	64
15.07	Waiver of Claims	65
15.08	Correction Period	66
Article 16—Suspension of Work and Termination		67
16.01	Owner May Suspend Work	67
16.02	Owner May Terminate for Cause.....	67
16.03	Owner May Terminate for Convenience.....	68
16.04	Contractor May Stop Work or Terminate	68
Article 17—Final Resolution of Disputes		69
17.01	Methods and Procedures.....	69
Article 18—Miscellaneous		69
18.01	Giving Notice	69

18.02	Computation of Times.....	69
18.03	Cumulative Remedies	70
18.04	Limitation of Damages	70
18.05	No Waiver	70
18.06	Survival of Obligations	70
18.07	Controlling Law	70
18.08	Assignment of Contract.....	70
18.09	Successors and Assigns	70
18.10	Headings.....	70

STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

ARTICLE 1—DEFINITIONS AND TERMINOLOGY

1.01 *Defined Terms*

- A. Wherever used in the Bidding Requirements or Contract Documents, a term printed with initial capital letters, including the term's singular and plural forms, will have the meaning indicated in the definitions below. In addition to terms specifically defined, terms with initial capital letters in the Contract Documents include references to identified articles and paragraphs, and the titles of other documents or forms.
1. *Addenda*—Written or graphic instruments issued prior to the opening of Bids which clarify, correct, or change the Bidding Requirements or the proposed Contract Documents.
 2. *Agreement*—The written instrument, executed by Owner and Contractor, that sets forth the Contract Price and Contract Times, identifies the parties and the Engineer, and designates the specific items that are Contract Documents.
 3. *Application for Payment*—The document prepared by Contractor, in a form acceptable to Engineer, to request progress or final payments, and which is to be accompanied by such supporting documentation as is required by the Contract Documents.
 4. *Bid*—The offer of a Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.
 5. *Bidder*—An individual or entity that submits a Bid to Owner.
 6. *Bidding Documents*—The Bidding Requirements, the proposed Contract Documents, and all Addenda.
 7. *Bidding Requirements*—The Advertisement or invitation to bid, Instructions to Bidders, Bid Bond or other Bid security, if any, the Bid Form, and the Bid with any attachments.
 8. *Change Order*—A document which is signed by Contractor and Owner and authorizes an addition, deletion, or revision in the Work or an adjustment in the Contract Price or the Contract Times, or other revision to the Contract, issued on or after the Effective Date of the Contract.
 9. *Change Proposal*—A written request by Contractor, duly submitted in compliance with the procedural requirements set forth herein, seeking an adjustment in Contract Price or Contract Times; contesting an initial decision by Engineer concerning the requirements of the Contract Documents or the acceptability of Work under the Contract Documents; challenging a set-off against payments due; or seeking other relief with respect to the terms of the Contract.
 10. *Claim*
 - a. A demand or assertion by Owner directly to Contractor, duly submitted in compliance with the procedural requirements set forth herein, seeking an adjustment of Contract Price or Contract Times; contesting an initial decision by Engineer concerning the

requirements of the Contract Documents or the acceptability of Work under the Contract Documents; contesting Engineer's decision regarding a Change Proposal; seeking resolution of a contractual issue that Engineer has declined to address; or seeking other relief with respect to the terms of the Contract.

- b. A demand or assertion by Contractor directly to Owner, duly submitted in compliance with the procedural requirements set forth herein, contesting Engineer's decision regarding a Change Proposal, or seeking resolution of a contractual issue that Engineer has declined to address.
 - c. A demand or assertion by Owner or Contractor, duly submitted in compliance with the procedural requirements set forth herein, made pursuant to Paragraph 12.01.A.4, concerning disputes arising after Engineer has issued a recommendation of final payment.
 - d. A demand for money or services by a third party is not a Claim.
- 11. *Constituent of Concern*—Asbestos, petroleum, radioactive materials, polychlorinated biphenyls (PCBs), lead-based paint (as defined by the HUD/EPA standard), hazardous waste, and any substance, product, waste, or other material of any nature whatsoever that is or becomes listed, regulated, or addressed pursuant to Laws and Regulations regulating, relating to, or imposing liability or standards of conduct concerning, any hazardous, toxic, or dangerous waste, substance, or material.
 - 12. *Contract*—The entire and integrated written contract between Owner and Contractor concerning the Work.
 - 13. *Contract Documents*—Those items so designated in the Agreement, and which together comprise the Contract.
 - 14. *Contract Price*—The money that Owner has agreed to pay Contractor for completion of the Work in accordance with the Contract Documents.
 - 15. *Contract Times*—The number of days or the dates by which Contractor shall: (a) achieve Milestones, if any; (b) achieve Substantial Completion; and (c) complete the Work.
 - 16. *Contractor*—The individual or entity with which Owner has contracted for performance of the Work.
 - 17. *Cost of the Work*—See Paragraph 13.01 for definition.
 - 18. *Drawings*—The part of the Contract that graphically shows the scope, extent, and character of the Work to be performed by Contractor.
 - 19. *Effective Date of the Contract*—The date, indicated in the Agreement, on which the Contract becomes effective.
 - 20. *Electronic Document*—Any Project-related correspondence, attachments to correspondence, data, documents, drawings, information, or graphics, including but not limited to Shop Drawings and other Submittals, that are in an electronic or digital format.
 - 21. *Electronic Means*—Electronic mail (email), upload/download from a secure Project website, or other communications methods that allow: (a) the transmission or communication of Electronic Documents; (b) the documentation of transmissions, including sending and receipt; (c) printing of the transmitted Electronic Document by the

recipient; (d) the storage and archiving of the Electronic Document by sender and recipient; and (e) the use by recipient of the Electronic Document for purposes permitted by this Contract. Electronic Means does not include the use of text messaging, or of Facebook, Twitter, Instagram, or similar social media services for transmission of Electronic Documents.

22. *Engineer*—The individual or entity named as such in the Agreement.
23. *Field Order*—A written order issued by Engineer which requires minor changes in the Work but does not change the Contract Price or the Contract Times.
24. *Hazardous Environmental Condition*—The presence at the Site of Constituents of Concern in such quantities or circumstances that may present a danger to persons or property exposed thereto.
 - a. The presence at the Site of materials that are necessary for the execution of the Work, or that are to be incorporated into the Work, and that are controlled and contained pursuant to industry practices, Laws and Regulations, and the requirements of the Contract, is not a Hazardous Environmental Condition.
 - b. The presence of Constituents of Concern that are to be removed or remediated as part of the Work is not a Hazardous Environmental Condition.
 - c. The presence of Constituents of Concern as part of the routine, anticipated, and obvious working conditions at the Site, is not a Hazardous Environmental Condition.
25. *Laws and Regulations; Laws or Regulations*—Any and all applicable laws, statutes, rules, regulations, ordinances, codes, and binding decrees, resolutions, and orders of any and all governmental bodies, agencies, authorities, and courts having jurisdiction.
26. *Liens*—Charges, security interests, or encumbrances upon Contract-related funds, real property, or personal property.
27. *Milestone*—A principal event in the performance of the Work that the Contract requires Contractor to achieve by an intermediate completion date, or by a time prior to Substantial Completion of all the Work.
28. *Notice of Award*—The written notice by Owner to a Bidder of Owner's acceptance of the Bid.
29. *Notice to Proceed*—A written notice by Owner to Contractor fixing the date on which the Contract Times will commence to run and on which Contractor shall start to perform the Work.
30. *Owner*—The individual or entity with which Contractor has contracted regarding the Work, and which has agreed to pay Contractor for the performance of the Work, pursuant to the terms of the Contract.
31. *Progress Schedule*—A schedule, prepared and maintained by Contractor, describing the sequence and duration of the activities comprising Contractor's plan to accomplish the Work within the Contract Times.
32. *Project*—The total undertaking to be accomplished for Owner by engineers, contractors, and others, including planning, study, design, construction, testing, commissioning, and start-up, and of which the Work to be performed under the Contract Documents is a part.

33. *Resident Project Representative*—The authorized representative of Engineer assigned to assist Engineer at the Site. As used herein, the term Resident Project Representative (RPR) includes any assistants or field staff of Resident Project Representative.
34. *Samples*—Physical examples of materials, equipment, or workmanship that are representative of some portion of the Work and that establish the standards by which such portion of the Work will be judged.
35. *Schedule of Submittals*—A schedule, prepared and maintained by Contractor, of required submittals and the time requirements for Engineer’s review of the submittals.
36. *Schedule of Values*—A schedule, prepared and maintained by Contractor, allocating portions of the Contract Price to various portions of the Work and used as the basis for reviewing Contractor’s Applications for Payment.
37. *Shop Drawings*—All drawings, diagrams, illustrations, schedules, and other data or information that are specifically prepared or assembled by or for Contractor and submitted by Contractor to illustrate some portion of the Work. Shop Drawings, whether approved or not, are not Drawings and are not Contract Documents.
38. *Site*—Lands or areas indicated in the Contract Documents as being furnished by Owner upon which the Work is to be performed, including rights-of-way and easements, and such other lands or areas furnished by Owner which are designated for the use of Contractor.
39. *Specifications*—The part of the Contract that consists of written requirements for materials, equipment, systems, standards, and workmanship as applied to the Work, and certain administrative requirements and procedural matters applicable to the Work.
40. *Subcontractor*—An individual or entity having a direct contract with Contractor or with any other Subcontractor for the performance of a part of the Work.
41. *Submittal*—A written or graphic document, prepared by or for Contractor, which the Contract Documents require Contractor to submit to Engineer, or that is indicated as a Submittal in the Schedule of Submittals accepted by Engineer. Submittals may include Shop Drawings and Samples; schedules; product data; Owner-delegated designs; sustainable design information; information on special procedures; testing plans; results of tests and evaluations, source quality-control testing and inspections, and field or Site quality-control testing and inspections; warranties and certifications; Suppliers’ instructions and reports; records of delivery of spare parts and tools; operations and maintenance data; Project photographic documentation; record documents; and other such documents required by the Contract Documents. Submittals, whether or not approved or accepted by Engineer, are not Contract Documents. Change Proposals, Change Orders, Claims, notices, Applications for Payment, and requests for interpretation or clarification are not Submittals.
42. *Substantial Completion*—The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of Engineer, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms “substantially complete” and “substantially completed” as applied to all or part of the Work refer to Substantial Completion of such Work.

43. *Successful Bidder*—The Bidder to which the Owner makes an award of contract.
44. *Supplementary Conditions*—The part of the Contract that amends or supplements these General Conditions.
45. *Supplier*—A manufacturer, fabricator, supplier, distributor, or vendor having a direct contract with Contractor or with any Subcontractor to furnish materials or equipment to be incorporated in the Work by Contractor or a Subcontractor.
46. *Technical Data*
- a. Those items expressly identified as Technical Data in the Supplementary Conditions, with respect to either (1) existing subsurface conditions at or adjacent to the Site, or existing physical conditions at or adjacent to the Site including existing surface or subsurface structures (except Underground Facilities) or (2) Hazardous Environmental Conditions at the Site.
 - b. If no such express identifications of Technical Data have been made with respect to conditions at the Site, then Technical Data is defined, with respect to conditions at the Site under Paragraphs 5.03, 5.04, and 5.06, as the data contained in boring logs, recorded measurements of subsurface water levels, assessments of the condition of subsurface facilities, laboratory test results, and other factual, objective information regarding conditions at the Site that are set forth in any geotechnical, environmental, or other Site or facilities conditions report prepared for the Project and made available to Contractor.
 - c. Information and data regarding the presence or location of Underground Facilities are not intended to be categorized, identified, or defined as Technical Data, and instead Underground Facilities are shown or indicated on the Drawings.
47. *Underground Facilities*—All active or not-in-service underground lines, pipelines, conduits, ducts, encasements, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or systems at the Site, including but not limited to those facilities or systems that produce, transmit, distribute, or convey telephone or other communications, cable television, fiber optic transmissions, power, electricity, light, heat, gases, oil, crude oil products, liquid petroleum products, water, steam, waste, wastewater, storm water, other liquids or chemicals, or traffic or other control systems. An abandoned facility or system is not an Underground Facility.
48. *Unit Price Work*—Work to be paid for on the basis of unit prices.
49. *Work*—The entire construction or the various separately identifiable parts thereof required to be provided under the Contract Documents. Work includes and is the result of performing or providing all labor, services, and documentation necessary to produce such construction; furnishing, installing, and incorporating all materials and equipment into such construction; and may include related services such as testing, start-up, and commissioning, all as required by the Contract Documents.
50. *Work Change Directive*—A written directive to Contractor issued on or after the Effective Date of the Contract, signed by Owner and recommended by Engineer, ordering an addition, deletion, or revision in the Work.

1.02 Terminology

- A. The words and terms discussed in Paragraphs 1.02.B, C, D, and E are not defined terms that require initial capital letters, but, when used in the Bidding Requirements or Contract Documents, have the indicated meaning.
- B. *Intent of Certain Terms or Adjectives:* The Contract Documents include the terms “as allowed,” “as approved,” “as ordered,” “as directed” or terms of like effect or import to authorize an exercise of professional judgment by Engineer. In addition, the adjectives “reasonable,” “suitable,” “acceptable,” “proper,” “satisfactory,” or adjectives of like effect or import are used to describe an action or determination of Engineer as to the Work. It is intended that such exercise of professional judgment, action, or determination will be solely to evaluate, in general, the Work for compliance with the information in the Contract Documents and with the design concept of the Project as a functioning whole as shown or indicated in the Contract Documents (unless there is a specific statement indicating otherwise). The use of any such term or adjective is not intended to and shall not be effective to assign to Engineer any duty or authority to supervise or direct the performance of the Work, or any duty or authority to undertake responsibility contrary to the provisions of Article 10 or any other provision of the Contract Documents.
- C. *Day:* The word “day” means a calendar day of 24 hours measured from midnight to the next midnight.
- D. *Defective:* The word “defective,” when modifying the word “Work,” refers to Work that is unsatisfactory, faulty, or deficient in that it:
 - 1. does not conform to the Contract Documents;
 - 2. does not meet the requirements of any applicable inspection, reference standard, test, or approval referred to in the Contract Documents; or
 - 3. has been damaged prior to Engineer’s recommendation of final payment (unless responsibility for the protection thereof has been assumed by Owner at Substantial Completion in accordance with Paragraph 15.03 or Paragraph 15.04).
- E. *Furnish, Install, Perform, Provide*
 - 1. The word “furnish,” when used in connection with services, materials, or equipment, means to supply and deliver said services, materials, or equipment to the Site (or some other specified location) ready for use or installation and in usable or operable condition.
 - 2. The word “install,” when used in connection with services, materials, or equipment, means to put into use or place in final position said services, materials, or equipment complete and ready for intended use.
 - 3. The words “perform” or “provide,” when used in connection with services, materials, or equipment, means to furnish and install said services, materials, or equipment complete and ready for intended use.
 - 4. If the Contract Documents establish an obligation of Contractor with respect to specific services, materials, or equipment, but do not expressly use any of the four words “furnish,” “install,” “perform,” or “provide,” then Contractor shall furnish and install said services, materials, or equipment complete and ready for intended use.

- F. *Contract Price or Contract Times*: References to a change in “Contract Price or Contract Times” or “Contract Times or Contract Price” or similar, indicate that such change applies to (1) Contract Price, (2) Contract Times, or (3) both Contract Price and Contract Times, as warranted, even if the term “or both” is not expressed.
- G. Unless stated otherwise in the Contract Documents, words or phrases that have a well-known technical or construction industry or trade meaning are used in the Contract Documents in accordance with such recognized meaning.

ARTICLE 2—PRELIMINARY MATTERS

2.01 *Delivery of Performance and Payment Bonds; Evidence of Insurance*

- A. *Performance and Payment Bonds*: When Contractor delivers the signed counterparts of the Agreement to Owner, Contractor shall also deliver to Owner the performance bond and payment bond (if the Contract requires Contractor to furnish such bonds).
- B. *Evidence of Contractor’s Insurance*: When Contractor delivers the signed counterparts of the Agreement to Owner, Contractor shall also deliver to Owner, with copies to each additional insured (as identified in the Contract), the certificates, endorsements, and other evidence of insurance required to be provided by Contractor in accordance with Article 6, except to the extent the Supplementary Conditions expressly establish other dates for delivery of specific insurance policies.
- C. *Evidence of Owner’s Insurance*: After receipt of the signed counterparts of the Agreement and all required bonds and insurance documentation, Owner shall promptly deliver to Contractor, with copies to each additional insured (as identified in the Contract), the certificates and other evidence of insurance required to be provided by Owner under Article 6.

2.02 *Copies of Documents*

- A. Owner shall furnish to Contractor four printed copies of the Contract (including one fully signed counterpart of the Agreement), and one copy in electronic portable document format (PDF). Additional printed copies will be furnished upon request at the cost of reproduction.
- B. Owner shall maintain and safeguard at least one original printed record version of the Contract, including Drawings and Specifications signed and sealed by Engineer and other design professionals. Owner shall make such original printed record version of the Contract available to Contractor for review. Owner may delegate the responsibilities under this provision to Engineer.

2.03 *Before Starting Construction*

- A. *Preliminary Schedules*: Within 10 days after the Effective Date of the Contract (or as otherwise required by the Contract Documents), Contractor shall submit to Engineer for timely review:
 - 1. a preliminary Progress Schedule indicating the times (numbers of days or dates) for starting and completing the various stages of the Work, including any Milestones specified in the Contract;
 - 2. a preliminary Schedule of Submittals; and
 - 3. a preliminary Schedule of Values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work

into component parts in sufficient detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

2.04 *Preconstruction Conference; Designation of Authorized Representatives*

- A. Before any Work at the Site is started, a conference attended by Owner, Contractor, Engineer, and others as appropriate will be held to establish a working understanding among the parties as to the Work, and to discuss the schedules referred to in Paragraph 2.03.A, procedures for handling Shop Drawings, Samples, and other Submittals, processing Applications for Payment, electronic or digital transmittals, and maintaining required records.
- B. At this conference Owner and Contractor each shall designate, in writing, a specific individual to act as its authorized representative with respect to the services and responsibilities under the Contract. Such individuals shall have the authority to transmit and receive information, render decisions relative to the Contract, and otherwise act on behalf of each respective party.

2.05 *Acceptance of Schedules*

- A. At least 10 days before submission of the first Application for Payment a conference, attended by Contractor, Engineer, and others as appropriate, will be held to review the schedules submitted in accordance with Paragraph 2.03.A. No progress payment will be made to Contractor until acceptable schedules are submitted to Engineer.
 - 1. The Progress Schedule will be acceptable to Engineer if it provides an orderly progression of the Work to completion within the Contract Times. Such acceptance will not impose on Engineer responsibility for the Progress Schedule, for sequencing, scheduling, or progress of the Work, nor interfere with or relieve Contractor from Contractor's full responsibility therefor.
 - 2. Contractor's Schedule of Submittals will be acceptable to Engineer if it provides a workable arrangement for reviewing and processing the required submittals.
 - 3. Contractor's Schedule of Values will be acceptable to Engineer as to form and substance if it provides a reasonable allocation of the Contract Price to the component parts of the Work.
 - 4. If a schedule is not acceptable, Contractor will have an additional 10 days to revise and resubmit the schedule.

2.06 *Electronic Transmittals*

- A. Except as otherwise stated elsewhere in the Contract, the Owner, Engineer, and Contractor may send, and shall accept, Electronic Documents transmitted by Electronic Means.
- B. If the Contract does not establish protocols for Electronic Means, then Owner, Engineer, and Contractor shall jointly develop such protocols.
- C. Subject to any governing protocols for Electronic Means, when transmitting Electronic Documents by Electronic Means, the transmitting party makes no representations as to long-term compatibility, usability, or readability of the Electronic Documents resulting from the recipient's use of software application packages, operating systems, or computer hardware differing from those used in the drafting or transmittal of the Electronic Documents.

ARTICLE 3—CONTRACT DOCUMENTS: INTENT, REQUIREMENTS, REUSE

3.01 *Intent*

- A. The Contract Documents are complementary; what is required by one Contract Document is as binding as if required by all.
- B. It is the intent of the Contract Documents to describe a functionally complete Project (or part thereof) to be constructed in accordance with the Contract Documents.
- C. Unless otherwise stated in the Contract Documents, if there is a discrepancy between the electronic versions of the Contract Documents (including any printed copies derived from such electronic versions) and the printed record version, the printed record version will govern.
- D. The Contract supersedes prior negotiations, representations, and agreements, whether written or oral.
- E. Engineer will issue clarifications and interpretations of the Contract Documents as provided herein.
- F. Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation will be deemed stricken, and all remaining provisions will continue to be valid and binding upon Owner and Contractor, which agree that the Contract Documents will be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.
- G. Nothing in the Contract Documents creates:
 - 1. any contractual relationship between Owner or Engineer and any Subcontractor, Supplier, or other individual or entity performing or furnishing any of the Work, for the benefit of such Subcontractor, Supplier, or other individual or entity; or
 - 2. any obligation on the part of Owner or Engineer to pay or to see to the payment of any money due any such Subcontractor, Supplier, or other individual or entity, except as may otherwise be required by Laws and Regulations.

3.02 *Reference Standards*

- A. *Standards Specifications, Codes, Laws and Regulations*
 - 1. Reference in the Contract Documents to standard specifications, manuals, reference standards, or codes of any technical society, organization, or association, or to Laws or Regulations, whether such reference be specific or by implication, means the standard specification, manual, reference standard, code, or Laws or Regulations in effect at the time of opening of Bids (or on the Effective Date of the Contract if there were no Bids), except as may be otherwise specifically stated in the Contract Documents.
 - 2. No provision of any such standard specification, manual, reference standard, or code, and no instruction of a Supplier, will be effective to change the duties or responsibilities of Owner, Contractor, or Engineer from those set forth in the part of the Contract Documents prepared by or for Engineer. No such provision or instruction shall be effective to assign to Owner or Engineer any duty or authority to supervise or direct the performance of the Work, or any duty or authority to undertake responsibility

inconsistent with the provisions of the part of the Contract Documents prepared by or for Engineer.

3.03 *Reporting and Resolving Discrepancies*

A. *Reporting Discrepancies*

1. *Contractor's Verification of Figures and Field Measurements:* Before undertaking each part of the Work, Contractor shall carefully study the Contract Documents, and check and verify pertinent figures and dimensions therein, particularly with respect to applicable field measurements. Contractor shall promptly report in writing to Engineer any conflict, error, ambiguity, or discrepancy that Contractor discovers, or has actual knowledge of, and shall not proceed with any Work affected thereby until the conflict, error, ambiguity, or discrepancy is resolved by a clarification or interpretation by Engineer, or by an amendment or supplement to the Contract issued pursuant to Paragraph 11.01.
2. *Contractor's Review of Contract Documents:* If, before or during the performance of the Work, Contractor discovers any conflict, error, ambiguity, or discrepancy within the Contract Documents, or between the Contract Documents and (a) any applicable Law or Regulation, (b) actual field conditions, (c) any standard specification, manual, reference standard, or code, or (d) any instruction of any Supplier, then Contractor shall promptly report it to Engineer in writing. Contractor shall not proceed with the Work affected thereby (except in an emergency as required by Paragraph 7.15) until the conflict, error, ambiguity, or discrepancy is resolved, by a clarification or interpretation by Engineer, or by an amendment or supplement to the Contract issued pursuant to Paragraph 11.01.
3. Contractor shall not be liable to Owner or Engineer for failure to report any conflict, error, ambiguity, or discrepancy in the Contract Documents unless Contractor had actual knowledge thereof.

B. *Resolving Discrepancies*

1. Except as may be otherwise specifically stated in the Contract Documents, the provisions of the part of the Contract Documents prepared by or for Engineer take precedence in resolving any conflict, error, ambiguity, or discrepancy between such provisions of the Contract Documents and:
 - a. the provisions of any standard specification, manual, reference standard, or code, or the instruction of any Supplier (whether or not specifically incorporated by reference as a Contract Document); or
 - b. the provisions of any Laws or Regulations applicable to the performance of the Work (unless such an interpretation of the provisions of the Contract Documents would result in violation of such Law or Regulation).

3.04 *Requirements of the Contract Documents*

- A. During the performance of the Work and until final payment, Contractor and Owner shall submit to the Engineer in writing all matters in question concerning the requirements of the Contract Documents (sometimes referred to as requests for information or interpretation—RFIs), or relating to the acceptability of the Work under the Contract Documents, as soon as possible after such matters arise. Engineer will be the initial interpreter of the requirements of the Contract Documents, and judge of the acceptability of the Work.

- B. Engineer will, with reasonable promptness, render a written clarification, interpretation, or decision on the issue submitted, or initiate an amendment or supplement to the Contract Documents. Engineer's written clarification, interpretation, or decision will be final and binding on Contractor, unless it appeals by submitting a Change Proposal, and on Owner, unless it appeals by filing a Claim.
- C. If a submitted matter in question concerns terms and conditions of the Contract Documents that do not involve (1) the performance or acceptability of the Work under the Contract Documents, (2) the design (as set forth in the Drawings, Specifications, or otherwise), or (3) other engineering or technical matters, then Engineer will promptly notify Owner and Contractor in writing that Engineer is unable to provide a decision or interpretation. If Owner and Contractor are unable to agree on resolution of such a matter in question, either party may pursue resolution as provided in Article 12.

3.05 *Reuse of Documents*

- A. Contractor and its Subcontractors and Suppliers shall not:
 - 1. have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) prepared by or bearing the seal of Engineer or its consultants, including electronic media versions, or reuse any such Drawings, Specifications, other documents, or copies thereof on extensions of the Project or any other project without written consent of Owner and Engineer and specific written verification or adaptation by Engineer; or
 - 2. have or acquire any title or ownership rights in any other Contract Documents, reuse any such Contract Documents for any purpose without Owner's express written consent, or violate any copyrights pertaining to such Contract Documents.
- B. The prohibitions of this Paragraph 3.05 will survive final payment, or termination of the Contract. Nothing herein precludes Contractor from retaining copies of the Contract Documents for record purposes.

ARTICLE 4—COMMENCEMENT AND PROGRESS OF THE WORK

4.01 *Commencement of Contract Times; Notice to Proceed*

- A. The Contract Times will commence to run on the 30th day after the Effective Date of the Contract or, if a Notice to Proceed is given, on the day indicated in the Notice to Proceed. A Notice to Proceed may be given at any time within 30 days after the Effective Date of the Contract. In no event will the Contract Times commence to run later than the 60th day after the day of Bid opening or the 30th day after the Effective Date of the Contract, whichever date is earlier.

4.02 *Starting the Work*

- A. Contractor shall start to perform the Work on the date when the Contract Times commence to run. No Work may be done at the Site prior to such date.

4.03 *Reference Points*

- A. Owner shall provide engineering surveys to establish reference points for construction which in Engineer's judgment are necessary to enable Contractor to proceed with the Work. Contractor shall be responsible for laying out the Work, shall protect and preserve the

established reference points and property monuments, and shall make no changes or relocations without the prior written approval of Owner. Contractor shall report to Engineer whenever any reference point or property monument is lost or destroyed or requires relocation because of necessary changes in grades or locations, and shall be responsible for the accurate replacement or relocation of such reference points or property monuments by professionally qualified personnel.

4.04 *Progress Schedule*

- A. Contractor shall adhere to the Progress Schedule established in accordance with Paragraph 2.05 as it may be adjusted from time to time as provided below.
 - 1. Contractor shall submit to Engineer for acceptance (to the extent indicated in Paragraph 2.05) proposed adjustments in the Progress Schedule that will not result in changing the Contract Times.
 - 2. Proposed adjustments in the Progress Schedule that will change the Contract Times must be submitted in accordance with the requirements of Article 11.
- B. Contractor shall carry on the Work and adhere to the Progress Schedule during all disputes or disagreements with Owner. No Work will be delayed or postponed pending resolution of any disputes or disagreements, or during any appeal process, except as permitted by Paragraph 16.04, or as Owner and Contractor may otherwise agree in writing.

4.05 *Delays in Contractor's Progress*

- A. If Owner, Engineer, or anyone for whom Owner is responsible, delays, disrupts, or interferes with the performance or progress of the Work, then Contractor shall be entitled to an equitable adjustment in Contract Price or Contract Times.
- B. Contractor shall not be entitled to an adjustment in Contract Price or Contract Times for delay, disruption, or interference caused by or within the control of Contractor. Delay, disruption, and interference attributable to and within the control of a Subcontractor or Supplier shall be deemed to be within the control of Contractor.
- C. If Contractor's performance or progress is delayed, disrupted, or interfered with by unanticipated causes not the fault of and beyond the control of Owner, Contractor, and those for which they are responsible, then Contractor shall be entitled to an equitable adjustment in Contract Times. Such an adjustment will be Contractor's sole and exclusive remedy for the delays, disruption, and interference described in this paragraph. Causes of delay, disruption, or interference that may give rise to an adjustment in Contract Times under this paragraph include but are not limited to the following:
 - 1. Severe and unavoidable natural catastrophes such as fires, floods, epidemics, and earthquakes;
 - 2. Abnormal weather conditions;
 - 3. Acts or failures to act of third-party utility owners or other third-party entities (other than those third-party utility owners or other third-party entities performing other work at or adjacent to the Site as arranged by or under contract with Owner, as contemplated in Article 8); and
 - 4. Acts of war or terrorism.

- D. Contractor's entitlement to an adjustment of Contract Times or Contract Price is limited as follows:
1. Contractor's entitlement to an adjustment of the Contract Times is conditioned on the delay, disruption, or interference adversely affecting an activity on the critical path to completion of the Work, as of the time of the delay, disruption, or interference.
 2. Contractor shall not be entitled to an adjustment in Contract Price for any delay, disruption, or interference if such delay is concurrent with a delay, disruption, or interference caused by or within the control of Contractor. Such a concurrent delay by Contractor shall not preclude an adjustment of Contract Times to which Contractor is otherwise entitled.
 3. Adjustments of Contract Times or Contract Price are subject to the provisions of Article 11.
- E. Each Contractor request or Change Proposal seeking an increase in Contract Times or Contract Price must be supplemented by supporting data that sets forth in detail the following:
1. The circumstances that form the basis for the requested adjustment;
 2. The date upon which each cause of delay, disruption, or interference began to affect the progress of the Work;
 3. The date upon which each cause of delay, disruption, or interference ceased to affect the progress of the Work;
 4. The number of days' increase in Contract Times claimed as a consequence of each such cause of delay, disruption, or interference; and
 5. The impact on Contract Price, in accordance with the provisions of Paragraph 11.07.
- Contractor shall also furnish such additional supporting documentation as Owner or Engineer may require including, where appropriate, a revised progress schedule indicating all the activities affected by the delay, disruption, or interference, and an explanation of the effect of the delay, disruption, or interference on the critical path to completion of the Work.
- F. Delays, disruption, and interference to the performance or progress of the Work resulting from the existence of a differing subsurface or physical condition, an Underground Facility that was not shown or indicated by the Contract Documents, or not shown or indicated with reasonable accuracy, and those resulting from Hazardous Environmental Conditions, are governed by Article 5, together with the provisions of Paragraphs 4.05.D and 4.05.E.
- G. Paragraph 8.03 addresses delays, disruption, and interference to the performance or progress of the Work resulting from the performance of certain other work at or adjacent to the Site.

ARTICLE 5—SITE; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS

5.01 *Availability of Lands*

- A. Owner shall furnish the Site. Owner shall notify Contractor in writing of any encumbrances or restrictions not of general application but specifically related to use of the Site with which Contractor must comply in performing the Work.

- B. Upon reasonable written request, Owner shall furnish Contractor with a current statement of record legal title and legal description of the lands upon which permanent improvements are to be made and Owner's interest therein as necessary for giving notice of or filing a mechanic's or construction lien against such lands in accordance with applicable Laws and Regulations.
- C. Contractor shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment.

5.02 *Use of Site and Other Areas*

A. *Limitation on Use of Site and Other Areas*

1. Contractor shall confine construction equipment, temporary construction facilities, the storage of materials and equipment, and the operations of workers to the Site, adjacent areas that Contractor has arranged to use through construction easements or otherwise, and other adjacent areas permitted by Laws and Regulations, and shall not unreasonably encumber the Site and such other adjacent areas with construction equipment or other materials or equipment. Contractor shall assume full responsibility for (a) damage to the Site; (b) damage to any such other adjacent areas used for Contractor's operations; (c) damage to any other adjacent land or areas, or to improvements, structures, utilities, or similar facilities located at such adjacent lands or areas; and (d) for injuries and losses sustained by the owners or occupants of any such land or areas; provided that such damage or injuries result from the performance of the Work or from other actions or conduct of the Contractor or those for which Contractor is responsible.
 2. If a damage or injury claim is made by the owner or occupant of any such land or area because of the performance of the Work, or because of other actions or conduct of the Contractor or those for which Contractor is responsible, Contractor shall (a) take immediate corrective or remedial action as required by Paragraph 7.13, or otherwise; (b) promptly attempt to settle the claim as to all parties through negotiations with such owner or occupant, or otherwise resolve the claim by arbitration or other dispute resolution proceeding, or in a court of competent jurisdiction; and (c) to the fullest extent permitted by Laws and Regulations, indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, from and against any such claim, and against all costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any claim or action, legal or equitable, brought by any such owner or occupant against Owner, Engineer, or any other party indemnified hereunder to the extent caused directly or indirectly, in whole or in part by, or based upon, Contractor's performance of the Work, or because of other actions or conduct of the Contractor or those for which Contractor is responsible.
- B. *Removal of Debris During Performance of the Work:* During the progress of the Work the Contractor shall keep the Site and other adjacent areas free from accumulations of waste materials, rubbish, and other debris. Removal and disposal of such waste materials, rubbish, and other debris will conform to applicable Laws and Regulations.
 - C. *Cleaning:* Prior to Substantial Completion of the Work Contractor shall clean the Site and the Work and make it ready for utilization by Owner. At the completion of the Work Contractor shall remove from the Site and adjacent areas all tools, appliances, construction equipment

and machinery, and surplus materials and shall restore to original condition all property not designated for alteration by the Contract Documents.

- D. *Loading of Structures:* Contractor shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall Contractor subject any part of the Work or adjacent structures or land to stresses or pressures that will endanger them.

5.03 *Subsurface and Physical Conditions*

- A. *Reports and Drawings:* The Supplementary Conditions identify:

1. Those reports of explorations and tests of subsurface conditions at or adjacent to the Site that contain Technical Data;
2. Those drawings of existing physical conditions at or adjacent to the Site, including those drawings depicting existing surface or subsurface structures at or adjacent to the Site (except Underground Facilities), that contain Technical Data; and
3. Technical Data contained in such reports and drawings.

- B. *Underground Facilities:* Underground Facilities are shown or indicated on the Drawings, pursuant to Paragraph 5.05, and not in the drawings referred to in Paragraph 5.03.A. Information and data regarding the presence or location of Underground Facilities are not intended to be categorized, identified, or defined as Technical Data.

- C. *Reliance by Contractor on Technical Data:* Contractor may rely upon the accuracy of the Technical Data expressly identified in the Supplementary Conditions with respect to such reports and drawings, but such reports and drawings are not Contract Documents. If no such express identification has been made, then Contractor may rely upon the accuracy of the Technical Data as defined in Paragraph 1.01.A.46.b.

- D. *Limitations of Other Data and Documents:* Except for such reliance on Technical Data, Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, with respect to:

1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, and safety precautions and programs incident thereto;
2. other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings;
3. the contents of other Site-related documents made available to Contractor, such as record drawings from other projects at or adjacent to the Site, or Owner's archival documents concerning the Site; or
4. any Contractor interpretation of or conclusion drawn from any Technical Data or any such other data, interpretations, opinions, or information.

5.04 *Differing Subsurface or Physical Conditions*

- A. *Notice by Contractor:* If Contractor believes that any subsurface or physical condition that is uncovered or revealed at the Site:
1. is of such a nature as to establish that any Technical Data on which Contractor is entitled to rely as provided in Paragraph 5.03 is materially inaccurate;
 2. is of such a nature as to require a change in the Drawings or Specifications;
 3. differs materially from that shown or indicated in the Contract Documents; or
 4. is of an unusual nature, and differs materially from conditions ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract Documents;

then Contractor shall, promptly after becoming aware thereof and before further disturbing the subsurface or physical conditions or performing any Work in connection therewith (except in an emergency as required by Paragraph 7.15), notify Owner and Engineer in writing about such condition. Contractor shall not further disturb such condition or perform any Work in connection therewith (except with respect to an emergency) until receipt of a written statement permitting Contractor to do so.

- B. *Engineer's Review:* After receipt of written notice as required by the preceding paragraph, Engineer will promptly review the subsurface or physical condition in question; determine whether it is necessary for Owner to obtain additional exploration or tests with respect to the condition; conclude whether the condition falls within any one or more of the differing site condition categories in Paragraph 5.04.A; obtain any pertinent cost or schedule information from Contractor; prepare recommendations to Owner regarding the Contractor's resumption of Work in connection with the subsurface or physical condition in question and the need for any change in the Drawings or Specifications; and advise Owner in writing of Engineer's findings, conclusions, and recommendations.
- C. *Owner's Statement to Contractor Regarding Site Condition:* After receipt of Engineer's written findings, conclusions, and recommendations, Owner shall issue a written statement to Contractor (with a copy to Engineer) regarding the subsurface or physical condition in question, addressing the resumption of Work in connection with such condition, indicating whether any change in the Drawings or Specifications will be made, and adopting or rejecting Engineer's written findings, conclusions, and recommendations, in whole or in part.
- D. *Early Resumption of Work:* If at any time Engineer determines that Work in connection with the subsurface or physical condition in question may resume prior to completion of Engineer's review or Owner's issuance of its statement to Contractor, because the condition in question has been adequately documented, and analyzed on a preliminary basis, then the Engineer may at its discretion instruct Contractor to resume such Work.
- E. *Possible Price and Times Adjustments*
1. Contractor shall be entitled to an equitable adjustment in Contract Price or Contract Times, to the extent that the existence of a differing subsurface or physical condition, or any related delay, disruption, or interference, causes an increase or decrease in

Contractor's cost of, or time required for, performance of the Work; subject, however, to the following:

- a. Such condition must fall within any one or more of the categories described in Paragraph 5.04.A;
 - b. With respect to Work that is paid for on a unit price basis, any adjustment in Contract Price will be subject to the provisions of Paragraph 13.03; and,
 - c. Contractor's entitlement to an adjustment of the Contract Times is subject to the provisions of Paragraphs 4.05.D and 4.05.E.
2. Contractor shall not be entitled to any adjustment in the Contract Price or Contract Times with respect to a subsurface or physical condition if:
 - a. Contractor knew of the existence of such condition at the time Contractor made a commitment to Owner with respect to Contract Price and Contract Times by the submission of a Bid or becoming bound under a negotiated contract, or otherwise;
 - b. The existence of such condition reasonably could have been discovered or revealed as a result of any examination, investigation, exploration, test, or study of the Site and contiguous areas expressly required by the Bidding Requirements or Contract Documents to be conducted by or for Contractor prior to Contractor's making such commitment; or
 - c. Contractor failed to give the written notice required by Paragraph 5.04.A.
 3. If Owner and Contractor agree regarding Contractor's entitlement to and the amount or extent of any adjustment in the Contract Price or Contract Times, then any such adjustment will be set forth in a Change Order.
 4. Contractor may submit a Change Proposal regarding its entitlement to or the amount or extent of any adjustment in the Contract Price or Contract Times, no later than 30 days after Owner's issuance of the Owner's written statement to Contractor regarding the subsurface or physical condition in question.
- F. *Underground Facilities; Hazardous Environmental Conditions:* Paragraph 5.05 governs rights and responsibilities regarding the presence or location of Underground Facilities. Paragraph 5.06 governs rights and responsibilities regarding Hazardous Environmental Conditions. The provisions of Paragraphs 5.03 and 5.04 are not applicable to the presence or location of Underground Facilities, or to Hazardous Environmental Conditions.

5.05 *Underground Facilities*

- A. *Contractor's Responsibilities:* Unless it is otherwise expressly provided in the Supplementary Conditions, the cost of all of the following are included in the Contract Price, and Contractor shall have full responsibility for:
1. reviewing and checking all information and data regarding existing Underground Facilities at the Site;
 2. complying with applicable state and local utility damage prevention Laws and Regulations;

3. verifying the actual location of those Underground Facilities shown or indicated in the Contract Documents as being within the area affected by the Work, by exposing such Underground Facilities during the course of construction;
 4. coordination of the Work with the owners (including Owner) of such Underground Facilities, during construction; and
 5. the safety and protection of all existing Underground Facilities at the Site, and repairing any damage thereto resulting from the Work.
- B. *Notice by Contractor:* If Contractor believes that an Underground Facility that is uncovered or revealed at the Site was not shown or indicated on the Drawings, or was not shown or indicated on the Drawings with reasonable accuracy, then Contractor shall, promptly after becoming aware thereof and before further disturbing conditions affected thereby or performing any Work in connection therewith (except in an emergency as required by Paragraph 7.15), notify Owner and Engineer in writing regarding such Underground Facility.
- C. *Engineer's Review:* Engineer will:
1. promptly review the Underground Facility and conclude whether such Underground Facility was not shown or indicated on the Drawings, or was not shown or indicated with reasonable accuracy;
 2. identify and communicate with the owner of the Underground Facility; prepare recommendations to Owner (and if necessary issue any preliminary instructions to Contractor) regarding the Contractor's resumption of Work in connection with the Underground Facility in question;
 3. obtain any pertinent cost or schedule information from Contractor; determine the extent, if any, to which a change is required in the Drawings or Specifications to reflect and document the consequences of the existence or location of the Underground Facility; and
 4. advise Owner in writing of Engineer's findings, conclusions, and recommendations.
- During such time, Contractor shall be responsible for the safety and protection of such Underground Facility.
- D. *Owner's Statement to Contractor Regarding Underground Facility:* After receipt of Engineer's written findings, conclusions, and recommendations, Owner shall issue a written statement to Contractor (with a copy to Engineer) regarding the Underground Facility in question addressing the resumption of Work in connection with such Underground Facility, indicating whether any change in the Drawings or Specifications will be made, and adopting or rejecting Engineer's written findings, conclusions, and recommendations in whole or in part.
- E. *Early Resumption of Work:* If at any time Engineer determines that Work in connection with the Underground Facility may resume prior to completion of Engineer's review or Owner's issuance of its statement to Contractor, because the Underground Facility in question and conditions affected by its presence have been adequately documented, and analyzed on a preliminary basis, then the Engineer may at its discretion instruct Contractor to resume such Work.
- F. *Possible Price and Times Adjustments*
1. Contractor shall be entitled to an equitable adjustment in the Contract Price or Contract Times, to the extent that any existing Underground Facility at the Site that was not shown

or indicated on the Drawings, or was not shown or indicated with reasonable accuracy, or any related delay, disruption, or interference, causes an increase or decrease in Contractor's cost of, or time required for, performance of the Work; subject, however, to the following:

- a. With respect to Work that is paid for on a unit price basis, any adjustment in Contract Price will be subject to the provisions of Paragraph 13.03;
 - b. Contractor's entitlement to an adjustment of the Contract Times is subject to the provisions of Paragraphs 4.05.D and 4.05.E; and
 - c. Contractor gave the notice required in Paragraph 5.05.B.
2. If Owner and Contractor agree regarding Contractor's entitlement to and the amount or extent of any adjustment in the Contract Price or Contract Times, then any such adjustment will be set forth in a Change Order.
 3. Contractor may submit a Change Proposal regarding its entitlement to or the amount or extent of any adjustment in the Contract Price or Contract Times, no later than 30 days after Owner's issuance of the Owner's written statement to Contractor regarding the Underground Facility in question.
 4. The information and data shown or indicated on the Drawings with respect to existing Underground Facilities at the Site is based on information and data (a) furnished by the owners of such Underground Facilities, or by others, (b) obtained from available records, or (c) gathered in an investigation conducted in accordance with the current edition of ASCE 38, Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data, by the American Society of Civil Engineers. If such information or data is incorrect or incomplete, Contractor's remedies are limited to those set forth in this Paragraph 5.05.F.

5.06 *Hazardous Environmental Conditions at Site*

A. *Reports and Drawings:* The Supplementary Conditions identify:

1. those reports known to Owner relating to Hazardous Environmental Conditions that have been identified at or adjacent to the Site;
2. drawings known to Owner relating to Hazardous Environmental Conditions that have been identified at or adjacent to the Site; and
3. Technical Data contained in such reports and drawings.

B. *Reliance by Contractor on Technical Data Authorized:* Contractor may rely upon the accuracy of the Technical Data expressly identified in the Supplementary Conditions with respect to such reports and drawings, but such reports and drawings are not Contract Documents. If no such express identification has been made, then Contractor may rely on the accuracy of the Technical Data as defined in Paragraph 1.01.A.46.b. Except for such reliance on Technical Data, Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, with respect to:

1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences and procedures

- of construction to be employed by Contractor, and safety precautions and programs incident thereto;
2. other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
 3. any Contractor interpretation of or conclusion drawn from any Technical Data or any such other data, interpretations, opinions or information.
- C. Contractor shall not be responsible for removing or remediating any Hazardous Environmental Condition encountered, uncovered, or revealed at the Site unless such removal or remediation is expressly identified in the Contract Documents to be within the scope of the Work.
- D. Contractor shall be responsible for controlling, containing, and duly removing all Constituents of Concern brought to the Site by Contractor, Subcontractors, Suppliers, or anyone else for whom Contractor is responsible, and for any associated costs; and for the costs of removing and remediating any Hazardous Environmental Condition created by the presence of any such Constituents of Concern.
- E. If Contractor encounters, uncovers, or reveals a Hazardous Environmental Condition whose removal or remediation is not expressly identified in the Contract Documents as being within the scope of the Work, or if Contractor or anyone for whom Contractor is responsible creates a Hazardous Environmental Condition, then Contractor shall immediately: (1) secure or otherwise isolate such condition; (2) stop all Work in connection with such condition and in any area affected thereby (except in an emergency as required by Paragraph 7.15); and (3) notify Owner and Engineer (and promptly thereafter confirm such notice in writing). Owner shall promptly consult with Engineer concerning the necessity for Owner to retain a qualified expert to evaluate such condition or take corrective action, if any. Promptly after consulting with Engineer, Owner shall take such actions as are necessary to permit Owner to timely obtain required permits and provide Contractor the written notice required by Paragraph 5.06.F. If Contractor or anyone for whom Contractor is responsible created the Hazardous Environmental Condition in question, then Owner may remove and remediate the Hazardous Environmental Condition, and impose a set-off against payments to account for the associated costs.
- F. Contractor shall not resume Work in connection with such Hazardous Environmental Condition or in any affected area until after Owner has obtained any required permits related thereto, and delivered written notice to Contractor either (1) specifying that such condition and any affected area is or has been rendered safe for the resumption of Work, or (2) specifying any special conditions under which such Work may be resumed safely.
- G. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times, as a result of such Work stoppage, such special conditions under which Work is agreed to be resumed by Contractor, or any costs or expenses incurred in response to the Hazardous Environmental Condition, then within 30 days of Owner's written notice regarding the resumption of Work, Contractor may submit a Change Proposal, or Owner may impose a set-off. Entitlement to any such adjustment is subject to the provisions of Paragraphs 4.05.D, 4.05.E, 11.07, and 11.08.
- H. If, after receipt of such written notice, Contractor does not agree to resume such Work based on a reasonable belief it is unsafe, or does not agree to resume such Work under such special

conditions, then Owner may order the portion of the Work that is in the area affected by such condition to be deleted from the Work, following the contractual change procedures in Article 11. Owner may have such deleted portion of the Work performed by Owner's own forces or others in accordance with Article 8.

- I. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court, arbitration, or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition, provided that such Hazardous Environmental Condition (1) was not shown or indicated in the Drawings, Specifications, or other Contract Documents, identified as Technical Data entitled to limited reliance pursuant to Paragraph 5.06.B, or identified in the Contract Documents to be included within the scope of the Work, and (2) was not created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 5.06.I obligates Owner to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.
- J. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to the failure to control, contain, or remove a Constituent of Concern brought to the Site by Contractor or by anyone for whom Contractor is responsible, or to a Hazardous Environmental Condition created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 5.06.J obligates Contractor to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.
- K. The provisions of Paragraphs 5.03, 5.04, and 5.05 do not apply to the presence of Constituents of Concern or to a Hazardous Environmental Condition uncovered or revealed at the Site.

ARTICLE 6—BONDS AND INSURANCE

6.01 *Performance, Payment, and Other Bonds*

- A. Contractor shall furnish a performance bond and a payment bond, each in an amount at least equal to the Contract Price, as security for the faithful performance and payment of Contractor's obligations under the Contract. These bonds must remain in effect until one year after the date when final payment becomes due or until completion of the correction period specified in Paragraph 15.08, whichever is later, except as provided otherwise by Laws or Regulations, the terms of a prescribed bond form, the Supplementary Conditions, or other provisions of the Contract.
- B. Contractor shall also furnish such other bonds (if any) as are required by the Supplementary Conditions or other provisions of the Contract.
- C. All bonds must be in the form included in the Bidding Documents or otherwise specified by Owner prior to execution of the Contract, except as provided otherwise by Laws or

Regulations, and must be issued and signed by a surety named in “Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies” as published in Department Circular 570 (as amended and supplemented) by the Bureau of the Fiscal Service, U.S. Department of the Treasury. A bond signed by an agent or attorney-in-fact must be accompanied by a certified copy of that individual’s authority to bind the surety. The evidence of authority must show that it is effective on the date the agent or attorney-in-fact signed the accompanying bond.

- D. Contractor shall obtain the required bonds from surety companies that are duly licensed or authorized, in the state or jurisdiction in which the Project is located, to issue bonds in the required amounts.
- E. If the surety on a bond furnished by Contractor is declared bankrupt or becomes insolvent, or the surety ceases to meet the requirements above, then Contractor shall promptly notify Owner and Engineer in writing and shall, within 20 days after the event giving rise to such notification, provide another bond and surety, both of which must comply with the bond and surety requirements above.
- F. If Contractor has failed to obtain a required bond, Owner may exclude the Contractor from the Site and exercise Owner’s termination rights under Article 16.
- G. Upon request to Owner from any Subcontractor, Supplier, or other person or entity claiming to have furnished labor, services, materials, or equipment used in the performance of the Work, Owner shall provide a copy of the payment bond to such person or entity.
- H. Upon request to Contractor from any Subcontractor, Supplier, or other person or entity claiming to have furnished labor, services, materials, or equipment used in the performance of the Work, Contractor shall provide a copy of the payment bond to such person or entity.

6.02 *Insurance—General Provisions*

- A. Owner and Contractor shall obtain and maintain insurance as required in this article and in the Supplementary Conditions.
- B. All insurance required by the Contract to be purchased and maintained by Owner or Contractor shall be obtained from insurance companies that are duly licensed or authorized in the state or jurisdiction in which the Project is located to issue insurance policies for the required limits and coverages. Unless a different standard is indicated in the Supplementary Conditions, all companies that provide insurance policies required under this Contract shall have an A.M. Best rating of A-VII or better.
- C. Alternative forms of insurance coverage, including but not limited to self-insurance and “Occupational Accident and Excess Employer’s Indemnity Policies,” are not sufficient to meet the insurance requirements of this Contract, unless expressly allowed in the Supplementary Conditions.
- D. Contractor shall deliver to Owner, with copies to each additional insured identified in the Contract, certificates of insurance and endorsements establishing that Contractor has obtained and is maintaining the policies and coverages required by the Contract. Upon request by Owner or any other insured, Contractor shall also furnish other evidence of such required insurance, including but not limited to copies of policies, documentation of applicable self-insured retentions (if allowed) and deductibles, full disclosure of all relevant exclusions, and evidence of insurance required to be purchased and maintained by

Subcontractors or Suppliers. In any documentation furnished under this provision, Contractor, Subcontractors, and Suppliers may block out (redact) (1) any confidential premium or pricing information and (2) any wording specific to a project or jurisdiction other than those applicable to this Contract.

- E. Owner shall deliver to Contractor, with copies to each additional insured identified in the Contract, certificates of insurance and endorsements establishing that Owner has obtained and is maintaining the policies and coverages required of Owner by the Contract (if any). Upon request by Contractor or any other insured, Owner shall also provide other evidence of such required insurance (if any), including but not limited to copies of policies, documentation of applicable self-insured retentions (if allowed) and deductibles, and full disclosure of all relevant exclusions. In any documentation furnished under this provision, Owner may block out (redact) (1) any confidential premium or pricing information and (2) any wording specific to a project or jurisdiction other than those relevant to this Contract.
- F. Failure of Owner or Contractor to demand such certificates or other evidence of the other party's full compliance with these insurance requirements, or failure of Owner or Contractor to identify a deficiency in compliance from the evidence provided, will not be construed as a waiver of the other party's obligation to obtain and maintain such insurance.
- G. In addition to the liability insurance required to be provided by Contractor, the Owner, at Owner's option, may purchase and maintain Owner's own liability insurance. Owner's liability policies, if any, operate separately and independently from policies required to be provided by Contractor, and Contractor cannot rely upon Owner's liability policies for any of Contractor's obligations to the Owner, Engineer, or third parties.
- H. Contractor shall require:
 - 1. Subcontractors to purchase and maintain worker's compensation, commercial general liability, and other insurance that is appropriate for their participation in the Project, and to name as additional insureds Owner and Engineer (and any other individuals or entities identified in the Supplementary Conditions as additional insureds on Contractor's liability policies) on each Subcontractor's commercial general liability insurance policy; and
 - 2. Suppliers to purchase and maintain insurance that is appropriate for their participation in the Project.
- I. If either party does not purchase or maintain the insurance required of such party by the Contract, such party shall notify the other party in writing of such failure to purchase prior to the start of the Work, or of such failure to maintain prior to any change in the required coverage.
- J. If Contractor has failed to obtain and maintain required insurance, Contractor's entitlement to enter or remain at the Site will end immediately, and Owner may impose an appropriate set-off against payment for any associated costs (including but not limited to the cost of purchasing necessary insurance coverage), and exercise Owner's termination rights under Article 16.
- K. Without prejudice to any other right or remedy, if a party has failed to obtain required insurance, the other party may elect (but is in no way obligated) to obtain equivalent insurance to protect such other party's interests at the expense of the party who was required to provide such coverage, and the Contract Price will be adjusted accordingly.

- L. Owner does not represent that insurance coverage and limits established in this Contract necessarily will be adequate to protect Contractor or Contractor's interests. Contractor is responsible for determining whether such coverage and limits are adequate to protect its interests, and for obtaining and maintaining any additional insurance that Contractor deems necessary.
- M. The insurance and insurance limits required herein will not be deemed as a limitation on Contractor's liability, or that of its Subcontractors or Suppliers, under the indemnities granted to Owner and other individuals and entities in the Contract or otherwise.
- N. All the policies of insurance required to be purchased and maintained under this Contract will contain a provision or endorsement that the coverage afforded will not be canceled, or renewal refused, until at least 10 days prior written notice has been given to the purchasing policyholder. Within three days of receipt of any such written notice, the purchasing policyholder shall provide a copy of the notice to each other insured and Engineer.

6.03 *Contractor's Insurance*

- A. *Required Insurance:* Contractor shall purchase and maintain Worker's Compensation, Commercial General Liability, and other insurance pursuant to the specific requirements of the Supplementary Conditions.
- B. *General Provisions:* The policies of insurance required by this Paragraph 6.03 as supplemented must:
 - 1. include at least the specific coverages required;
 - 2. be written for not less than the limits provided, or those required by Laws or Regulations, whichever is greater;
 - 3. remain in effect at least until the Work is complete (as set forth in Paragraph 15.06.D), and longer if expressly required elsewhere in this Contract, and at all times thereafter when Contractor may be correcting, removing, or replacing defective Work as a warranty or correction obligation, or otherwise, or returning to the Site to conduct other tasks arising from the Contract;
 - 4. apply with respect to the performance of the Work, whether such performance is by Contractor, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable; and
 - 5. include all necessary endorsements to support the stated requirements.
- C. *Additional Insureds:* The Contractor's commercial general liability, automobile liability, employer's liability, umbrella or excess, pollution liability, and unmanned aerial vehicle liability policies, if required by this Contract, must:
 - 1. include and list as additional insureds Owner and Engineer, and any individuals or entities identified as additional insureds in the Supplementary Conditions;
 - 2. include coverage for the respective officers, directors, members, partners, employees, and consultants of all such additional insureds;
 - 3. afford primary coverage to these additional insureds for all claims covered thereby (including as applicable those arising from both ongoing and completed operations);

4. not seek contribution from insurance maintained by the additional insured; and
5. as to commercial general liability insurance, apply to additional insureds with respect to liability caused in whole or in part by Contractor's acts or omissions, or the acts and omissions of those working on Contractor's behalf, in the performance of Contractor's operations.

6.04 *Builder's Risk and Other Property Insurance*

- A. *Builder's Risk*: Unless otherwise provided in the Supplementary Conditions, Contractor shall purchase and maintain builder's risk insurance upon the Work on a completed value basis, in the amount of the Work's full insurable replacement cost (subject to such deductible amounts as may be provided in the Supplementary Conditions or required by Laws and Regulations). The specific requirements applicable to the builder's risk insurance are set forth in the Supplementary Conditions.
- B. *Property Insurance for Facilities of Owner Where Work Will Occur*: Owner is responsible for obtaining and maintaining property insurance covering each existing structure, building, or facility in which any part of the Work will occur, or to which any part of the Work will attach or be adjoined. Such property insurance will be written on a special perils (all-risk) form, on a replacement cost basis, providing coverage consistent with that required for the builder's risk insurance, and will be maintained until the Work is complete, as set forth in Paragraph 15.06.D.
- C. *Property Insurance for Substantially Complete Facilities*: Promptly after Substantial Completion, and before actual occupancy or use of the substantially completed Work, Owner will obtain property insurance for such substantially completed Work, and maintain such property insurance at least until the Work is complete, as set forth in Paragraph 15.06.D. Such property insurance will be written on a special perils (all-risk) form, on a replacement cost basis, and provide coverage consistent with that required for the builder's risk insurance. The builder's risk insurance may terminate upon written confirmation of Owner's procurement of such property insurance.
- D. *Partial Occupancy or Use by Owner*: If Owner will occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work, as provided in Paragraph 15.04, then Owner (directly, if it is the purchaser of the builder's risk policy, or through Contractor) will provide advance notice of such occupancy or use to the builder's risk insurer, and obtain an endorsement consenting to the continuation of coverage prior to commencing such partial occupancy or use.
- E. *Insurance of Other Property; Additional Insurance*: If the express insurance provisions of the Contract do not require or address the insurance of a property item or interest, then the entity or individual owning such property item will be responsible for insuring it. If Contractor elects to obtain other special insurance to be included in or supplement the builder's risk or property insurance policies provided under this Paragraph 6.04, it may do so at Contractor's expense.

6.05 *Property Losses; Subrogation*

- A. The builder's risk insurance policy purchased and maintained in accordance with Paragraph 6.04 (or an installation floater policy if authorized by the Supplementary Conditions), will contain provisions to the effect that in the event of payment of any loss or damage the insurer will have no rights of recovery against any insureds thereunder, or against

Engineer or its consultants, or their officers, directors, members, partners, employees, agents, consultants, or subcontractors.

1. Owner and Contractor waive all rights against each other and the respective officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, for all losses and damages caused by, arising out of, or resulting from any of the perils, risks, or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Engineer, its consultants, all individuals or entities identified in the Supplementary Conditions as builder's risk or installation floater insureds, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, under such policies for losses and damages so caused.
 2. None of the above waivers extends to the rights that any party making such waiver may have to the proceeds of insurance held by Owner or Contractor as trustee or fiduciary, or otherwise payable under any policy so issued.
- B. Any property insurance policy maintained by Owner covering any loss, damage, or consequential loss to Owner's existing structures, buildings, or facilities in which any part of the Work will occur, or to which any part of the Work will attach or adjoin; to adjacent structures, buildings, or facilities of Owner; or to part or all of the completed or substantially completed Work, during partial occupancy or use pursuant to Paragraph 15.04, after Substantial Completion pursuant to Paragraph 15.03, or after final payment pursuant to Paragraph 15.06, will contain provisions to the effect that in the event of payment of any loss or damage the insurer will have no rights of recovery against any insureds thereunder, or against Contractor, Subcontractors, or Engineer, or the officers, directors, members, partners, employees, agents, consultants, or subcontractors of each and any of them, and that the insured is allowed to waive the insurer's rights of subrogation in a written contract executed prior to the loss, damage, or consequential loss.
1. Owner waives all rights against Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, for all losses and damages caused by, arising out of, or resulting from fire or any of the perils, risks, or causes of loss covered by such policies.
- C. The waivers in this Paragraph 6.05 include the waiver of rights due to business interruption, loss of use, or other consequential loss extending beyond direct physical loss or damage to Owner's property or the Work caused by, arising out of, or resulting from fire or other insured peril, risk, or cause of loss.
- D. Contractor shall be responsible for assuring that each Subcontract contains provisions whereby the Subcontractor waives all rights against Owner, Contractor, all individuals or entities identified in the Supplementary Conditions as insureds, the Engineer and its consultants, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, for all losses and damages caused by, arising out of, relating to, or resulting from fire or other peril, risk, or cause of loss covered by builder's risk insurance, installation floater, and any other property insurance applicable to the Work.

6.06 *Receipt and Application of Property Insurance Proceeds*

- A. Any insured loss under the builder's risk and other policies of property insurance required by Paragraph 6.04 will be adjusted and settled with the named insured that purchased the policy. Such named insured shall act as fiduciary for the other insureds, and give notice to such other insureds that adjustment and settlement of a claim is in progress. Any other insured may state its position regarding a claim for insured loss in writing within 15 days after notice of such claim.
- B. Proceeds for such insured losses may be made payable by the insurer either jointly to multiple insureds, or to the named insured that purchased the policy in its own right and as fiduciary for other insureds, subject to the requirements of any applicable mortgage clause. A named insured receiving insurance proceeds under the builder's risk and other policies of insurance required by Paragraph 6.04 shall maintain such proceeds in a segregated account, and distribute such proceeds in accordance with such agreement as the parties in interest may reach, or as otherwise required under the dispute resolution provisions of this Contract or applicable Laws and Regulations.
- C. If no other special agreement is reached, Contractor shall repair or replace the damaged Work, using allocated insurance proceeds.

ARTICLE 7—CONTRACTOR'S RESPONSIBILITIES

7.01 *Contractor's Means and Methods of Construction*

- A. Contractor shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction.
- B. If the Contract Documents note, or Contractor determines, that professional engineering or other design services are needed to carry out Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures, or for Site safety, then Contractor shall cause such services to be provided by a properly licensed design professional, at Contractor's expense. Such services are not Owner-delegated professional design services under this Contract, and neither Owner nor Engineer has any responsibility with respect to (1) Contractor's determination of the need for such services, (2) the qualifications or licensing of the design professionals retained or employed by Contractor, (3) the performance of such services, or (4) any errors, omissions, or defects in such services.

7.02 *Supervision and Superintendence*

- A. Contractor shall supervise, inspect, and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents.
- B. At all times during the progress of the Work, Contractor shall assign a competent resident superintendent who will not be replaced without written notice to Owner and Engineer except under extraordinary circumstances.

7.03 *Labor; Working Hours*

- A. Contractor shall provide competent, suitably qualified personnel to survey and lay out the Work and perform construction as required by the Contract Documents. Contractor shall maintain good discipline and order at the Site.

- B. Contractor shall be fully responsible to Owner and Engineer for all acts and omissions of Contractor's employees; of Suppliers and Subcontractors, and their employees; and of any other individuals or entities performing or furnishing any of the Work, just as Contractor is responsible for Contractor's own acts and omissions.
- C. Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the Contract Documents, all Work at the Site will be performed during regular working hours, Monday through Friday. Contractor will not perform Work on a Saturday, Sunday, or any legal holiday. Contractor may perform Work outside regular working hours or on Saturdays, Sundays, or legal holidays only with Owner's written consent, which will not be unreasonably withheld.

7.04 *Services, Materials, and Equipment*

- A. Unless otherwise specified in the Contract Documents, Contractor shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start up, and completion of the Work, whether or not such items are specifically called for in the Contract Documents.
- B. All materials and equipment incorporated into the Work must be new and of good quality, except as otherwise provided in the Contract Documents. All special warranties and guarantees required by the Specifications will expressly run to the benefit of Owner. If required by Engineer, Contractor shall furnish satisfactory evidence (including reports of required tests) as to the source, kind, and quality of materials and equipment.
- C. All materials and equipment must be stored, applied, installed, connected, erected, protected, used, cleaned, and conditioned in accordance with instructions of the applicable Supplier, except as otherwise may be provided in the Contract Documents.

7.05 *"Or Equals"*

- A. *Contractor's Request; Governing Criteria:* Whenever an item of equipment or material is specified or described in the Contract Documents by using the names of one or more proprietary items or specific Suppliers, the Contract Price has been based upon Contractor furnishing such item as specified. The specification or description of such an item is intended to establish the type, function, appearance, and quality required. Unless the specification or description contains or is followed by words reading that no like, equivalent, or "or equal" item is permitted, Contractor may request that Engineer authorize the use of other items of equipment or material, or items from other proposed Suppliers, under the circumstances described below.
 - 1. If Engineer in its sole discretion determines that an item of equipment or material proposed by Contractor is functionally equal to that named and sufficiently similar so that no change in related Work will be required, Engineer will deem it an "or equal" item. For the purposes of this paragraph, a proposed item of equipment or material will be considered functionally equal to an item so named if:
 - a. in the exercise of reasonable judgment Engineer determines that the proposed item:
 - 1) is at least equal in materials of construction, quality, durability, appearance, strength, and design characteristics;

- 2) will reliably perform at least equally well the function and achieve the results imposed by the design concept of the completed Project as a functioning whole;
 - 3) has a proven record of performance and availability of responsive service; and
 - 4) is not objectionable to Owner.
- b. Contractor certifies that, if the proposed item is approved and incorporated into the Work:
 - 1) there will be no increase in cost to the Owner or increase in Contract Times; and
 - 2) the item will conform substantially to the detailed requirements of the item named in the Contract Documents.
- B. *Contractor's Expense*: Contractor shall provide all data in support of any proposed "or equal" item at Contractor's expense.
- C. *Engineer's Evaluation and Determination*: Engineer will be allowed a reasonable time to evaluate each "or-equal" request. Engineer may require Contractor to furnish additional data about the proposed "or-equal" item. Engineer will be the sole judge of acceptability. No "or-equal" item will be ordered, furnished, installed, or utilized until Engineer's review is complete and Engineer determines that the proposed item is an "or-equal," which will be evidenced by an approved Shop Drawing or other written communication. Engineer will advise Contractor in writing of any negative determination.
- D. *Effect of Engineer's Determination*: Neither approval nor denial of an "or-equal" request will result in any change in Contract Price. The Engineer's denial of an "or-equal" request will be final and binding, and may not be reversed through an appeal under any provision of the Contract.
- E. *Treatment as a Substitution Request*: If Engineer determines that an item of equipment or material proposed by Contractor does not qualify as an "or-equal" item, Contractor may request that Engineer consider the item a proposed substitute pursuant to Paragraph 7.06.

7.06 Substitutes

- A. *Contractor's Request; Governing Criteria*: Unless the specification or description of an item of equipment or material required to be furnished under the Contract Documents contains or is followed by words reading that no substitution is permitted, Contractor may request that Engineer authorize the use of other items of equipment or material under the circumstances described below. To the extent possible such requests must be made before commencement of related construction at the Site.
1. Contractor shall submit sufficient information as provided below to allow Engineer to determine if the item of material or equipment proposed is functionally equivalent to that named and an acceptable substitute therefor. Engineer will not accept requests for review of proposed substitute items of equipment or material from anyone other than Contractor.
 2. The requirements for review by Engineer will be as set forth in Paragraph 7.06.B, as supplemented by the Specifications, and as Engineer may decide is appropriate under the circumstances.

3. Contractor shall make written application to Engineer for review of a proposed substitute item of equipment or material that Contractor seeks to furnish or use. The application:
 - a. will certify that the proposed substitute item will:
 - 1) perform adequately the functions and achieve the results called for by the general design;
 - 2) be similar in substance to the item specified; and
 - 3) be suited to the same use as the item specified.
 - b. will state:
 - 1) the extent, if any, to which the use of the proposed substitute item will necessitate a change in Contract Times;
 - 2) whether use of the proposed substitute item in the Work will require a change in any of the Contract Documents (or in the provisions of any other direct contract with Owner for other work on the Project) to adapt the design to the proposed substitute item; and
 - 3) whether incorporation or use of the proposed substitute item in connection with the Work is subject to payment of any license fee or royalty.
 - c. will identify:
 - 1) all variations of the proposed substitute item from the item specified; and
 - 2) available engineering, sales, maintenance, repair, and replacement services.
 - d. will contain an itemized estimate of all costs or credits that will result directly or indirectly from use of such substitute item, including but not limited to changes in Contract Price, shared savings, costs of redesign, and claims of other contractors affected by any resulting change.
- B. *Engineer's Evaluation and Determination*: Engineer will be allowed a reasonable time to evaluate each substitute request, and to obtain comments and direction from Owner. Engineer may require Contractor to furnish additional data about the proposed substitute item. Engineer will be the sole judge of acceptability. No substitute will be ordered, furnished, installed, or utilized until Engineer's review is complete and Engineer determines that the proposed item is an acceptable substitute. Engineer's determination will be evidenced by a Field Order or a proposed Change Order accounting for the substitution itself and all related impacts, including changes in Contract Price or Contract Times. Engineer will advise Contractor in writing of any negative determination.
- C. *Special Guarantee*: Owner may require Contractor to furnish at Contractor's expense a special performance guarantee or other surety with respect to any substitute.
- D. *Reimbursement of Engineer's Cost*: Engineer will record Engineer's costs in evaluating a substitute proposed or submitted by Contractor. Whether or not Engineer approves a substitute so proposed or submitted by Contractor, Contractor shall reimburse Owner for the reasonable charges of Engineer for evaluating each such proposed substitute. Contractor shall also reimburse Owner for the reasonable charges of Engineer for making changes in the Contract Documents (or in the provisions of any other direct contract with Owner) resulting from the acceptance of each proposed substitute.

- E. *Contractor's Expense*: Contractor shall provide all data in support of any proposed substitute at Contractor's expense.
- F. *Effect of Engineer's Determination*: If Engineer approves the substitution request, Contractor shall execute the proposed Change Order and proceed with the substitution. The Engineer's denial of a substitution request will be final and binding, and may not be reversed through an appeal under any provision of the Contract. Contractor may challenge the scope of reimbursement costs imposed under Paragraph 7.06.D, by timely submittal of a Change Proposal.

7.07 *Concerning Subcontractors and Suppliers*

- A. Contractor may retain Subcontractors and Suppliers for the performance of parts of the Work. Such Subcontractors and Suppliers must be acceptable to Owner. The Contractor's retention of a Subcontractor or Supplier for the performance of parts of the Work will not relieve Contractor's obligation to Owner to perform and complete the Work in accordance with the Contract Documents.
- B. Contractor shall retain specific Subcontractors and Suppliers for the performance of designated parts of the Work if required by the Contract to do so.
- C. Subsequent to the submittal of Contractor's Bid or final negotiation of the terms of the Contract, Owner may not require Contractor to retain any Subcontractor or Supplier to furnish or perform any of the Work against which Contractor has reasonable objection.
- D. Prior to entry into any binding subcontract or purchase order, Contractor shall submit to Owner the identity of the proposed Subcontractor or Supplier (unless Owner has already deemed such proposed Subcontractor or Supplier acceptable during the bidding process or otherwise). Such proposed Subcontractor or Supplier shall be deemed acceptable to Owner unless Owner raises a substantive, reasonable objection within 5 days.
- E. Owner may require the replacement of any Subcontractor or Supplier. Owner also may require Contractor to retain specific replacements; provided, however, that Owner may not require a replacement to which Contractor has a reasonable objection. If Contractor has submitted the identity of certain Subcontractors or Suppliers for acceptance by Owner, and Owner has accepted it (either in writing or by failing to make written objection thereto), then Owner may subsequently revoke the acceptance of any such Subcontractor or Supplier so identified solely on the basis of substantive, reasonable objection after due investigation. Contractor shall submit an acceptable replacement for the rejected Subcontractor or Supplier.
- F. If Owner requires the replacement of any Subcontractor or Supplier retained by Contractor to perform any part of the Work, then Contractor shall be entitled to an adjustment in Contract Price or Contract Times, with respect to the replacement; and Contractor shall initiate a Change Proposal for such adjustment within 30 days of Owner's requirement of replacement.
- G. No acceptance by Owner of any such Subcontractor or Supplier, whether initially or as a replacement, will constitute a waiver of the right of Owner to the completion of the Work in accordance with the Contract Documents.

- H. On a monthly basis, Contractor shall submit to Engineer a complete list of all Subcontractors and Suppliers having a direct contract with Contractor, and of all other Subcontractors and Suppliers known to Contractor at the time of submittal.
- I. Contractor shall be solely responsible for scheduling and coordinating the work of Subcontractors and Suppliers.
- J. The divisions and sections of the Specifications and the identifications of any Drawings do not control Contractor in dividing the Work among Subcontractors or Suppliers, or in delineating the Work to be performed by any specific trade.
- K. All Work performed for Contractor by a Subcontractor or Supplier must be pursuant to an appropriate contractual agreement that specifically binds the Subcontractor or Supplier to the applicable terms and conditions of the Contract for the benefit of Owner and Engineer.
- L. Owner may furnish to any Subcontractor or Supplier, to the extent practicable, information about amounts paid to Contractor for Work performed for Contractor by the Subcontractor or Supplier.
- M. Contractor shall restrict all Subcontractors and Suppliers from communicating with Engineer or Owner, except through Contractor or in case of an emergency, or as otherwise expressly allowed in this Contract.

7.08 *Patent Fees and Royalties*

- A. Contractor shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work or the incorporation in the Work of any invention, design, process, product, or device which is the subject of patent rights or copyrights held by others. If an invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the Work and if, to the actual knowledge of Owner or Engineer, its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights will be disclosed in the Contract Documents.
- B. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, and its officers, directors, members, partners, employees, agents, consultants, and subcontractors, from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device specified in the Contract Documents, but not identified as being subject to payment of any license fee or royalty to others required by patent rights or copyrights.
- C. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device not specified in the Contract Documents.

7.09 *Permits*

- A. Unless otherwise provided in the Contract Documents, Contractor shall obtain and pay for all construction permits, licenses, and certificates of occupancy. Owner shall assist Contractor, when necessary, in obtaining such permits and licenses. Contractor shall pay all governmental charges and inspection fees necessary for the prosecution of the Work which are applicable at the time of the submission of Contractor's Bid (or when Contractor became bound under a negotiated contract). Owner shall pay all charges of utility owners for connections for providing permanent service to the Work.

7.10 *Taxes*

- A. Contractor shall pay all sales, consumer, use, and other similar taxes required to be paid by Contractor in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work.

7.11 *Laws and Regulations*

- A. Contractor shall give all notices required by and shall comply with all Laws and Regulations applicable to the performance of the Work. Neither Owner nor Engineer shall be responsible for monitoring Contractor's compliance with any Laws or Regulations.
- B. If Contractor performs any Work or takes any other action knowing or having reason to know that it is contrary to Laws or Regulations, Contractor shall bear all resulting costs and losses, and shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such Work or other action. It is not Contractor's responsibility to make certain that the Work described in the Contract Documents is in accordance with Laws and Regulations, but this does not relieve Contractor of its obligations under Paragraph 3.03.
- C. Owner or Contractor may give written notice to the other party of any changes after the submission of Contractor's Bid (or after the date when Contractor became bound under a negotiated contract) in Laws or Regulations having an effect on the cost or time of performance of the Work, including but not limited to changes in Laws or Regulations having an effect on procuring permits and on sales, use, value-added, consumption, and other similar taxes. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times resulting from such changes, then within 30 days of such written notice Contractor may submit a Change Proposal, or Owner may initiate a Claim.

7.12 *Record Documents*

- A. Contractor shall maintain in a safe place at the Site one printed record copy of all Drawings, Specifications, Addenda, Change Orders, Work Change Directives, Field Orders, written interpretations and clarifications, and approved Shop Drawings. Contractor shall keep such record documents in good order and annotate them to show changes made during construction. These record documents, together with all approved Samples, will be available to Engineer for reference. Upon completion of the Work, Contractor shall deliver these record documents to Engineer.

7.13 *Safety and Protection*

- A. Contractor shall be solely responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the Work. Such responsibility does not relieve Subcontractors of their responsibility for the safety of persons or property in the performance of their work, nor for compliance with applicable safety Laws and Regulations.
- B. Contractor shall designate a qualified and experienced safety representative whose duties and responsibilities are the prevention of Work-related accidents and the maintenance and supervision of safety precautions and programs.
- C. Contractor shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury, or loss to:
 - 1. all persons on the Site or who may be affected by the Work;
 - 2. all the Work and materials and equipment to be incorporated therein, whether in storage on or off the Site; and
 - 3. other property at the Site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, other work in progress, utilities, and Underground Facilities not designated for removal, relocation, or replacement in the course of construction.
- D. All damage, injury, or loss to any property referred to in Paragraph 7.13.C.2 or 7.13.C.3 caused, directly or indirectly, in whole or in part, by Contractor, any Subcontractor, Supplier, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, shall be remedied by Contractor at its expense (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of Owner or Engineer or anyone employed by any of them, or anyone for whose acts any of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of Contractor or any Subcontractor, Supplier, or other individual or entity directly or indirectly employed by any of them).
- E. Contractor shall comply with all applicable Laws and Regulations relating to the safety of persons or property, or to the protection of persons or property from damage, injury, or loss; and shall erect and maintain all necessary safeguards for such safety and protection.
- F. Contractor shall notify Owner; the owners of adjacent property; the owners of Underground Facilities and other utilities (if the identity of such owners is known to Contractor); and other contractors and utility owners performing work at or adjacent to the Site, in writing, when Contractor knows that prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property or work in progress.
- G. Contractor shall comply with the applicable requirements of Owner's safety programs, if any. Any Owner's safety programs that are applicable to the Work are identified or included in the Supplementary Conditions or Specifications.
- H. Contractor shall inform Owner and Engineer of the specific requirements of Contractor's safety program with which Owner's and Engineer's employees and representatives must comply while at the Site.

- I. Contractor's duties and responsibilities for safety and protection will continue until all the Work is completed, Engineer has issued a written notice to Owner and Contractor in accordance with Paragraph 15.06.C that the Work is acceptable, and Contractor has left the Site (except as otherwise expressly provided in connection with Substantial Completion).
- J. Contractor's duties and responsibilities for safety and protection will resume whenever Contractor or any Subcontractor or Supplier returns to the Site to fulfill warranty or correction obligations, or to conduct other tasks arising from the Contract Documents.

7.14 *Hazard Communication Programs*

- A. Contractor shall be responsible for coordinating any exchange of safety data sheets (formerly known as material safety data sheets) or other hazard communication information required to be made available to or exchanged between or among employers at the Site in accordance with Laws or Regulations.

7.15 *Emergencies*

- A. In emergencies affecting the safety or protection of persons or the Work or property at the Site or adjacent thereto, Contractor is obligated to act to prevent damage, injury, or loss. Contractor shall give Engineer prompt written notice if Contractor believes that any significant changes in the Work or variations from the Contract Documents have been caused by an emergency, or are required as a result of Contractor's response to an emergency. If Engineer determines that a change in the Contract Documents is required because of an emergency or Contractor's response, a Work Change Directive or Change Order will be issued.

7.16 *Submittals*

A. *Shop Drawing and Sample Requirements*

- 1. Before submitting a Shop Drawing or Sample, Contractor shall:
 - a. review and coordinate the Shop Drawing or Sample with other Shop Drawings and Samples and with the requirements of the Work and the Contract Documents;
 - b. determine and verify:
 - 1) all field measurements, quantities, dimensions, specified performance and design criteria, installation requirements, materials, catalog numbers, and similar information with respect to the Submittal;
 - 2) the suitability of all materials and equipment offered with respect to the indicated application, fabrication, shipping, handling, storage, assembly, and installation pertaining to the performance of the Work; and
 - 3) all information relative to Contractor's responsibilities for means, methods, techniques, sequences, and procedures of construction, and safety precautions and programs incident thereto;
 - c. confirm that the Submittal is complete with respect to all related data included in the Submittal.
- 2. Each Shop Drawing or Sample must bear a stamp or specific written certification that Contractor has satisfied Contractor's obligations under the Contract Documents with respect to Contractor's review of that Submittal, and that Contractor approves the Submittal.

3. With each Shop Drawing or Sample, Contractor shall give Engineer specific written notice of any variations that the Submittal may have from the requirements of the Contract Documents. This notice must be set forth in a written communication separate from the Submittal; and, in addition, in the case of a Shop Drawing by a specific notation made on the Shop Drawing itself.
- B. *Submittal Procedures for Shop Drawings and Samples:* Contractor shall label and submit Shop Drawings and Samples to Engineer for review and approval in accordance with the accepted Schedule of Submittals.
1. *Shop Drawings*
 - a. Contractor shall submit the number of copies required in the Specifications.
 - b. Data shown on the Shop Drawings must be complete with respect to quantities, dimensions, specified performance and design criteria, materials, and similar data to show Engineer the services, materials, and equipment Contractor proposes to provide, and to enable Engineer to review the information for the limited purposes required by Paragraph 7.16.C.
 2. *Samples*
 - a. Contractor shall submit the number of Samples required in the Specifications.
 - b. Contractor shall clearly identify each Sample as to material, Supplier, pertinent data such as catalog numbers, the use for which intended and other data as Engineer may require to enable Engineer to review the Submittal for the limited purposes required by Paragraph 7.16.C.
 3. Where a Shop Drawing or Sample is required by the Contract Documents or the Schedule of Submittals, any related Work performed prior to Engineer's review and approval of the pertinent submittal will be at the sole expense and responsibility of Contractor.
- C. *Engineer's Review of Shop Drawings and Samples*
1. Engineer will provide timely review of Shop Drawings and Samples in accordance with the accepted Schedule of Submittals. Engineer's review and approval will be only to determine if the items covered by the Submittals will, after installation or incorporation in the Work, comply with the requirements of the Contract Documents, and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents.
 2. Engineer's review and approval will not extend to means, methods, techniques, sequences, or procedures of construction, or to safety precautions or programs incident thereto.
 3. Engineer's review and approval of a separate item as such will not indicate approval of the assembly in which the item functions.
 4. Engineer's review and approval of a Shop Drawing or Sample will not relieve Contractor from responsibility for any variation from the requirements of the Contract Documents unless Contractor has complied with the requirements of Paragraph 7.16.A.3 and Engineer has given written approval of each such variation by specific written notation thereof incorporated in or accompanying the Shop Drawing or Sample. Engineer will

document any such approved variation from the requirements of the Contract Documents in a Field Order or other appropriate Contract modification.

5. Engineer's review and approval of a Shop Drawing or Sample will not relieve Contractor from responsibility for complying with the requirements of Paragraphs 7.16.A and B.
6. Engineer's review and approval of a Shop Drawing or Sample, or of a variation from the requirements of the Contract Documents, will not, under any circumstances, change the Contract Times or Contract Price, unless such changes are included in a Change Order.
7. Neither Engineer's receipt, review, acceptance, or approval of a Shop Drawing or Sample will result in such item becoming a Contract Document.
8. Contractor shall perform the Work in compliance with the requirements and commitments set forth in approved Shop Drawings and Samples, subject to the provisions of Paragraph 7.16.C.4.

D. Resubmittal Procedures for Shop Drawings and Samples

1. Contractor shall make corrections required by Engineer and shall return the required number of corrected copies of Shop Drawings and submit, as required, new Samples for review and approval. Contractor shall direct specific attention in writing to revisions other than the corrections called for by Engineer on previous Submittals.
2. Contractor shall furnish required Shop Drawing and Sample submittals with sufficient information and accuracy to obtain required approval of an item with no more than two resubmittals. Engineer will record Engineer's time for reviewing a third or subsequent resubmittal of a Shop Drawing or Sample, and Contractor shall be responsible for Engineer's charges to Owner for such time. Owner may impose a set-off against payments due Contractor to secure reimbursement for such charges.
3. If Contractor requests a change of a previously approved Shop Drawing or Sample, Contractor shall be responsible for Engineer's charges to Owner for its review time, and Owner may impose a set-off against payments due Contractor to secure reimbursement for such charges, unless the need for such change is beyond the control of Contractor.

E. Submittals Other than Shop Drawings, Samples, and Owner-Delegated Designs

1. The following provisions apply to all Submittals other than Shop Drawings, Samples, and Owner-delegated designs:
 - a. Contractor shall submit all such Submittals to the Engineer in accordance with the Schedule of Submittals and pursuant to the applicable terms of the Contract Documents.
 - b. Engineer will provide timely review of all such Submittals in accordance with the Schedule of Submittals and return such Submittals with a notation of either Accepted or Not Accepted. Any such Submittal that is not returned within the time established in the Schedule of Submittals will be deemed accepted.
 - c. Engineer's review will be only to determine if the Submittal is acceptable under the requirements of the Contract Documents as to general form and content of the Submittal.

- d. If any such Submittal is not accepted, Contractor shall confer with Engineer regarding the reason for the non-acceptance, and resubmit an acceptable document.
- 2. Procedures for the submittal and acceptance of the Progress Schedule, the Schedule of Submittals, and the Schedule of Values are set forth in Paragraphs 2.03, 2.04, and 2.05.
- F. Owner-delegated Designs: Submittals pursuant to Owner-delegated designs are governed by the provisions of Paragraph 7.19.

7.17 Contractor's General Warranty and Guarantee

- A. Contractor warrants and guarantees to Owner that all Work will be in accordance with the Contract Documents and will not be defective. Engineer is entitled to rely on Contractor's warranty and guarantee.
- B. Owner's rights under this warranty and guarantee are in addition to, and are not limited by, Owner's rights under the correction period provisions of Paragraph 15.08. The time in which Owner may enforce its warranty and guarantee rights under this Paragraph 7.17 is limited only by applicable Laws and Regulations restricting actions to enforce such rights; provided, however, that after the end of the correction period under Paragraph 15.08:
 - 1. Owner shall give Contractor written notice of any defective Work within 60 days of the discovery that such Work is defective; and
 - 2. Such notice will be deemed the start of an event giving rise to a Claim under Paragraph 12.01.B, such that any related Claim must be brought within 30 days of the notice.
- C. Contractor's warranty and guarantee hereunder excludes defects or damage caused by:
 - 1. abuse, or improper modification, maintenance, or operation, by persons other than Contractor, Subcontractors, Suppliers, or any other individual or entity for whom Contractor is responsible; or
 - 2. normal wear and tear under normal usage.
- D. Contractor's obligation to perform and complete the Work in accordance with the Contract Documents is absolute. None of the following will constitute an acceptance of Work that is not in accordance with the Contract Documents, a release of Contractor's obligation to perform the Work in accordance with the Contract Documents, or a release of Owner's warranty and guarantee rights under this Paragraph 7.17:
 - 1. Observations by Engineer;
 - 2. Recommendation by Engineer or payment by Owner of any progress or final payment;
 - 3. The issuance of a certificate of Substantial Completion by Engineer or any payment related thereto by Owner;
 - 4. Use or occupancy of the Work or any part thereof by Owner;
 - 5. Any review and approval of a Shop Drawing or Sample submittal;
 - 6. The issuance of a notice of acceptability by Engineer;
 - 7. The end of the correction period established in Paragraph 15.08;
 - 8. Any inspection, test, or approval by others; or

9. Any correction of defective Work by Owner.
- E. If the Contract requires the Contractor to accept the assignment of a contract entered into by Owner, then the specific warranties, guarantees, and correction obligations contained in the assigned contract will govern with respect to Contractor's performance obligations to Owner for the Work described in the assigned contract.

7.18 *Indemnification*

- A. To the fullest extent permitted by Laws and Regulations, and in addition to any other obligations of Contractor under the Contract or otherwise, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, from losses, damages, costs, and judgments (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court or arbitration or other dispute resolution costs) arising from third-party claims or actions relating to or resulting from the performance or furnishing of the Work, provided that any such claim, action, loss, cost, judgment or damage is attributable to bodily injury, sickness, disease, or death, or to damage to or destruction of tangible property (other than the Work itself), including the loss of use resulting therefrom, but only to the extent caused by any negligent act or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable.
- B. In any and all claims against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, by any employee (or the survivor or personal representative of such employee) of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, the indemnification obligation under Paragraph 7.18.A will not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for Contractor or any such Subcontractor, Supplier, or other individual or entity under workers' compensation acts, disability benefit acts, or other employee benefit acts.

7.19 *Delegation of Professional Design Services*

- A. Owner may require Contractor to provide professional design services for a portion of the Work by express delegation in the Contract Documents. Such delegation will specify the performance and design criteria that such services must satisfy, and the Submittals that Contractor must furnish to Engineer with respect to the Owner-delegated design.
- B. Contractor shall cause such Owner-delegated professional design services to be provided pursuant to the professional standard of care by a properly licensed design professional, whose signature and seal must appear on all drawings, calculations, specifications, certifications, and Submittals prepared by such design professional. Such design professional must issue all certifications of design required by Laws and Regulations.
- C. If a Shop Drawing or other Submittal related to the Owner-delegated design is prepared by Contractor, a Subcontractor, or others for submittal to Engineer, then such Shop Drawing or other Submittal must bear the written approval of Contractor's design professional when submitted by Contractor to Engineer.

- D. Owner and Engineer shall be entitled to rely upon the adequacy, accuracy, and completeness of the services, certifications, and approvals performed or provided by the design professionals retained or employed by Contractor under an Owner-delegated design, subject to the professional standard of care and the performance and design criteria stated in the Contract Documents.
- E. Pursuant to this Paragraph 7.19, Engineer's review, approval, and other determinations regarding design drawings, calculations, specifications, certifications, and other Submittals furnished by Contractor pursuant to an Owner-delegated design will be only for the following limited purposes:
 - 1. Checking for conformance with the requirements of this Paragraph 7.19;
 - 2. Confirming that Contractor (through its design professionals) has used the performance and design criteria specified in the Contract Documents; and
 - 3. Establishing that the design furnished by Contractor is consistent with the design concept expressed in the Contract Documents.
- F. Contractor shall not be responsible for the adequacy of performance or design criteria specified by Owner or Engineer.
- G. Contractor is not required to provide professional services in violation of applicable Laws and Regulations.

ARTICLE 8—OTHER WORK AT THE SITE

8.01 *Other Work*

- A. In addition to and apart from the Work under the Contract Documents, the Owner may perform other work at or adjacent to the Site. Such other work may be performed by Owner's employees, or through contracts between the Owner and third parties. Owner may also arrange to have third-party utility owners perform work on their utilities and facilities at or adjacent to the Site.
- B. If Owner performs other work at or adjacent to the Site with Owner's employees, or through contracts for such other work, then Owner shall give Contractor written notice thereof prior to starting any such other work. If Owner has advance information regarding the start of any third-party utility work that Owner has arranged to take place at or adjacent to the Site, Owner shall provide such information to Contractor.
- C. Contractor shall afford proper and safe access to the Site to each contractor that performs such other work, each utility owner performing other work, and Owner, if Owner is performing other work with Owner's employees, and provide a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such other work.
- D. Contractor shall do all cutting, fitting, and patching of the Work that may be required to properly connect or otherwise make its several parts come together and properly integrate with such other work. Contractor shall not endanger any work of others by cutting, excavating, or otherwise altering such work; provided, however, that Contractor may cut or alter others' work with the written consent of Engineer and the others whose work will be affected.

- E. If the proper execution or results of any part of Contractor's Work depends upon work performed by others, Contractor shall inspect such other work and promptly report to Engineer in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of Contractor's Work. Contractor's failure to so report will constitute an acceptance of such other work as fit and proper for integration with Contractor's Work except for latent defects and deficiencies in such other work.
- F. The provisions of this article are not applicable to work that is performed by third-party utilities or other third-party entities without a contract with Owner, or that is performed without having been arranged by Owner. If such work occurs, then any related delay, disruption, or interference incurred by Contractor is governed by the provisions of Paragraph 4.05.C.3.

8.02 *Coordination*

- A. If Owner intends to contract with others for the performance of other work at or adjacent to the Site, to perform other work at or adjacent to the Site with Owner's employees, or to arrange to have utility owners perform work at or adjacent to the Site, the following will be set forth in the Supplementary Conditions or provided to Contractor prior to the start of any such other work:
 - 1. The identity of the individual or entity that will have authority and responsibility for coordination of the activities among the various contractors;
 - 2. An itemization of the specific matters to be covered by such authority and responsibility; and
 - 3. The extent of such authority and responsibilities.
- B. Unless otherwise provided in the Supplementary Conditions, Owner shall have sole authority and responsibility for such coordination.

8.03 *Legal Relationships*

- A. If, in the course of performing other work for Owner at or adjacent to the Site, the Owner's employees, any other contractor working for Owner, or any utility owner that Owner has arranged to perform work, causes damage to the Work or to the property of Contractor or its Subcontractors, or delays, disrupts, interferes with, or increases the scope or cost of the performance of the Work, through actions or inaction, then Contractor shall be entitled to an equitable adjustment in the Contract Price or the Contract Times. Contractor must submit any Change Proposal seeking an equitable adjustment in the Contract Price or the Contract Times under this paragraph within 30 days of the damaging, delaying, disrupting, or interfering event. The entitlement to, and extent of, any such equitable adjustment will take into account information (if any) regarding such other work that was provided to Contractor in the Contract Documents prior to the submittal of the Bid or the final negotiation of the terms of the Contract, and any remedies available to Contractor under Laws or Regulations concerning utility action or inaction. When applicable, any such equitable adjustment in Contract Price will be conditioned on Contractor assigning to Owner all Contractor's rights against such other contractor or utility owner with respect to the damage, delay, disruption, or interference that is the subject of the adjustment. Contractor's entitlement to an adjustment of the Contract Times or Contract Price is subject to the provisions of Paragraphs 4.05.D and 4.05.E.

- B. Contractor shall take reasonable and customary measures to avoid damaging, delaying, disrupting, or interfering with the work of Owner, any other contractor, or any utility owner performing other work at or adjacent to the Site.
 - 1. If Contractor fails to take such measures and as a result damages, delays, disrupts, or interferes with the work of any such other contractor or utility owner, then Owner may impose a set-off against payments due Contractor, and assign to such other contractor or utility owner the Owner's contractual rights against Contractor with respect to the breach of the obligations set forth in this Paragraph 8.03.B.
 - 2. When Owner is performing other work at or adjacent to the Site with Owner's employees, Contractor shall be liable to Owner for damage to such other work, and for the reasonable direct delay, disruption, and interference costs incurred by Owner as a result of Contractor's failure to take reasonable and customary measures with respect to Owner's other work. In response to such damage, delay, disruption, or interference, Owner may impose a set-off against payments due Contractor.
- C. If Contractor damages, delays, disrupts, or interferes with the work of any other contractor, or any utility owner performing other work at or adjacent to the Site, through Contractor's failure to take reasonable and customary measures to avoid such impacts, or if any claim arising out of Contractor's actions, inactions, or negligence in performance of the Work at or adjacent to the Site is made by any such other contractor or utility owner against Contractor, Owner, or Engineer, then Contractor shall (1) promptly attempt to settle the claim as to all parties through negotiations with such other contractor or utility owner, or otherwise resolve the claim by arbitration or other dispute resolution proceeding or at law, and (2) indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against any such claims, and against all costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such damage, delay, disruption, or interference.

ARTICLE 9—OWNER'S RESPONSIBILITIES

9.01 *Communications to Contractor*

- A. Except as otherwise provided in these General Conditions, Owner shall issue all communications to Contractor through Engineer.

9.02 *Replacement of Engineer*

- A. Owner may at its discretion appoint an engineer to replace Engineer, provided Contractor makes no reasonable objection to the replacement engineer. The replacement engineer's status under the Contract Documents will be that of the former Engineer.

9.03 *Furnish Data*

- A. Owner shall promptly furnish the data required of Owner under the Contract Documents.

9.04 *Pay When Due*

- A. Owner shall make payments to Contractor when they are due as provided in the Agreement.

9.05 *Lands and Easements; Reports, Tests, and Drawings*

- A. Owner's duties with respect to providing lands and easements are set forth in Paragraph 5.01.
- B. Owner's duties with respect to providing engineering surveys to establish reference points are set forth in Paragraph 4.03.
- C. Article 5 refers to Owner's identifying and making available to Contractor copies of reports of explorations and tests of conditions at the Site, and drawings of physical conditions relating to existing surface or subsurface structures at the Site.

9.06 *Insurance*

- A. Owner's responsibilities, if any, with respect to purchasing and maintaining liability and property insurance are set forth in Article 6.

9.07 *Change Orders*

- A. Owner's responsibilities with respect to Change Orders are set forth in Article 11.

9.08 *Inspections, Tests, and Approvals*

- A. Owner's responsibility with respect to certain inspections, tests, and approvals is set forth in Paragraph 14.02.B.

9.09 *Limitations on Owner's Responsibilities*

- A. The Owner shall not supervise, direct, or have control or authority over, nor be responsible for, Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Owner will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.

9.10 *Undisclosed Hazardous Environmental Condition*

- A. Owner's responsibility in respect to an undisclosed Hazardous Environmental Condition is set forth in Paragraph 5.06.

9.11 *Evidence of Financial Arrangements*

- A. Upon request of Contractor, Owner shall furnish Contractor reasonable evidence that financial arrangements have been made to satisfy Owner's obligations under the Contract (including obligations under proposed changes in the Work).

9.12 *Safety Programs*

- A. While at the Site, Owner's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Owner has been informed.
- B. Owner shall furnish copies of any applicable Owner safety programs to Contractor.

ARTICLE 10—ENGINEER'S STATUS DURING CONSTRUCTION

10.01 *Owner's Representative*

- A. Engineer will be Owner's representative during the construction period. The duties and responsibilities and the limitations of authority of Engineer as Owner's representative during construction are set forth in the Contract.

10.02 *Visits to Site*

- A. Engineer will make visits to the Site at intervals appropriate to the various stages of construction as Engineer deems necessary in order to observe, as an experienced and qualified design professional, the progress that has been made and the quality of the various aspects of Contractor's executed Work. Based on information obtained during such visits and observations, Engineer, for the benefit of Owner, will determine, in general, if the Work is proceeding in accordance with the Contract Documents. Engineer will not be required to make exhaustive or continuous inspections on the Site to check the quality or quantity of the Work. Engineer's efforts will be directed toward providing for Owner a greater degree of confidence that the completed Work will conform generally to the Contract Documents. On the basis of such visits and observations, Engineer will keep Owner informed of the progress of the Work and will endeavor to guard Owner against defective Work.
- B. Engineer's visits and observations are subject to all the limitations on Engineer's authority and responsibility set forth in Paragraph 10.07. Particularly, but without limitation, during or as a result of Engineer's visits or observations of Contractor's Work, Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work.

10.03 *Resident Project Representative*

- A. If Owner and Engineer have agreed that Engineer will furnish a Resident Project Representative to represent Engineer at the Site and assist Engineer in observing the progress and quality of the Work, then the authority and responsibilities of any such Resident Project Representative will be as provided in the Supplementary Conditions, and limitations on the responsibilities thereof will be as provided in the Supplementary Conditions and in Paragraph 10.07.
- B. If Owner designates an individual or entity who is not Engineer's consultant, agent, or employee to represent Owner at the Site, then the responsibilities and authority of such individual or entity will be as provided in the Supplementary Conditions.

10.04 *Engineer's Authority*

- A. Engineer has the authority to reject Work in accordance with Article 14.
- B. Engineer's authority as to Submittals is set forth in Paragraph 7.16.
- C. Engineer's authority as to design drawings, calculations, specifications, certifications and other Submittals from Contractor in response to Owner's delegation (if any) to Contractor of professional design services, is set forth in Paragraph 7.19.
- D. Engineer's authority as to changes in the Work is set forth in Article 11.

E. Engineer's authority as to Applications for Payment is set forth in Article 15.

10.05 *Determinations for Unit Price Work*

A. Engineer will determine the actual quantities and classifications of Unit Price Work performed by Contractor as set forth in Paragraph 13.03.

10.06 *Decisions on Requirements of Contract Documents and Acceptability of Work*

A. Engineer will render decisions regarding the requirements of the Contract Documents, and judge the acceptability of the Work, pursuant to the specific procedures set forth herein for initial interpretations, Change Proposals, and acceptance of the Work. In rendering such decisions and judgments, Engineer will not show partiality to Owner or Contractor, and will not be liable to Owner, Contractor, or others in connection with any proceedings, interpretations, decisions, or judgments conducted or rendered in good faith.

10.07 *Limitations on Engineer's Authority and Responsibilities*

A. Neither Engineer's authority or responsibility under this Article 10 or under any other provision of the Contract, nor any decision made by Engineer in good faith either to exercise or not exercise such authority or responsibility or the undertaking, exercise, or performance of any authority or responsibility by Engineer, will create, impose, or give rise to any duty in contract, tort, or otherwise owed by Engineer to Contractor, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.

B. Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Engineer will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.

C. Engineer will not be responsible for the acts or omissions of Contractor or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.

D. Engineer's review of the final Application for Payment and accompanying documentation, and all maintenance and operating instructions, schedules, guarantees, bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by Contractor under Paragraph 15.06.A, will only be to determine generally that their content complies with the requirements of, and in the case of certificates of inspections, tests, and approvals, that the results certified indicate compliance with the Contract Documents.

E. The limitations upon authority and responsibility set forth in this Paragraph 10.07 also apply to the Resident Project Representative, if any.

10.08 *Compliance with Safety Program*

A. While at the Site, Engineer's employees and representatives will comply with the specific applicable requirements of Owner's and Contractor's safety programs of which Engineer has been informed.

ARTICLE 11—CHANGES TO THE CONTRACT

11.01 *Amending and Supplementing the Contract*

- A. The Contract may be amended or supplemented by a Change Order, a Work Change Directive, or a Field Order.
- B. If an amendment or supplement to the Contract includes a change in the Contract Price or the Contract Times, such amendment or supplement must be set forth in a Change Order.
- C. All changes to the Contract that involve (1) the performance or acceptability of the Work, (2) the design (as set forth in the Drawings, Specifications, or otherwise), or (3) other engineering or technical matters, must be supported by Engineer's recommendation. Owner and Contractor may amend other terms and conditions of the Contract without the recommendation of the Engineer.

11.02 *Change Orders*

- A. Owner and Contractor shall execute appropriate Change Orders covering:
 - 1. Changes in Contract Price or Contract Times which are agreed to by the parties, including any undisputed sum or amount of time for Work actually performed in accordance with a Work Change Directive;
 - 2. Changes in Contract Price resulting from an Owner set-off, unless Contractor has duly contested such set-off;
 - 3. Changes in the Work which are: (a) ordered by Owner pursuant to Paragraph 11.05, (b) required because of Owner's acceptance of defective Work under Paragraph 14.04 or Owner's correction of defective Work under Paragraph 14.07, or (c) agreed to by the parties, subject to the need for Engineer's recommendation if the change in the Work involves the design (as set forth in the Drawings, Specifications, or otherwise) or other engineering or technical matters; and
 - 4. Changes that embody the substance of any final and binding results under: Paragraph 11.03.B, resolving the impact of a Work Change Directive; Paragraph 11.09, concerning Change Proposals; Article 12, Claims; Paragraph 13.02.D, final adjustments resulting from allowances; Paragraph 13.03.D, final adjustments relating to determination of quantities for Unit Price Work; and similar provisions.
- B. If Owner or Contractor refuses to execute a Change Order that is required to be executed under the terms of Paragraph 11.02.A, it will be deemed to be of full force and effect, as if fully executed.

11.03 *Work Change Directives*

- A. A Work Change Directive will not change the Contract Price or the Contract Times but is evidence that the parties expect that the modification ordered or documented by a Work Change Directive will be incorporated in a subsequently issued Change Order, following negotiations by the parties as to the Work Change Directive's effect, if any, on the Contract Price and Contract Times; or, if negotiations are unsuccessful, by a determination under the terms of the Contract Documents governing adjustments, expressly including Paragraph 11.07 regarding change of Contract Price.

- B. If Owner has issued a Work Change Directive and:
 - 1. Contractor believes that an adjustment in Contract Times or Contract Price is necessary, then Contractor shall submit any Change Proposal seeking such an adjustment no later than 30 days after the completion of the Work set out in the Work Change Directive.
 - 2. Owner believes that an adjustment in Contract Times or Contract Price is necessary, then Owner shall submit any Claim seeking such an adjustment no later than 60 days after issuance of the Work Change Directive.

11.04 *Field Orders*

- A. Engineer may authorize minor changes in the Work if the changes do not involve an adjustment in the Contract Price or the Contract Times and are compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. Such changes will be accomplished by a Field Order and will be binding on Owner and also on Contractor, which shall perform the Work involved promptly.
- B. If Contractor believes that a Field Order justifies an adjustment in the Contract Price or Contract Times, then before proceeding with the Work at issue, Contractor shall submit a Change Proposal as provided herein.

11.05 *Owner-Authorized Changes in the Work*

- A. Without invalidating the Contract and without notice to any surety, Owner may, at any time or from time to time, order additions, deletions, or revisions in the Work. Changes involving the design (as set forth in the Drawings, Specifications, or otherwise) or other engineering or technical matters will be supported by Engineer's recommendation.
- B. Such changes in the Work may be accomplished by a Change Order, if Owner and Contractor have agreed as to the effect, if any, of the changes on Contract Times or Contract Price; or by a Work Change Directive. Upon receipt of any such document, Contractor shall promptly proceed with the Work involved; or, in the case of a deletion in the Work, promptly cease construction activities with respect to such deleted Work. Added or revised Work must be performed under the applicable conditions of the Contract Documents.
- C. Nothing in this Paragraph 11.05 obligates Contractor to undertake work that Contractor reasonably concludes cannot be performed in a manner consistent with Contractor's safety obligations under the Contract Documents or Laws and Regulations.

11.06 *Unauthorized Changes in the Work*

- A. Contractor shall not be entitled to an increase in the Contract Price or an extension of the Contract Times with respect to any work performed that is not required by the Contract Documents, as amended, modified, or supplemented, except in the case of an emergency as provided in Paragraph 7.15 or in the case of uncovering Work as provided in Paragraph 14.05.C.2.

11.07 *Change of Contract Price*

- A. The Contract Price may only be changed by a Change Order. Any Change Proposal for an adjustment in the Contract Price must comply with the provisions of Paragraph 11.09. Any Claim for an adjustment of Contract Price must comply with the provisions of Article 12.
- B. An adjustment in the Contract Price will be determined as follows:

1. Where the Work involved is covered by unit prices contained in the Contract Documents, then by application of such unit prices to the quantities of the items involved (subject to the provisions of Paragraph 13.03);
 2. Where the Work involved is not covered by unit prices contained in the Contract Documents, then by a mutually agreed lump sum (which may include an allowance for overhead and profit not necessarily in accordance with Paragraph 11.07.C.2); or
 3. Where the Work involved is not covered by unit prices contained in the Contract Documents and the parties do not reach mutual agreement to a lump sum, then on the basis of the Cost of the Work (determined as provided in Paragraph 13.01) plus a Contractor's fee for overhead and profit (determined as provided in Paragraph 11.07.C).
- C. *Contractor's Fee:* When applicable, the Contractor's fee for overhead and profit will be determined as follows:
1. A mutually acceptable fixed fee; or
 2. If a fixed fee is not agreed upon, then a fee based on the following percentages of the various portions of the Cost of the Work:
 - a. For costs incurred under Paragraphs 13.01.B.1 and 13.01.B.2, the Contractor's fee will be 15 percent;
 - b. For costs incurred under Paragraph 13.01.B.3, the Contractor's fee will be 5 percent;
 - c. Where one or more tiers of subcontracts are on the basis of Cost of the Work plus a fee and no fixed fee is agreed upon, the intent of Paragraphs 11.07.C.2.a and 11.07.C.2.b is that the Contractor's fee will be based on: (1) a fee of 15 percent of the costs incurred under Paragraphs 13.01.B.1 and 13.01.B.2 by the Subcontractor that actually performs the Work, at whatever tier, and (2) with respect to Contractor itself and to any Subcontractors of a tier higher than that of the Subcontractor that actually performs the Work, a fee of 5 percent of the amount (fee plus underlying costs incurred) attributable to the next lower tier Subcontractor; provided, however, that for any such subcontracted Work the maximum total fee to be paid by Owner will be no greater than 27 percent of the costs incurred by the Subcontractor that actually performs the Work;
 - d. No fee will be payable on the basis of costs itemized under Paragraphs 13.01.B.4, 13.01.B.5, and 13.01.C;
 - e. The amount of credit to be allowed by Contractor to Owner for any change which results in a net decrease in Cost of the Work will be the amount of the actual net decrease in Cost of the Work and a deduction of an additional amount equal to 5 percent of such actual net decrease in Cost of the Work; and
 - f. When both additions and credits are involved in any one change or Change Proposal, the adjustment in Contractor's fee will be computed by determining the sum of the costs in each of the cost categories in Paragraph 13.01.B (specifically, payroll costs, Paragraph 13.01.B.1; incorporated materials and equipment costs, Paragraph 13.01.B.2; Subcontract costs, Paragraph 13.01.B.3; special consultants costs, Paragraph 13.01.B.4; and other costs, Paragraph 13.01.B.5) and applying to each such cost category sum the appropriate fee from Paragraphs 11.07.C.2.a through 11.07.C.2.e, inclusive.

11.08 *Change of Contract Times*

- A. The Contract Times may only be changed by a Change Order. Any Change Proposal for an adjustment in the Contract Times must comply with the provisions of Paragraph 11.09. Any Claim for an adjustment in the Contract Times must comply with the provisions of Article 12.
- B. Delay, disruption, and interference in the Work, and any related changes in Contract Times, are addressed in and governed by Paragraph 4.05.

11.09 *Change Proposals*

- A. *Purpose and Content:* Contractor shall submit a Change Proposal to Engineer to request an adjustment in the Contract Times or Contract Price; contest an initial decision by Engineer concerning the requirements of the Contract Documents or relating to the acceptability of the Work under the Contract Documents; challenge a set-off against payment due; or seek other relief under the Contract. The Change Proposal will specify any proposed change in Contract Times or Contract Price, or other proposed relief, and explain the reason for the proposed change, with citations to any governing or applicable provisions of the Contract Documents. Each Change Proposal will address only one issue, or a set of closely related issues.

- B. *Change Proposal Procedures*

- 1. *Submittal:* Contractor shall submit each Change Proposal to Engineer within 30 days after the start of the event giving rise thereto, or after such initial decision.
- 2. *Supporting Data:* The Contractor shall submit supporting data, including the proposed change in Contract Price or Contract Time (if any), to the Engineer and Owner within 15 days after the submittal of the Change Proposal.
 - a. Change Proposals based on or related to delay, interruption, or interference must comply with the provisions of Paragraphs 4.05.D and 4.05.E.
 - b. Change proposals related to a change of Contract Price must include full and detailed accounts of materials incorporated into the Work and labor and equipment used for the subject Work.

The supporting data must be accompanied by a written statement that the supporting data are accurate and complete, and that any requested time or price adjustment is the entire adjustment to which Contractor believes it is entitled as a result of said event.

- 3. *Engineer's Initial Review:* Engineer will advise Owner regarding the Change Proposal, and consider any comments or response from Owner regarding the Change Proposal. If in its discretion Engineer concludes that additional supporting data is needed before conducting a full review and making a decision regarding the Change Proposal, then Engineer may request that Contractor submit such additional supporting data by a date specified by Engineer, prior to Engineer beginning its full review of the Change Proposal.
- 4. *Engineer's Full Review and Action on the Change Proposal:* Upon receipt of Contractor's supporting data (including any additional data requested by Engineer), Engineer will conduct a full review of each Change Proposal and, within 30 days after such receipt of the Contractor's supporting data, either approve the Change Proposal in whole, deny it in whole, or approve it in part and deny it in part. Such actions must be in writing, with a copy provided to Owner and Contractor. If Engineer does not take action on the Change

Proposal within 30 days, then either Owner or Contractor may at any time thereafter submit a letter to the other party indicating that as a result of Engineer's inaction the Change Proposal is deemed denied, thereby commencing the time for appeal of the denial under Article 12.

5. *Binding Decision*: Engineer's decision is final and binding upon Owner and Contractor, unless Owner or Contractor appeals the decision by filing a Claim under Article 12.
- C. *Resolution of Certain Change Proposals*: If the Change Proposal does not involve the design (as set forth in the Drawings, Specifications, or otherwise), the acceptability of the Work, or other engineering or technical matters, then Engineer will notify the parties in writing that the Engineer is unable to resolve the Change Proposal. For purposes of further resolution of such a Change Proposal, such notice will be deemed a denial, and Contractor may choose to seek resolution under the terms of Article 12.
- D. *Post-Completion*: Contractor shall not submit any Change Proposals after Engineer issues a written recommendation of final payment pursuant to Paragraph 15.06.B.

11.10 *Notification to Surety*

- A. If the provisions of any bond require notice to be given to a surety of any change affecting the general scope of the Work or the provisions of the Contract Documents (including, but not limited to, Contract Price or Contract Times), the giving of any such notice will be Contractor's responsibility. The amount of each applicable bond will be adjusted to reflect the effect of any such change.

ARTICLE 12—CLAIMS

12.01 *Claims*

- A. *Claims Process*: The following disputes between Owner and Contractor are subject to the Claims process set forth in this article:
 1. Appeals by Owner or Contractor of Engineer's decisions regarding Change Proposals;
 2. Owner demands for adjustments in the Contract Price or Contract Times, or other relief under the Contract Documents;
 3. Disputes that Engineer has been unable to address because they do not involve the design (as set forth in the Drawings, Specifications, or otherwise), the acceptability of the Work, or other engineering or technical matters; and
 4. Subject to the waiver provisions of Paragraph 15.07, any dispute arising after Engineer has issued a written recommendation of final payment pursuant to Paragraph 15.06.B.
- B. *Submittal of Claim*: The party submitting a Claim shall deliver it directly to the other party to the Contract promptly (but in no event later than 30 days) after the start of the event giving rise thereto; in the case of appeals regarding Change Proposals within 30 days of the decision under appeal. The party submitting the Claim shall also furnish a copy to the Engineer, for its information only. The responsibility to substantiate a Claim rests with the party making the Claim. In the case of a Claim by Contractor seeking an increase in the Contract Times or Contract Price, Contractor shall certify that the Claim is made in good faith, that the supporting data are accurate and complete, and that to the best of Contractor's knowledge

and belief the amount of time or money requested accurately reflects the full amount to which Contractor is entitled.

- C. *Review and Resolution*: The party receiving a Claim shall review it thoroughly, giving full consideration to its merits. The two parties shall seek to resolve the Claim through the exchange of information and direct negotiations. The parties may extend the time for resolving the Claim by mutual agreement. All actions taken on a Claim will be stated in writing and submitted to the other party, with a copy to Engineer.
- D. *Mediation*
 - 1. At any time after initiation of a Claim, Owner and Contractor may mutually agree to mediation of the underlying dispute. The agreement to mediate will stay the Claim submittal and response process.
 - 2. If Owner and Contractor agree to mediation, then after 60 days from such agreement, either Owner or Contractor may unilaterally terminate the mediation process, and the Claim submittal and decision process will resume as of the date of the termination. If the mediation proceeds but is unsuccessful in resolving the dispute, the Claim submittal and decision process will resume as of the date of the conclusion of the mediation, as determined by the mediator.
 - 3. Owner and Contractor shall each pay one-half of the mediator's fees and costs.
- E. *Partial Approval*: If the party receiving a Claim approves the Claim in part and denies it in part, such action will be final and binding unless within 30 days of such action the other party invokes the procedure set forth in Article 17 for final resolution of disputes.
- F. *Denial of Claim*: If efforts to resolve a Claim are not successful, the party receiving the Claim may deny it by giving written notice of denial to the other party. If the receiving party does not take action on the Claim within 90 days, then either Owner or Contractor may at any time thereafter submit a letter to the other party indicating that as a result of the inaction, the Claim is deemed denied, thereby commencing the time for appeal of the denial. A denial of the Claim will be final and binding unless within 30 days of the denial the other party invokes the procedure set forth in Article 17 for the final resolution of disputes.
- G. *Final and Binding Results*: If the parties reach a mutual agreement regarding a Claim, whether through approval of the Claim, direct negotiations, mediation, or otherwise; or if a Claim is approved in part and denied in part, or denied in full, and such actions become final and binding; then the results of the agreement or action on the Claim will be incorporated in a Change Order or other written document to the extent they affect the Contract, including the Work, the Contract Times, or the Contract Price.

ARTICLE 13—COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

13.01 *Cost of the Work*

- A. *Purposes for Determination of Cost of the Work*: The term Cost of the Work means the sum of all costs necessary for the proper performance of the Work at issue, as further defined below. The provisions of this Paragraph 13.01 are used for two distinct purposes:
 - 1. To determine Cost of the Work when Cost of the Work is a component of the Contract Price, under cost-plus-fee, time-and-materials, or other cost-based terms; or

2. When needed to determine the value of a Change Order, Change Proposal, Claim, set-off, or other adjustment in Contract Price. When the value of any such adjustment is determined on the basis of Cost of the Work, Contractor is entitled only to those additional or incremental costs required because of the change in the Work or because of the event giving rise to the adjustment.
- B. *Costs Included:* Except as otherwise may be agreed to in writing by Owner, costs included in the Cost of the Work will be in amounts no higher than those commonly incurred in the locality of the Project, will not include any of the costs itemized in Paragraph 13.01.C, and will include only the following items:
1. Payroll costs for employees in the direct employ of Contractor in the performance of the Work under schedules of job classifications agreed upon by Owner and Contractor in advance of the subject Work. Such employees include, without limitation, superintendents, foremen, safety managers, safety representatives, and other personnel employed full time on the Work. Payroll costs for employees not employed full time on the Work will be apportioned on the basis of their time spent on the Work. Payroll costs include, but are not limited to, salaries and wages plus the cost of fringe benefits, which include social security contributions, unemployment, excise, and payroll taxes, workers' compensation, health and retirement benefits, sick leave, and vacation and holiday pay applicable thereto. The expenses of performing Work outside of regular working hours, on Saturday, Sunday, or legal holidays, will be included in the above to the extent authorized by Owner.
 2. Cost of all materials and equipment furnished and incorporated in the Work, including costs of transportation and storage thereof, and Suppliers' field services required in connection therewith. All cash discounts accrue to Contractor unless Owner deposits funds with Contractor with which to make payments, in which case the cash discounts will accrue to Owner. All trade discounts, rebates, and refunds and returns from sale of surplus materials and equipment will accrue to Owner, and Contractor shall make provisions so that they may be obtained.
 3. Payments made by Contractor to Subcontractors for Work performed by Subcontractors. If required by Owner, Contractor shall obtain competitive bids from subcontractors acceptable to Owner and Contractor and shall deliver such bids to Owner, which will then determine, with the advice of Engineer, which bids, if any, will be acceptable. If any subcontract provides that the Subcontractor is to be paid on the basis of Cost of the Work plus a fee, the Subcontractor's Cost of the Work and fee will be determined in the same manner as Contractor's Cost of the Work and fee as provided in this Paragraph 13.01.
 4. Costs of special consultants (including but not limited to engineers, architects, testing laboratories, surveyors, attorneys, and accountants) employed or retained for services specifically related to the Work.
 5. Other costs consisting of the following:
 - a. The proportion of necessary transportation, travel, and subsistence expenses of Contractor's employees incurred in discharge of duties connected with the Work.
 - b. Cost, including transportation and maintenance, of all materials, supplies, equipment, machinery, appliances, office, and temporary facilities at the Site, which are

consumed in the performance of the Work, and cost, less market value, of such items used but not consumed which remain the property of Contractor.

- 1) In establishing included costs for materials such as scaffolding, plating, or sheeting, consideration will be given to the actual or the estimated life of the material for use on other projects; or rental rates may be established on the basis of purchase or salvage value of such items, whichever is less. Contractor will not be eligible for compensation for such items in an amount that exceeds the purchase cost of such item.

c. *Construction Equipment Rental*

- 1) Rentals of all construction equipment and machinery, and the parts thereof, in accordance with rental agreements approved by Owner as to price (including any surcharge or special rates applicable to overtime use of the construction equipment or machinery), and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs will be in accordance with the terms of said rental agreements. The rental of any such equipment, machinery, or parts must cease when the use thereof is no longer necessary for the Work.
 - 2) Costs for equipment and machinery owned by Contractor or a Contractor-related entity will be paid at a rate shown for such equipment in the equipment rental rate book specified in the Supplementary Conditions. An hourly rate will be computed by dividing the monthly rates by 176. These computed rates will include all operating costs.
 - 3) With respect to Work that is the result of a Change Order, Change Proposal, Claim, set-off, or other adjustment in Contract Price ("changed Work"), included costs will be based on the time the equipment or machinery is in use on the changed Work and the costs of transportation, loading, unloading, assembly, dismantling, and removal when directly attributable to the changed Work. The cost of any such equipment or machinery, or parts thereof, must cease to accrue when the use thereof is no longer necessary for the changed Work.
- d. Sales, consumer, use, and other similar taxes related to the Work, and for which Contractor is liable, as imposed by Laws and Regulations.
- e. Deposits lost for causes other than negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, and royalty payments and fees for permits and licenses.
- f. Losses and damages (and related expenses) caused by damage to the Work, not compensated by insurance or otherwise, sustained by Contractor in connection with the performance of the Work (except losses and damages within the deductible amounts of builder's risk or other property insurance established in accordance with Paragraph 6.04), provided such losses and damages have resulted from causes other than the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable. Such losses include settlements made with the written consent and approval of Owner. No such losses, damages, and expenses will be included in the Cost of the Work for the purpose of determining Contractor's fee.

- g. The cost of utilities, fuel, and sanitary facilities at the Site.
 - h. Minor expenses such as communication service at the Site, express and courier services, and similar petty cash items in connection with the Work.
 - i. The costs of premiums for all bonds and insurance that Contractor is required by the Contract Documents to purchase and maintain.
- C. *Costs Excluded:* The term Cost of the Work does not include any of the following items:
- 1. Payroll costs and other compensation of Contractor's officers, executives, principals, general managers, engineers, architects, estimators, attorneys, auditors, accountants, purchasing and contracting agents, expeditors, timekeepers, clerks, and other personnel employed by Contractor, whether at the Site or in Contractor's principal or branch office for general administration of the Work and not specifically included in the agreed upon schedule of job classifications referred to in Paragraph 13.01.B.1 or specifically covered by Paragraph 13.01.B.4. The payroll costs and other compensation excluded here are to be considered administrative costs covered by the Contractor's fee.
 - 2. The cost of purchasing, renting, or furnishing small tools and hand tools.
 - 3. Expenses of Contractor's principal and branch offices other than Contractor's office at the Site.
 - 4. Any part of Contractor's capital expenses, including interest on Contractor's capital employed for the Work and charges against Contractor for delinquent payments.
 - 5. Costs due to the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but not limited to, the correction of defective Work, disposal of materials or equipment wrongly supplied, and making good any damage to property.
 - 6. Expenses incurred in preparing and advancing Claims.
 - 7. Other overhead or general expense costs of any kind and the costs of any item not specifically and expressly included in Paragraph 13.01.B.
- D. *Contractor's Fee*
- 1. When the Work as a whole is performed on the basis of cost-plus-a-fee, then:
 - a. Contractor's fee for the Work set forth in the Contract Documents as of the Effective Date of the Contract will be determined as set forth in the Agreement.
 - b. for any Work covered by a Change Order, Change Proposal, Claim, set-off, or other adjustment in Contract Price on the basis of Cost of the Work, Contractor's fee will be determined as follows:
 - 1) When the fee for the Work as a whole is a percentage of the Cost of the Work, the fee will automatically adjust as the Cost of the Work changes.
 - 2) When the fee for the Work as a whole is a fixed fee, the fee for any additions or deletions will be determined in accordance with Paragraph 11.07.C.2.
 - 2. When the Work as a whole is performed on the basis of a stipulated sum, or any other basis other than cost-plus-a-fee, then Contractor's fee for any Work covered by a Change

Order, Change Proposal, Claim, set-off, or other adjustment in Contract Price on the basis of Cost of the Work will be determined in accordance with Paragraph 11.07.C.2.

- E. *Documentation and Audit*: Whenever the Cost of the Work for any purpose is to be determined pursuant to this Article 13, Contractor and pertinent Subcontractors will establish and maintain records of the costs in accordance with generally accepted accounting practices. Subject to prior written notice, Owner will be afforded reasonable access, during normal business hours, to all Contractor's accounts, records, books, correspondence, instructions, drawings, receipts, vouchers, memoranda, and similar data relating to the Cost of the Work and Contractor's fee. Contractor shall preserve all such documents for a period of three years after the final payment by Owner. Pertinent Subcontractors will afford such access to Owner, and preserve such documents, to the same extent required of Contractor.

13.02 Allowances

- A. It is understood that Contractor has included in the Contract Price all allowances so named in the Contract Documents and shall cause the Work so covered to be performed for such sums and by such persons or entities as may be acceptable to Owner and Engineer.
- B. *Cash Allowances*: Contractor agrees that:
1. the cash allowances include the cost to Contractor (less any applicable trade discounts) of materials and equipment required by the allowances to be delivered at the Site, and all applicable taxes; and
 2. Contractor's costs for unloading and handling on the Site, labor, installation, overhead, profit, and other expenses contemplated for the cash allowances have been included in the Contract Price and not in the allowances, and no demand for additional payment for any of the foregoing will be valid.
- C. *Owner's Contingency Allowance*: Contractor agrees that an Owner's contingency allowance, if any, is for the sole use of Owner to cover unanticipated costs.
- D. Prior to final payment, an appropriate Change Order will be issued as recommended by Engineer to reflect actual amounts due Contractor for Work covered by allowances, and the Contract Price will be correspondingly adjusted.

13.03 Unit Price Work

- A. Where the Contract Documents provide that all or part of the Work is to be Unit Price Work, initially the Contract Price will be deemed to include for all Unit Price Work an amount equal to the sum of the unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement.
- B. The estimated quantities of items of Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Payments to Contractor for Unit Price Work will be based on actual quantities.
- C. Each unit price will be deemed to include an amount considered by Contractor to be adequate to cover Contractor's overhead and profit for each separately identified item.
- D. Engineer will determine the actual quantities and classifications of Unit Price Work performed by Contractor. Engineer will review with Contractor the Engineer's preliminary determinations on such matters before rendering a written decision thereon (by recommendation of an Application for Payment or otherwise). Engineer's written decision

thereon will be final and binding (except as modified by Engineer to reflect changed factual conditions or more accurate data) upon Owner and Contractor, and the final adjustment of Contract Price will be set forth in a Change Order, subject to the provisions of the following paragraph.

E. *Adjustments in Unit Price*

1. Contractor or Owner shall be entitled to an adjustment in the unit price with respect to an item of Unit Price Work if:
 - a. the quantity of the item of Unit Price Work performed by Contractor differs materially and significantly from the estimated quantity of such item indicated in the Agreement; and
 - b. Contractor's unit costs to perform the item of Unit Price Work have changed materially and significantly as a result of the quantity change.
2. The adjustment in unit price will account for and be coordinated with any related changes in quantities of other items of Work, and in Contractor's costs to perform such other Work, such that the resulting overall change in Contract Price is equitable to Owner and Contractor.
3. Adjusted unit prices will apply to all units of that item.

ARTICLE 14—TESTS AND INSPECTIONS; CORRECTION, REMOVAL, OR ACCEPTANCE OF DEFECTIVE WORK

14.01 *Access to Work*

- A. Owner, Engineer, their consultants and other representatives and personnel of Owner, independent testing laboratories, and authorities having jurisdiction have access to the Site and the Work at reasonable times for their observation, inspection, and testing. Contractor shall provide them proper and safe conditions for such access and advise them of Contractor's safety procedures and programs so that they may comply with such procedures and programs as applicable.

14.02 *Tests, Inspections, and Approvals*

- A. Contractor shall give Engineer timely notice of readiness of the Work (or specific parts thereof) for all required inspections and tests, and shall cooperate with inspection and testing personnel to facilitate required inspections and tests.
- B. Owner shall retain and pay for the services of an independent inspector, testing laboratory, or other qualified individual or entity to perform all inspections and tests expressly required by the Contract Documents to be furnished and paid for by Owner, except that costs incurred in connection with tests or inspections of covered Work will be governed by the provisions of Paragraph 14.05.
- C. If Laws or Regulations of any public body having jurisdiction require any Work (or part thereof) specifically to be inspected, tested, or approved by an employee or other representative of such public body, Contractor shall assume full responsibility for arranging and obtaining such inspections, tests, or approvals, pay all costs in connection therewith, and furnish Engineer the required certificates of inspection or approval.

- D. Contractor shall be responsible for arranging, obtaining, and paying for all inspections and tests required:
1. by the Contract Documents, unless the Contract Documents expressly allocate responsibility for a specific inspection or test to Owner;
 2. to attain Owner's and Engineer's acceptance of materials or equipment to be incorporated in the Work;
 3. by manufacturers of equipment furnished under the Contract Documents;
 4. for testing, adjusting, and balancing of mechanical, electrical, and other equipment to be incorporated into the Work; and
 5. for acceptance of materials, mix designs, or equipment submitted for approval prior to Contractor's purchase thereof for incorporation in the Work.

Such inspections and tests will be performed by independent inspectors, testing laboratories, or other qualified individuals or entities acceptable to Owner and Engineer.

- E. If the Contract Documents require the Work (or part thereof) to be approved by Owner, Engineer, or another designated individual or entity, then Contractor shall assume full responsibility for arranging and obtaining such approvals.
- F. If any Work (or the work of others) that is to be inspected, tested, or approved is covered by Contractor without written concurrence of Engineer, Contractor shall, if requested by Engineer, uncover such Work for observation. Such uncovering will be at Contractor's expense unless Contractor had given Engineer timely notice of Contractor's intention to cover the same and Engineer had not acted with reasonable promptness in response to such notice.

14.03 *Defective Work*

- A. *Contractor's Obligation:* It is Contractor's obligation to assure that the Work is not defective.
- B. *Engineer's Authority:* Engineer has the authority to determine whether Work is defective, and to reject defective Work.
- C. *Notice of Defects:* Prompt written notice of all defective Work of which Owner or Engineer has actual knowledge will be given to Contractor.
- D. *Correction, or Removal and Replacement:* Promptly after receipt of written notice of defective Work, Contractor shall correct all such defective Work, whether or not fabricated, installed, or completed, or, if Engineer has rejected the defective Work, remove it from the Project and replace it with Work that is not defective.
- E. *Preservation of Warranties:* When correcting defective Work, Contractor shall take no action that would void or otherwise impair Owner's special warranty and guarantee, if any, on said Work.
- F. *Costs and Damages:* In addition to its correction, removal, and replacement obligations with respect to defective Work, Contractor shall pay all claims, costs, losses, and damages arising out of or relating to defective Work, including but not limited to the cost of the inspection, testing, correction, removal, replacement, or reconstruction of such defective Work, fines levied against Owner by governmental authorities because the Work is defective, and the costs of repair or replacement of work of others resulting from defective Work. Prior to final payment, if Owner and Contractor are unable to agree as to the measure of such claims, costs,

losses, and damages resulting from defective Work, then Owner may impose a reasonable set-off against payments due under Article 15.

14.04 *Acceptance of Defective Work*

- A. If, instead of requiring correction or removal and replacement of defective Work, Owner prefers to accept it, Owner may do so (subject, if such acceptance occurs prior to final payment, to Engineer's confirmation that such acceptance is in general accord with the design intent and applicable engineering principles, and will not endanger public safety). Contractor shall pay all claims, costs, losses, and damages attributable to Owner's evaluation of and determination to accept such defective Work (such costs to be approved by Engineer as to reasonableness), and for the diminished value of the Work to the extent not otherwise paid by Contractor. If any such acceptance occurs prior to final payment, the necessary revisions in the Contract Documents with respect to the Work will be incorporated in a Change Order. If the parties are unable to agree as to the decrease in the Contract Price, reflecting the diminished value of Work so accepted, then Owner may impose a reasonable set-off against payments due under Article 15. If the acceptance of defective Work occurs after final payment, Contractor shall pay an appropriate amount to Owner.

14.05 *Uncovering Work*

- A. Engineer has the authority to require additional inspection or testing of the Work, whether or not the Work is fabricated, installed, or completed.
- B. If any Work is covered contrary to the written request of Engineer, then Contractor shall, if requested by Engineer, uncover such Work for Engineer's observation, and then replace the covering, all at Contractor's expense.
- C. If Engineer considers it necessary or advisable that covered Work be observed by Engineer or inspected or tested by others, then Contractor, at Engineer's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as Engineer may require, that portion of the Work in question, and provide all necessary labor, material, and equipment.
 - 1. If it is found that the uncovered Work is defective, Contractor shall be responsible for all claims, costs, losses, and damages arising out of or relating to such uncovering, exposure, observation, inspection, and testing, and of satisfactory replacement or reconstruction (including but not limited to all costs of repair or replacement of work of others); and pending Contractor's full discharge of this responsibility the Owner shall be entitled to impose a reasonable set-off against payments due under Article 15.
 - 2. If the uncovered Work is not found to be defective, Contractor shall be allowed an increase in the Contract Price or an extension of the Contract Times, directly attributable to such uncovering, exposure, observation, inspection, testing, replacement, and reconstruction. If the parties are unable to agree as to the amount or extent thereof, then Contractor may submit a Change Proposal within 30 days of the determination that the Work is not defective.

14.06 *Owner May Stop the Work*

- A. If the Work is defective, or Contractor fails to supply sufficient skilled workers or suitable materials or equipment, or fails to perform the Work in such a way that the completed Work will conform to the Contract Documents, then Owner may order Contractor to stop the Work,

or any portion thereof, until the cause for such order has been eliminated; however, this right of Owner to stop the Work will not give rise to any duty on the part of Owner to exercise this right for the benefit of Contractor, any Subcontractor, any Supplier, any other individual or entity, or any surety for, or employee or agent of any of them.

14.07 Owner May Correct Defective Work

- A. If Contractor fails within a reasonable time after written notice from Engineer to correct defective Work, or to remove and replace defective Work as required by Engineer, then Owner may, after 7 days' written notice to Contractor, correct or remedy any such deficiency.
- B. In exercising the rights and remedies under this Paragraph 14.07, Owner shall proceed expeditiously. In connection with such corrective or remedial action, Owner may exclude Contractor from all or part of the Site, take possession of all or part of the Work and suspend Contractor's services related thereto, and incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere. Contractor shall allow Owner, Owner's representatives, agents and employees, Owner's other contractors, and Engineer and Engineer's consultants access to the Site to enable Owner to exercise the rights and remedies under this paragraph.
- C. All claims, costs, losses, and damages incurred or sustained by Owner in exercising the rights and remedies under this Paragraph 14.07 will be charged against Contractor as set-offs against payments due under Article 15. Such claims, costs, losses and damages will include but not be limited to all costs of repair, or replacement of work of others destroyed or damaged by correction, removal, or replacement of Contractor's defective Work.
- D. Contractor shall not be allowed an extension of the Contract Times because of any delay in the performance of the Work attributable to the exercise by Owner of Owner's rights and remedies under this Paragraph 14.07.

ARTICLE 15—PAYMENTS TO CONTRACTOR; SET-OFFS; COMPLETION; CORRECTION PERIOD

15.01 Progress Payments

- A. *Basis for Progress Payments:* The Schedule of Values established as provided in Article 2 will serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to Engineer. Progress payments for Unit Price Work will be based on the number of units completed during the pay period, as determined under the provisions of Paragraph 13.03. Progress payments for cost-based Work will be based on Cost of the Work completed by Contractor during the pay period.
- B. *Applications for Payments*
 - 1. At least 20 days before the date established in the Agreement for each progress payment (but not more often than once a month), Contractor shall submit to Engineer for review an Application for Payment filled out and signed by Contractor covering the Work completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents.
 - 2. If payment is requested on the basis of materials and equipment not incorporated in the Work but delivered and suitably stored at the Site or at another location agreed to in writing, the Application for Payment must also be accompanied by: (a) a bill of sale, invoice, copies of subcontract or purchase order payments, or other documentation

establishing full payment by Contractor for the materials and equipment; (b) at Owner's request, documentation warranting that Owner has received the materials and equipment free and clear of all Liens; and (c) evidence that the materials and equipment are covered by appropriate property insurance, a warehouse bond, or other arrangements to protect Owner's interest therein, all of which must be satisfactory to Owner.

3. Beginning with the second Application for Payment, each Application must include an affidavit of Contractor stating that all previous progress payments received by Contractor have been applied to discharge Contractor's legitimate obligations associated with prior Applications for Payment.
4. The amount of retainage with respect to progress payments will be as stipulated in the Agreement.

C. Review of Applications

1. Engineer will, within 10 days after receipt of each Application for Payment, including each resubmittal, either indicate in writing a recommendation of payment and present the Application to Owner, or return the Application to Contractor indicating in writing Engineer's reasons for refusing to recommend payment. In the latter case, Contractor may make the necessary corrections and resubmit the Application.
2. Engineer's recommendation of any payment requested in an Application for Payment will constitute a representation by Engineer to Owner, based on Engineer's observations of the executed Work as an experienced and qualified design professional, and on Engineer's review of the Application for Payment and the accompanying data and schedules, that to the best of Engineer's knowledge, information and belief:
 - a. the Work has progressed to the point indicated;
 - b. the quality of the Work is generally in accordance with the Contract Documents (subject to an evaluation of the Work as a functioning whole prior to or upon Substantial Completion, the results of any subsequent tests called for in the Contract Documents, a final determination of quantities and classifications for Unit Price Work under Paragraph 13.03, and any other qualifications stated in the recommendation); and
 - c. the conditions precedent to Contractor's being entitled to such payment appear to have been fulfilled in so far as it is Engineer's responsibility to observe the Work.
3. By recommending any such payment Engineer will not thereby be deemed to have represented that:
 - a. inspections made to check the quality or the quantity of the Work as it has been performed have been exhaustive, extended to every aspect of the Work in progress, or involved detailed inspections of the Work beyond the responsibilities specifically assigned to Engineer in the Contract; or
 - b. there may not be other matters or issues between the parties that might entitle Contractor to be paid additionally by Owner or entitle Owner to withhold payment to Contractor.

4. Neither Engineer's review of Contractor's Work for the purposes of recommending payments nor Engineer's recommendation of any payment, including final payment, will impose responsibility on Engineer:
 - a. to supervise, direct, or control the Work;
 - b. for the means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto;
 - c. for Contractor's failure to comply with Laws and Regulations applicable to Contractor's performance of the Work;
 - d. to make any examination to ascertain how or for what purposes Contractor has used the money paid by Owner; or
 - e. to determine that title to any of the Work, materials, or equipment has passed to Owner free and clear of any Liens.
5. Engineer may refuse to recommend the whole or any part of any payment if, in Engineer's opinion, it would be incorrect to make the representations to Owner stated in Paragraph 15.01.C.2.
6. Engineer will recommend reductions in payment (set-offs) necessary in Engineer's opinion to protect Owner from loss because:
 - a. the Work is defective, requiring correction or replacement;
 - b. the Contract Price has been reduced by Change Orders;
 - c. Owner has been required to correct defective Work in accordance with Paragraph 14.07, or has accepted defective Work pursuant to Paragraph 14.04;
 - d. Owner has been required to remove or remediate a Hazardous Environmental Condition for which Contractor is responsible; or
 - e. Engineer has actual knowledge of the occurrence of any of the events that would constitute a default by Contractor and therefore justify termination for cause under the Contract Documents.

D. *Payment Becomes Due*

1. Ten days after presentation of the Application for Payment to Owner with Engineer's recommendation, the amount recommended (subject to any Owner set-offs) will become due, and when due will be paid by Owner to Contractor.

E. *Reductions in Payment by Owner*

1. In addition to any reductions in payment (set-offs) recommended by Engineer, Owner is entitled to impose a set-off against payment based on any of the following:
 - a. Claims have been made against Owner based on Contractor's conduct in the performance or furnishing of the Work, or Owner has incurred costs, losses, or damages resulting from Contractor's conduct in the performance or furnishing of the Work, including but not limited to claims, costs, losses, or damages from workplace injuries, adjacent property damage, non-compliance with Laws and Regulations, and patent infringement;

- b. Contractor has failed to take reasonable and customary measures to avoid damage, delay, disruption, and interference with other work at or adjacent to the Site;
 - c. Contractor has failed to provide and maintain required bonds or insurance;
 - d. Owner has been required to remove or remediate a Hazardous Environmental Condition for which Contractor is responsible;
 - e. Owner has incurred extra charges or engineering costs related to submittal reviews, evaluations of proposed substitutes, tests and inspections, or return visits to manufacturing or assembly facilities;
 - f. The Work is defective, requiring correction or replacement;
 - g. Owner has been required to correct defective Work in accordance with Paragraph 14.07, or has accepted defective Work pursuant to Paragraph 14.04;
 - h. The Contract Price has been reduced by Change Orders;
 - i. An event has occurred that would constitute a default by Contractor and therefore justify a termination for cause;
 - j. Liquidated or other damages have accrued as a result of Contractor's failure to achieve Milestones, Substantial Completion, or final completion of the Work;
 - k. Liens have been filed in connection with the Work, except where Contractor has delivered a specific bond satisfactory to Owner to secure the satisfaction and discharge of such Liens; or
 - l. Other items entitle Owner to a set-off against the amount recommended.
2. If Owner imposes any set-off against payment, whether based on its own knowledge or on the written recommendations of Engineer, Owner will give Contractor immediate written notice (with a copy to Engineer) stating the reasons for such action and the specific amount of the reduction, and promptly pay Contractor any amount remaining after deduction of the amount so withheld. Owner shall promptly pay Contractor the amount so withheld, or any adjustment thereto agreed to by Owner and Contractor, if Contractor remedies the reasons for such action. The reduction imposed will be binding on Contractor unless it duly submits a Change Proposal contesting the reduction.
 3. Upon a subsequent determination that Owner's refusal of payment was not justified, the amount wrongfully withheld will be treated as an amount due as determined by Paragraph 15.01.D.1 and subject to interest as provided in the Agreement.

15.02 *Contractor's Warranty of Title*

- A. Contractor warrants and guarantees that title to all Work, materials, and equipment furnished under the Contract will pass to Owner free and clear of (1) all Liens and other title defects, and (2) all patent, licensing, copyright, or royalty obligations, no later than 7 days after the time of payment by Owner.

15.03 *Substantial Completion*

- A. When Contractor considers the entire Work ready for its intended use Contractor shall notify Owner and Engineer in writing that the entire Work is substantially complete and request that Engineer issue a certificate of Substantial Completion. Contractor shall at the same time

submit to Owner and Engineer an initial draft of punch list items to be completed or corrected before final payment.

- B. Promptly after Contractor's notification, Owner, Contractor, and Engineer shall make an inspection of the Work to determine the status of completion. If Engineer does not consider the Work substantially complete, Engineer will notify Contractor in writing giving the reasons therefor.
- C. If Engineer considers the Work substantially complete, Engineer will deliver to Owner a preliminary certificate of Substantial Completion which will fix the date of Substantial Completion. Engineer shall attach to the certificate a punch list of items to be completed or corrected before final payment. Owner shall have 7 days after receipt of the preliminary certificate during which to make written objection to Engineer as to any provisions of the certificate or attached punch list. If, after considering the objections to the provisions of the preliminary certificate, Engineer concludes that the Work is not substantially complete, Engineer will, within 14 days after submission of the preliminary certificate to Owner, notify Contractor in writing that the Work is not substantially complete, stating the reasons therefor. If Owner does not object to the provisions of the certificate, or if despite consideration of Owner's objections Engineer concludes that the Work is substantially complete, then Engineer will, within said 14 days, execute and deliver to Owner and Contractor a final certificate of Substantial Completion (with a revised punch list of items to be completed or corrected) reflecting such changes from the preliminary certificate as Engineer believes justified after consideration of any objections from Owner.
- D. At the time of receipt of the preliminary certificate of Substantial Completion, Owner and Contractor will confer regarding Owner's use or occupancy of the Work following Substantial Completion, review the builder's risk insurance policy with respect to the end of the builder's risk coverage, and confirm the transition to coverage of the Work under a permanent property insurance policy held by Owner. Unless Owner and Contractor agree otherwise in writing, Owner shall bear responsibility for security, operation, protection of the Work, property insurance, maintenance, heat, and utilities upon Owner's use or occupancy of the Work.
- E. After Substantial Completion the Contractor shall promptly begin work on the punch list of items to be completed or corrected prior to final payment. In appropriate cases Contractor may submit monthly Applications for Payment for completed punch list items, following the progress payment procedures set forth above.
- F. Owner shall have the right to exclude Contractor from the Site after the date of Substantial Completion subject to allowing Contractor reasonable access to remove its property and complete or correct items on the punch list.

15.04 *Partial Use or Occupancy*

- A. Prior to Substantial Completion of all the Work, Owner may use or occupy any substantially completed part of the Work which has specifically been identified in the Contract Documents, or which Owner, Engineer, and Contractor agree constitutes a separately functioning and usable part of the Work that can be used by Owner for its intended purpose without

significant interference with Contractor's performance of the remainder of the Work, subject to the following conditions:

1. At any time, Owner may request in writing that Contractor permit Owner to use or occupy any such part of the Work that Owner believes to be substantially complete. If and when Contractor agrees that such part of the Work is substantially complete, Contractor, Owner, and Engineer will follow the procedures of Paragraph 15.03.A through 15.03.E for that part of the Work.
2. At any time, Contractor may notify Owner and Engineer in writing that Contractor considers any such part of the Work substantially complete and request Engineer to issue a certificate of Substantial Completion for that part of the Work.
3. Within a reasonable time after either such request, Owner, Contractor, and Engineer shall make an inspection of that part of the Work to determine its status of completion. If Engineer does not consider that part of the Work to be substantially complete, Engineer will notify Owner and Contractor in writing giving the reasons therefor. If Engineer considers that part of the Work to be substantially complete, the provisions of Paragraph 15.03 will apply with respect to certification of Substantial Completion of that part of the Work and the division of responsibility in respect thereof and access thereto.
4. No use or occupancy or separate operation of part of the Work may occur prior to compliance with the requirements of Paragraph 6.04 regarding builder's risk or other property insurance.

15.05 *Final Inspection*

- A. Upon written notice from Contractor that the entire Work or an agreed portion thereof is complete, Engineer will promptly make a final inspection with Owner and Contractor and will notify Contractor in writing of all particulars in which this inspection reveals that the Work, or agreed portion thereof, is incomplete or defective. Contractor shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies.

15.06 *Final Payment*

A. *Application for Payment*

1. After Contractor has, in the opinion of Engineer, satisfactorily completed all corrections identified during the final inspection and has delivered, in accordance with the Contract Documents, all maintenance and operating instructions, schedules, guarantees, bonds, certificates or other evidence of insurance, certificates of inspection, annotated record documents (as provided in Paragraph 7.12), and other documents, Contractor may make application for final payment.
2. The final Application for Payment must be accompanied (except as previously delivered) by:
 - a. all documentation called for in the Contract Documents;
 - b. consent of the surety, if any, to final payment;
 - c. satisfactory evidence that all title issues have been resolved such that title to all Work, materials, and equipment has passed to Owner free and clear of any Liens or other title defects, or will so pass upon final payment.

- d. a list of all duly pending Change Proposals and Claims; and
 - e. complete and legally effective releases or waivers (satisfactory to Owner) of all Lien rights arising out of the Work, and of Liens filed in connection with the Work.
- 3. In lieu of the releases or waivers of Liens specified in Paragraph 15.06.A.2 and as approved by Owner, Contractor may furnish receipts or releases in full and an affidavit of Contractor that: (a) the releases and receipts include all labor, services, material, and equipment for which a Lien could be filed; and (b) all payrolls, material and equipment bills, and other indebtedness connected with the Work for which Owner might in any way be responsible, or which might in any way result in liens or other burdens on Owner's property, have been paid or otherwise satisfied. If any Subcontractor or Supplier fails to furnish such a release or receipt in full, Contractor may furnish a bond or other collateral satisfactory to Owner to indemnify Owner against any Lien, or Owner at its option may issue joint checks payable to Contractor and specified Subcontractors and Suppliers.
- B. *Engineer's Review of Final Application and Recommendation of Payment:* If, on the basis of Engineer's observation of the Work during construction and final inspection, and Engineer's review of the final Application for Payment and accompanying documentation as required by the Contract Documents, Engineer is satisfied that the Work has been completed and Contractor's other obligations under the Contract have been fulfilled, Engineer will, within 10 days after receipt of the final Application for Payment, indicate in writing Engineer's recommendation of final payment and present the final Application for Payment to Owner for payment. Such recommendation will account for any set-offs against payment that are necessary in Engineer's opinion to protect Owner from loss for the reasons stated above with respect to progress payments. Otherwise, Engineer will return the Application for Payment to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application for Payment.
- C. *Notice of Acceptability:* In support of its recommendation of payment of the final Application for Payment, Engineer will also give written notice to Owner and Contractor that the Work is acceptable, subject to stated limitations in the notice and to the provisions of Paragraph 15.07.
- D. *Completion of Work:* The Work is complete (subject to surviving obligations) when it is ready for final payment as established by the Engineer's written recommendation of final payment and issuance of notice of the acceptability of the Work.
- E. *Final Payment Becomes Due:* Upon receipt from Engineer of the final Application for Payment and accompanying documentation, Owner shall set off against the amount recommended by Engineer for final payment any further sum to which Owner is entitled, including but not limited to set-offs for liquidated damages and set-offs allowed under the provisions of this Contract with respect to progress payments. Owner shall pay the resulting balance due to Contractor within 30 days of Owner's receipt of the final Application for Payment from Engineer.

15.07 *Waiver of Claims*

- A. By making final payment, Owner waives its claim or right to liquidated damages or other damages for late completion by Contractor, except as set forth in an outstanding Claim,

appeal under the provisions of Article 17, set-off, or express reservation of rights by Owner. Owner reserves all other claims or rights after final payment.

- B. The acceptance of final payment by Contractor will constitute a waiver by Contractor of all claims and rights against Owner other than those pending matters that have been duly submitted as a Claim, or appealed under the provisions of Article 17.

15.08 *Correction Period*

- A. If within one year after the date of Substantial Completion (or such longer period of time as may be prescribed by the Supplementary Conditions or the terms of any applicable special guarantee required by the Contract Documents), Owner gives Contractor written notice that any Work has been found to be defective, or that Contractor's repair of any damages to the Site or adjacent areas has been found to be defective, then after receipt of such notice of defect Contractor shall promptly, without cost to Owner and in accordance with Owner's written instructions:
 - 1. correct the defective repairs to the Site or such adjacent areas;
 - 2. correct such defective Work;
 - 3. remove the defective Work from the Project and replace it with Work that is not defective, if the defective Work has been rejected by Owner, and
 - 4. satisfactorily correct or repair or remove and replace any damage to other Work, to the work of others, or to other land or areas resulting from the corrective measures.
- B. Owner shall give any such notice of defect within 60 days of the discovery that such Work or repairs is defective. If such notice is given within such 60 days but after the end of the correction period, the notice will be deemed a notice of defective Work under Paragraph 7.17.B.
- C. If, after receipt of a notice of defect within 60 days and within the correction period, Contractor does not promptly comply with the terms of Owner's written instructions, or in an emergency where delay would cause serious risk of loss or damage, Owner may have the defective Work corrected or repaired or may have the rejected Work removed and replaced. Contractor shall pay all costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or repair or such removal and replacement (including but not limited to all costs of repair or replacement of work of others). Contractor's failure to pay such costs, losses, and damages within 10 days of invoice from Owner will be deemed the start of an event giving rise to a Claim under Paragraph 12.01.B, such that any related Claim must be brought within 30 days of the failure to pay.
- D. In special circumstances where a particular item of equipment is placed in continuous service before Substantial Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications.
- E. Where defective Work (and damage to other Work resulting therefrom) has been corrected or removed and replaced under this paragraph, the correction period hereunder with respect to such Work will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.

- F. Contractor's obligations under this paragraph are in addition to all other obligations and warranties. The provisions of this paragraph are not to be construed as a substitute for, or a waiver of, the provisions of any applicable statute of limitation or repose.

ARTICLE 16—SUSPENSION OF WORK AND TERMINATION

16.01 *Owner May Suspend Work*

- A. At any time and without cause, Owner may suspend the Work or any portion thereof for a period of not more than 90 consecutive days by written notice to Contractor and Engineer. Such notice will fix the date on which Work will be resumed. Contractor shall resume the Work on the date so fixed. Contractor shall be entitled to an adjustment in the Contract Price or an extension of the Contract Times directly attributable to any such suspension. Any Change Proposal seeking such adjustments must be submitted no later than 30 days after the date fixed for resumption of Work.

16.02 *Owner May Terminate for Cause*

- A. The occurrence of any one or more of the following events will constitute a default by Contractor and justify termination for cause:
 - 1. Contractor's persistent failure to perform the Work in accordance with the Contract Documents (including, but not limited to, failure to supply sufficient skilled workers or suitable materials or equipment, or failure to adhere to the Progress Schedule);
 - 2. Failure of Contractor to perform or otherwise to comply with a material term of the Contract Documents;
 - 3. Contractor's disregard of Laws or Regulations of any public body having jurisdiction; or
 - 4. Contractor's repeated disregard of the authority of Owner or Engineer.
- B. If one or more of the events identified in Paragraph 16.02.A occurs, then after giving Contractor (and any surety) 10 days' written notice that Owner is considering a declaration that Contractor is in default and termination of the Contract, Owner may proceed to:
 - 1. declare Contractor to be in default, and give Contractor (and any surety) written notice that the Contract is terminated; and
 - 2. enforce the rights available to Owner under any applicable performance bond.
- C. Subject to the terms and operation of any applicable performance bond, if Owner has terminated the Contract for cause, Owner may exclude Contractor from the Site, take possession of the Work, incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere, and complete the Work as Owner may deem expedient.
- D. Owner may not proceed with termination of the Contract under Paragraph 16.02.B if Contractor within 7 days of receipt of notice of intent to terminate begins to correct its failure to perform and proceeds diligently to cure such failure.
- E. If Owner proceeds as provided in Paragraph 16.02.B, Contractor shall not be entitled to receive any further payment until the Work is completed. If the unpaid balance of the Contract Price exceeds the cost to complete the Work, including all related claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects,

- attorneys, and other professionals) sustained by Owner, such excess will be paid to Contractor. If the cost to complete the Work including such related claims, costs, losses, and damages exceeds such unpaid balance, Contractor shall pay the difference to Owner. Such claims, costs, losses, and damages incurred by Owner will be reviewed by Engineer as to their reasonableness and, when so approved by Engineer, incorporated in a Change Order. When exercising any rights or remedies under this paragraph, Owner shall not be required to obtain the lowest price for the Work performed.
- F. Where Contractor's services have been so terminated by Owner, the termination will not affect any rights or remedies of Owner against Contractor then existing or which may thereafter accrue, or any rights or remedies of Owner against Contractor or any surety under any payment bond or performance bond. Any retention or payment of money due Contractor by Owner will not release Contractor from liability.
 - G. If and to the extent that Contractor has provided a performance bond under the provisions of Paragraph 6.01.A, the provisions of that bond will govern over any inconsistent provisions of Paragraphs 16.02.B and 16.02.D.

16.03 *Owner May Terminate for Convenience*

- A. Upon 7 days' written notice to Contractor and Engineer, Owner may, without cause and without prejudice to any other right or remedy of Owner, terminate the Contract. In such case, Contractor shall be paid for (without duplication of any items):
 - 1. completed and acceptable Work executed in accordance with the Contract Documents prior to the effective date of termination, including fair and reasonable sums for overhead and profit on such Work;
 - 2. expenses sustained prior to the effective date of termination in performing services and furnishing labor, materials, or equipment as required by the Contract Documents in connection with uncompleted Work, plus fair and reasonable sums for overhead and profit on such expenses; and
 - 3. other reasonable expenses directly attributable to termination, including costs incurred to prepare a termination for convenience cost proposal.
- B. Contractor shall not be paid for any loss of anticipated profits or revenue, post-termination overhead costs, or other economic loss arising out of or resulting from such termination.

16.04 *Contractor May Stop Work or Terminate*

- A. If, through no act or fault of Contractor, (1) the Work is suspended for more than 90 consecutive days by Owner or under an order of court or other public authority, or (2) Engineer fails to act on any Application for Payment within 30 days after it is submitted, or (3) Owner fails for 30 days to pay Contractor any sum finally determined to be due, then Contractor may, upon 7 days' written notice to Owner and Engineer, and provided Owner or Engineer do not remedy such suspension or failure within that time, terminate the contract and recover from Owner payment on the same terms as provided in Paragraph 16.03.
- B. In lieu of terminating the Contract and without prejudice to any other right or remedy, if Engineer has failed to act on an Application for Payment within 30 days after it is submitted, or Owner has failed for 30 days to pay Contractor any sum finally determined to be due, Contractor may, 7 days after written notice to Owner and Engineer, stop the Work until payment is made of all such amounts due Contractor, including interest thereon. The

provisions of this paragraph are not intended to preclude Contractor from submitting a Change Proposal for an adjustment in Contract Price or Contract Times or otherwise for expenses or damage directly attributable to Contractor's stopping the Work as permitted by this paragraph.

ARTICLE 17—FINAL RESOLUTION OF DISPUTES

17.01 *Methods and Procedures*

- A. *Disputes Subject to Final Resolution:* The following disputed matters are subject to final resolution under the provisions of this article:
 - 1. A timely appeal of an approval in part and denial in part of a Claim, or of a denial in full, pursuant to Article 12; and
 - 2. Disputes between Owner and Contractor concerning the Work, or obligations under the Contract Documents, that arise after final payment has been made.
- B. *Final Resolution of Disputes:* For any dispute subject to resolution under this article, Owner or Contractor may:
 - 1. elect in writing to invoke the dispute resolution process provided for in the Supplementary Conditions;
 - 2. agree with the other party to submit the dispute to another dispute resolution process; or
 - 3. if no dispute resolution process is provided for in the Supplementary Conditions or mutually agreed to, give written notice to the other party of the intent to submit the dispute to a court of competent jurisdiction.

ARTICLE 18—MISCELLANEOUS

18.01 *Giving Notice*

- A. Whenever any provision of the Contract requires the giving of written notice to Owner, Engineer, or Contractor, it will be deemed to have been validly given only if delivered:
 - 1. in person, by a commercial courier service or otherwise, to the recipient's place of business;
 - 2. by registered or certified mail, postage prepaid, to the recipient's place of business; or
 - 3. by e-mail to the recipient, with the words "Formal Notice" or similar in the e-mail's subject line.

18.02 *Computation of Times*

- A. When any period of time is referred to in the Contract by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or on a day made a legal holiday by the law of the applicable jurisdiction, such day will be omitted from the computation.

18.03 *Cumulative Remedies*

- A. The duties and obligations imposed by these General Conditions and the rights and remedies available hereunder to the parties hereto are in addition to, and are not to be construed in any way as a limitation of, any rights and remedies available to any or all of them which are otherwise imposed or available by Laws or Regulations, by special warranty or guarantee, or by other provisions of the Contract. The provisions of this paragraph will be as effective as if repeated specifically in the Contract Documents in connection with each particular duty, obligation, right, and remedy to which they apply.

18.04 *Limitation of Damages*

- A. With respect to any and all Change Proposals, Claims, disputes subject to final resolution, and other matters at issue, neither Owner nor Engineer, nor any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, shall be liable to Contractor for any claims, costs, losses, or damages sustained by Contractor on or in connection with any other project or anticipated project.

18.05 *No Waiver*

- A. A party's non-enforcement of any provision will not constitute a waiver of that provision, nor will it affect the enforceability of that provision or of the remainder of this Contract.

18.06 *Survival of Obligations*

- A. All representations, indemnifications, warranties, and guarantees made in, required by, or given in accordance with the Contract, as well as all continuing obligations indicated in the Contract, will survive final payment, completion, and acceptance of the Work or termination of the Contract or of the services of Contractor.

18.07 *Controlling Law*

- A. This Contract is to be governed by the law of the state in which the Project is located.

18.08 *Assignment of Contract*

- A. Unless expressly agreed to elsewhere in the Contract, no assignment by a party to this Contract of any rights under or interests in the Contract will be binding on the other party without the written consent of the party sought to be bound; and, specifically but without limitation, money that may become due and money that is due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract.

18.09 *Successors and Assigns*

- A. Owner and Contractor each binds itself, its successors, assigns, and legal representatives to the other party hereto, its successors, assigns, and legal representatives in respect to all covenants, agreements, and obligations contained in the Contract Documents.

18.10 *Headings*

- A. Article and paragraph headings are inserted for convenience only and do not constitute parts of these General Conditions.

SUPPLEMENTARY CONDITIONS OF THE CONSTRUCTION CONTRACT

TABLE OF CONTENTS

	Page
Article 1 - Definitions and Terminology	2
Article 2 - Preliminary Matters	3
Article 3 - Contract Documents: Intent, Requirements , Reuse.....	4
Article 4 - Commencement and Progress of the Work.....	4
Article 5 - Site; Subsurface and Physical Conditions; Hazardous Environmental Conditions	5
Article 6 - Bonds and Insurance	8
Article 7 - Contractor's Responsibilities	21
Article 8 - Other Work at the Site.....	27
Article 9 - Owner's Responsibilities	28
Article 10 - Engineer's Status During Construction	29
Article 11 - Changes to the Contract	32
Article 12 - Claims	32
Article 13 - Cost of the Work; Allowances; Unit Price Work	32
Article 14 - Tests and Inspections; Correction, Removal, or Acceptance of Defective Work	34
Article 15 - Payments to Contractor; Set-offs; Completion; Correction Period	35
Article 16 - Suspension of Work and Termination.....	38
Article 17 - Final Resolution of Disputes.....	38
Article 18 - Miscellaneous	39

SUPPLEMENTARY CONDITIONS OF THE CONSTRUCTION CONTRACT

These Supplementary Conditions amend or supplement EJCDC® C-700, Standard General Conditions of the Construction Contract (2018). The General Conditions remain in full force and effect except as amended.

The terms used in these Supplementary Conditions have the meanings stated in the General Conditions. Additional terms used in these Supplementary Conditions have the meanings stated below, which are applicable to both the singular and plural thereof.

The address system used in these Supplementary Conditions is the same as the address system used in the General Conditions, with the prefix “SC” added—for example, “Paragraph SC-4.05.”

ARTICLE 1 - DEFINITIONS AND TERMINOLOGY

1.01 *Defined Terms*

SC-1.01.A.3. Add the following language to the end of Paragraph 1.01.A.3:

The Application for Payment form to be used on this Project is per City of Raleigh standards. Standard form to be used as a summary and signature sheet is included in Section 00620. Contractor shall use the City’s standard computerized forms, as included in these Contract Documents, for providing detail payment breakdown as an attachment to summary sheet. Contractor shall also include as part of the Application for Payment the “Certificate of the Contractor or His Duly Authorized Representative”.

SC-1.01.A.8. Add the following language to the end of Paragraph 1.01.A.8:

The Change Order form to be used on this Project is the City of Raleigh standard. The Standard Form to be used is included in these Contract Documents.

SC-1.01.A.9. Add the following language to the end of Paragraph 1.01.A.9:

The Change Proposal form to be used on this Project is the City of Raleigh standard. The Standard Form to be used is included in these Contract Documents.

SC-1.01.A.42. Amend the first sentence of Paragraph 1.01.A.42 to read as follows:

The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of Engineer and Owner, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended.

SC-1.01.A.51. Add the following definitions after Paragraph 1.01.A.50:

A.51 *City* – City of Raleigh.

A.52 *Minority Business* - A business:

- a. In which at least fifty-one percent (51%) is owned by one or more minority persons or socially and economically disadvantaged individuals, or in the case of a corporation,

in which at least fifty-one percent (51%) of the stock is owned by one or more minority persons or socially and economically disadvantaged individuals; and

- b. Of which the management and daily business operations are controlled by one or more of the minority persons or socially and economically disadvantaged individuals who own it.

A.53 *Minority Person* - A person who is a citizen or lawful permanent resident of the United States and who is:

- a. Black, that is, a person having origins in any of the black racial groups in Africa;
- b. Hispanic, that is, a person of Spanish or Portuguese culture with origins in Mexico, South or Central America, or the Caribbean Islands, regardless of race;
- c. Asian American, that is, a person having origins in any of the original peoples of the Far East, Southeast Asia and Asia, the Indian subcontinent, or the Pacific Islands;
- d. American Indian, that is, a person having origins in any of the original Indian peoples of North America; or
- e. Female.

A.54 *Notice of Violation* - A written notification from a governmental agency that the Owner has violated a law or regulation that the agency has jurisdiction over. Notice will take the form used by the agency and may outline action to be taken by the Owner to correct the violation and may include a monetary fine.

A.55 *Small Tools* - Tools and equipment with an individual cost of less than \$1,000.

A.56 *Socially and Economically Disadvantaged Individual* - Same as defined in 15 U.S.C. 637; "Socially disadvantaged individuals are those who have been subjected to racial or ethnic prejudice or cultural bias because of their identity as a member of a group without regard to their individual qualities". "Economically disadvantaged individuals are those socially disadvantaged individuals whose ability to compete in the free enterprise system has been impaired due to diminished capital and credit opportunities as compared to others in the same business area who are not socially disadvantaged."

ARTICLE 2 - PRELIMINARY MATTERS

2.01 Delivery of Performance and Payment Bonds; Evidence of Insurance

SC-2.01.A Amend the first sentence of Paragraph 2.01.A by striking out the following words:

"(if the Contract requires Contractor to furnish such bonds)."

2.02 *Copies of Documents*

SC-2.02.A Delete the word "four" and insert "five" in its place in Paragraph 2.02.A.

ARTICLE 3 - CONTRACT DOCUMENTS: INTENT, REQUIREMENTS , REUSE

3.01 *Intent*

SC-3.01 Add the following new paragraphs immediately after Paragraph 3.01.G:

- H. The Contract Drawings may be supplemented from time to time with additional Drawings by the Engineer as may be required to illustrate the Work or, as the Work progresses, with additional Drawings, by the Contractor, subject to the approval of the Engineer. Supplementary Drawings, when issued by the Engineer or by the Contractor, after approval by the Engineer, shall be furnished in sufficient quantity to all those who, in the opinion of the Engineer, are affected by such Drawings.

ARTICLE 4 - COMMENCEMENT AND PROGRESS OF THE WORK

4.01 *Commencement of Contract Times; Notice to Proceed*

SC-4.01.A Delete Paragraph 4.01.A in its entirety and insert the following in its place:

The Contract Times will commence to run on the day indicated in the Notice to Proceed; but in no event will the Contract Time commence to run later than the thirtieth day after the effective date of the Agreement. By mutual consent of the parties to the Contract, these time limits may be changed.

4.05 *Delays in Contractor's Progress*

SC-4.05.C Amend Paragraph 4.05.C by adding the following subparagraphs:

5. *Weather-Related Delays*

- a. If "abnormal weather conditions" as set forth in Paragraph 4.05.C.2 of the General Conditions are the basis for a request for an equitable adjustment in the Contract Times, such request must be documented by data substantiating each of the following: 1) that weather conditions were abnormal for the period of time in which the delay occurred, 2) that such weather conditions could not have been reasonably anticipated, and 3) that such weather conditions adversely affected an activity on the critical path to completion of the Work, as of the time of the weather condition.
- b. The existence of abnormal weather conditions will be determined on a month-by-month basis in accordance with the following.
 - 1) Bad Weather Day: a workday where weather conditions adversely affect the Work and the impacted Work is on the critical path.
 - a) Determination of actual Bad Weather Days during performance of the Work will be based on weather at the Site. When Site weather data is not available, use nearest USGS weather station data.

- b) A workday after a daily rainfall amount greater than 1 inch will be considered an additional Bad Weather Day, subject to having an adverse effect on the Work as scheduled.
- 2) Foreseeable Bad Weather Days: determination of Foreseeable Bad Weather Days during performance of the Work will be based on the weather records measured and recorded by the National Oceanic & Atmospheric Administration, National Centers for Environmental Information (NOAA-NCEI) at the nearest weather monitoring station. For example, one source of weather records is from the NOAA-NCEI website: <https://www.ncdc.noaa.gov/cdo-web/datatools/normals>. From the website, click on the "View Station Report" link to find the Summary of Monthly Totals report.
 - a) Contractor shall anticipate and factor into its bid and construction schedule the number of Foreseeable Bad Weather Days per month.
- 3) Abnormal Weather Conditions: is defined as the total Bad Weather Days in each month minus the Foreseeable Bad Weather Days.
 - a) The existence of Abnormal Weather Conditions will not relieve Contractor of the obligation to demonstrate and document that delays caused by Abnormal Weather Conditions are specific to the planned work activities or that such activities thus delayed were on Contractor's then-current Progress Schedule's critical path for the Project.

SC-4.05 Add the following new paragraph immediately after Paragraph 4.05.G:

- H. Claims for additional Contract Time for delays beyond the Contractor's control shall be submitted within 30 days following the event(s) that caused the delay.

ARTICLE 5 - SITE; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS

5.02 Use of Site and Other Areas

SC-5.02.A Delete Paragraph 5.02.A.2 in its entirety and insert the following in its place:

- 2. If a damage or injury claim is made by the owner or occupant of any such land or area because of the performance of the Work, or because of other actions or conduct of the Contractor or its Derivative Parties (as defined in SC-7.18.E.3), Contractor shall (a) take immediate corrective or remedial action as required by Paragraph 7.13, or otherwise and (b) promptly attempt to settle the claim as to all parties through negotiations with such owner or occupant, or otherwise resolve the claim by arbitration or other dispute resolution proceeding, or in a court of competent jurisdiction. In addition, the Contractor's indemnity, defense and hold harmless obligations to the Indemnified Parties (as defined in SC-7.18.A) under SC-7.18 shall apply as to any and all Losses (as defined in SC-7.18.E.2),

liabilities, damages, expenses and costs arising out of, resulting from, or in connection with any and all claims or actions brought by any such owner or occupant against one or more of the Indemnified Parties when the Fault of the Contractor or its Derivative Parties is a proximate cause of the Losses, liabilities, damages, expenses and costs so indemnified. Provided, however, nothing herein shall require the Contractor to indemnify the Indemnified Parties against any Losses, liabilities, damages, expenses and costs arising out of, resulting from, or in connection with any negligent acts of one or more of the Indemnified Parties.

5.03 *Subsurface and Physical Conditions*

SC-5.03 Add the following new paragraphs immediately after Paragraph 5.03.D:

- E. The following table lists the reports of explorations and tests of subsurface conditions at or adjacent to the Site that contain Technical Data, and specifically identifies the Technical Data in the report upon which Contractor may rely:

Report Title	Date of Report	Technical Data
		None

- F. The following table lists the drawings of existing physical conditions at or adjacent to the Site, including those drawings depicting existing surface or subsurface structures at or adjacent to the Site (except Underground Facilities), that contain Technical Data, and specifically identifies the Technical Data in the drawings upon which Contractor may rely:

Drawings Title	Date of Drawings	Technical Data
		None

- G. Contractor may examine copies of reports and drawings identified in SC-5.03.E and SC-5.03.F that were not included with the Bidding Documents at **N/A** during regular business hours or may request copies from Engineer.

5.05 *Underground Facilities*

SC-5.05.A Add the following new subparagraphs immediately after Subparagraph 5.05.A.5:

6. following the North Carolina General Statutes, Chapter 87, Article 8 Underground Damage Prevention;
7. notifying owners of Underground Facilities prior to start of Work;
8. investigating ahead of the Work to verify the existence of Underground Facilities;

9. assuming risks and repairing damage caused by the Work to existing Underground Facilities whether indicated or not in the Contract Documents. Repairs to Underground Facilities shall be done to the satisfaction of the Underground Facility owner. Underground Facility owner reserves the right to repair damage by the Contractor to their Underground Facilities. If the owner exercises this right, the owner's cost of this Work shall be deducted from the money due the Contractor;
10. uncovering Underground Facilities, with that Owners approval, that are located within the Work as necessary for Engineer to determine the requirements for the change in the Work;
11. unforeseen Underground Facilities unless a design change is required; this includes Underground Facilities not shown on the Drawings/ Bidding Documents. The Engineer and the Owner assume no responsibility for the locations of Underground Facilities shown or not shown. There will be no compensation for "lost time" due to unforeseen utilities. If existing Underground Facilities require change(s) to the design, the Contractor shall provide a price to complete revised Work.

5.06 *Hazardous Environmental Conditions at Site*

SC-5.06.A Add the following new subparagraphs immediately after subparagraph 5.06.A.3:

4. The following table lists the reports known to Owner relating to Hazardous Environmental Conditions at or adjacent to the Site, and the Technical Data (if any) contained in such reports upon which Contractor may rely:

Report Title	Date of Report	Technical Data
		None

5. The following table lists the drawings known to Owner relating to Hazardous Environmental Conditions at or adjacent to the Site, and Technical Data (if any) contained in such Drawings upon which Contractor may rely:

Drawings Title	Date of Drawings	Technical Data
		None

SC-5.06.B Delete Paragraph 5.06.B in its entirety and insert the following:

B. Not used.

SC-5.06.I In the first line, insert "North Carolina" between "by" and "Laws".

SC-5.06.I Add the following language at the end of Paragraph 5.06.I:

The parties understand and acknowledge that no North Carolina case, statute, or Constitutional provision authorizes a local government to indemnify a Contractor and that this contract provision may be unenforceable.

SC-5.06.J Delete Paragraph 5.06.J in its entirety and insert the following in its place:

- J. Contractor's indemnity, defense and hold harmless obligations to the Indemnified Parties under SC-7.18 shall apply as to any and all Losses, liabilities, damages, expenses and costs caused by, arising out of, resulting from, or in connection with the Contractor's or its Derivative Parties' failure to control, contain, or remove a Constituent of Concern brought to the Site by Contractor or its Derivative Parties, or to a Hazardous Environmental Condition created by Contractor or its Derivate Parties when the Fault of the Contractor or its Derivative Parties is a proximate cause of the Losses, liabilities, damages, expenses and costs so indemnified. Provided, however, nothing herein shall require the Contractor to indemnify the Indemnified Parties against any such Losses, liabilities, damages, expenses and costs arising out of, resulting from, or in connection with any negligent acts of one or more of the Indemnified Parties.

ARTICLE 6 - BONDS AND INSURANCE

Article 6 Delete Article 6 in its entirety and insert the following in its place:

SC-6.01 *Performance and Payment Bonds*

- A. Concurrent with execution of the Contract and within fifteen (15) days of the Notice of Award, the successful Contractor shall procure, execute and deliver to the Owner and maintain, at Contractor's own cost and expense, the following bonds, in the forms included (Sections 00610 and 00615), of a surety company approved by the State of North Carolina as a Surety:
- B. Performance Bond - in an amount not less than 100% of the total amount payable to the Contractor by the terms of the Contract as security for the faithful performance of the Work. Bond must be valid until one year after the date of issuance of the certificate of Substantial Completion.
- C. Payment Bond - in an amount not less than 100% of the total amount payable to the Contractor by the terms of the Contract as security for the payment of all persons performing labor and furnishing material in connection with the Work. Bond must be valid until one (1) year after date of issuance of the certificate of Substantial Completion.
- D. All bonds signed by an agent must be accompanied by a certified copy of the authority to act.
- E. If the surety on any bond furnished by the Contractor is declared bankrupt or becomes insolvent or its right to do business in the State of North Carolina is revoked, the Contractor shall within five (5) days thereafter substitute another.

SC-6.02 *Insurance Requirements*

- A. The Owner shall not be required under this Contract to procure or maintain any insurance for the Project or for the benefit of the Project participants.
- B. The Contractor shall ensure that it and all its Subcontractors shall procure and maintain insurance as required herein and as required by Laws and Regulations.
- C. All insurance required by the Contract to be purchased and maintained by Contractor shall be obtained from insurance companies that are duly licensed or authorized to do business in the state of North Carolina and to issue insurance policies for the required limits and coverages. Unless a different standard is authorized by the Owner in writing, all companies that provide insurance policies required under this Contract shall have an A.M. Best rating of A-VII or better.
- D. Alternative forms of insurance coverage, including but not limited to self-insurance and "Occupational Accident and Excess Employer's Indemnity Policies," are not sufficient to meet the insurance requirements of this Contract.
- E. Contractor shall deliver to Owner, with copies to each additional insured identified in the Contract, certificates of insurance and endorsements establishing that Contractor has obtained and is maintaining the policies and coverages required by the Contract. Upon request by Owner or any other insured, Contractor shall also furnish other evidence of such required insurance, including but not limited to copies of policies, documentation of applicable self-insured retentions (if allowed) and deductibles, full disclosure of all relevant exclusions, and evidence of insurance required to be purchased and maintained by Subcontractors or Suppliers. In any documentation furnished under this provision, Contractor, Subcontractors, and Suppliers may block out (redact) (1) any confidential premium or pricing information and (2) any wording specific to a project or jurisdiction other than those applicable to this Contract.
- F. Owner, only if specified in this agreement, shall deliver to Contractor, with copies to each additional insured identified in the Contract, certificates of insurance that Owner has obtained and is maintaining the policies and coverages required of Owner by the Contract (if any). None Required.
- G. Failure of Owner or Contractor to demand such certificates or other evidence of the other party's full compliance with these insurance requirements, or failure of Owner or Contractor to identify a deficiency in compliance from the evidence provided, will not be construed as a waiver of the other party's obligation to obtain and maintain such insurance.
- H. In addition to the liability insurance required to be provided by Contractor, the Owner, at Owner's sole option, may purchase and maintain Owner's own liability insurance. Owner's liability policies, if any, operate separately and independently from policies required to be provided by Contractor, and Contractor cannot rely upon Owner's liability policies for any of Contractor's obligations to the Owner, Engineer, or third parties.

- I. Contractor shall require:
1. Subcontractors to purchase and maintain workers' compensation, commercial general liability and other insurance coverages required by Contractor where appropriate and applicable for their participation in the Project, and to name as additional insureds Owner and Engineer (and any other individuals or entities identified as additional insureds on Contractor's liability policies) on each Subcontractor's commercial general liability, automobile liability, and excess or umbrella insurance policy. Owner, Engineer and other additional insureds shall be covered under Subcontractors' commercial general liability and any umbrella insurance with respect to liabilities arising out of both ongoing and completed operations of Subcontractor(s). Such additional insured coverage shall be subject to the terms of ISO additional insured endorsement forms CG 20 10 (ongoing operations) and CG 20 37 (products-completed operations), or substitute form(s) providing equivalent coverage and utilizing 10/01 as the edition date of the ISO endorsements; and
 2. Suppliers to purchase and maintain insurance that is appropriate for their participation in the Project; and
 3. If the Scope of Work to be performed and/or the work site and surrounding area creates a special or high risk exposure to on-site individuals or the public, the Owner reserves the right to require the Contractor to ensure its Subcontractors, Suppliers, or categories of Subcontractor or Supplier, to provide specific insurance with policy limits as follows: None.
- J. If either party does not purchase or maintain the insurance required of such party by the Contract, such party shall notify the other party in writing of such failure to purchase prior to the start of the Work, or of such failure to maintain prior to any change in the required coverage.
- K. If Contractor has failed to obtain and maintain required insurance, Contractor's entitlement to enter or remain at the Site will end immediately, and Owner may impose an appropriate set-off against payment for any associated costs (including but not limited to the cost of purchasing necessary insurance coverage), and exercise Owner's termination rights under Article 16.
- L. Owner does not represent that insurance coverage and limits established in this Contract necessarily will be adequate to protect Contractor or Contractor's interests. Contractor is responsible for determining whether such coverage and limits are adequate to protect its interests, and for obtaining and maintaining any additional insurance that Contractor deems necessary.
- M. The insurance and insurance limits required herein will not be deemed as a limitation on Contractor's liability, or that of its Subcontractors or Suppliers, under the indemnities granted to Owner and other individuals and entities in the Contract or otherwise.
- N. All the policies of insurance required to be purchased and maintained under this Contract will contain a provision or endorsement that the coverage afforded will not be canceled, or renewal refused, without at least 30 days prior written to Owner (10

days for cancellation due to non-payment of premium). Direct Notice of Cancellation endorsement is to be attached to corresponding certificates of insurance. In the event of any such cancellation, non-renewal or material limitation, the Contractor or subcontractor, as applicable, is obligated to replace such insurance within seven (7) days of any such cancellation, non-renewal or material limitation without a gap in coverage and file accordingly such notice with the Owner and other interested parties.

- O. The Work under this Contract shall not commence until the Contractor has verified to the Owner that all required insurance coverage as described herein, have been obtained and verifying Certificates of Insurance have been approved in writing by the Owner. The Owner's review and/or acceptance of certificates of insurance shall neither relieve Contractor of any requirement to provide the specific coverages set forth herein nor shall it constitute a waiver or acknowledgement of satisfaction of the specific insurance coverage requirements set forth in this Contract.
1. The Description of Operations/Locations/Vehicles section in the certificates of insurance should include the City of Raleigh Department/Division, Name of Project or Services, Project Dates of contract.

The Certificate holder address should read:

City of Raleigh
Post Office Box 590
Raleigh, NC 27602-0590

SC-6.03 *Contractor's Insurance*

- A. *Required Insurance:* Contractor shall purchase and maintain Worker's Compensation, Commercial General Liability, Automobile Liability, Excess/Umbrella insurance and any other insurance specified within these Supplementary Conditions. Any and all deductibles and Self-insured Retentions (SIRs) in the insurance policies shall be assumed by, and at the sole risk of the Contractor.
- B. *Supplemental Provisions:* The policies of insurance required by this SC-6.03 as supplemented must:
1. include at least the specific coverages required;
 2. be written for not less than the limits provided, or those required by Laws or Regulations, whichever is greater;
 3. remain in effect at least until the Work is complete (as set forth in Paragraph 15.06.D), and longer if expressly required elsewhere in this Contract, and at all times thereafter when Contractor may be correcting, removing, or replacing defective Work as a warranty or correction obligation, or otherwise, or returning to the Site to conduct other tasks arising from the Contract;
 4. apply with respect to the performance of the Work, whether such performance is by Contractor, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable;

5. be primary and noncontributory, evidenced by ISO form CG 20 01 04 13 (Primary and Non-Contributory – Other Insurance condition) endorsement or its equivalent, with respect to the Owner's insurance or self-insurance to the extent of the Contractor's liability hereunder. Any other insurance or self-insurance maintained by the Owner shall be excess of, and non-contributory with the coverage afforded by Contractor's commercial general liability insurance and commercial umbrella insurance, if any;
 6. provide for reinstatement of full coverage after payment of any claim;
 7. state insurers have no right of recovery or subrogation against the Owner, its agents and agencies and shall have no recourse against them for the payment of any premiums or assessments under any form of policy; and
 8. include all necessary endorsements to support the stated requirements.
- C. *Additional Insureds:* The Contractor's commercial general liability, automobile liability, employer's liability, umbrella or excess, pollution liability, and unmanned aerial vehicle liability policies must:
1. include and list as additional insureds Owner and Engineer, and any individuals or entities identified as additional insureds in this agreement;
 2. include coverage for the respective officers, directors, members, partners, employees, and consultants of all such additional insureds;
 3. afford primary and noncontributory coverage to these additional insureds for all claims covered thereby (including as applicable those arising from both ongoing and completed operations); and
 4. as to commercial general liability insurance, apply to additional insureds with respect to liability caused in whole or in part by Contractor's acts or omissions, or the acts and omissions of those working on Contractor's behalf, in the performance of Contractor's operations.
- D. *Other Additional Insureds:* If specified herein, the commercial general liability, automobile liability, umbrella or excess, pollution liability, and unmanned aerial vehicle liability policies must include as additional insureds (in addition to Owner and Engineer) the following: None.
- E. *Workers' Compensation and Employer's Liability:* Contractor shall purchase and maintain workers' compensation and employer's liability insurance for:
1. claims under workers' compensation, disability benefits, and other similar employee benefit acts.
 2. United States Longshoreman and Harbor Workers' Compensation Act and Jones Act coverage (if applicable).

3. claims for damages because of bodily injury, occupational sickness or disease, or death of Contractor's employees (by stop-gap endorsement in monopolist worker's compensation states).
4. Foreign voluntary worker compensation (if applicable).

Workers' Compensation and Related Policies	Policy limits of not less than:
Workers' Compensation	
North Carolina - State	Statutory
Employer's Liability	
Each accident	\$1,000,000
Each employee	\$1,000,000
Policy limit	\$1,000,000

- F. *Commercial General Liability—Claims Covered:* Contractor shall purchase and maintain commercial general liability insurance, covering all operations by or on behalf of Contractor, on an occurrence basis, against claims for:
1. damages because of bodily injury, sickness or disease, or death of any person other than Contractor's employees,
 2. damages insured by reasonably available personal injury and advertising liability coverage, and
 3. damages because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom.
- G. *Commercial General Liability—Form and Content:* Contractor's commercial liability policy must be written on an Insurance Services Organization, Inc. (ISO) commercial general liability form (occurrence form) and include the following coverages and endorsements:
1. Products and completed operations coverage.
 - a. Such insurance must be maintained for the period of the applicable statute of repose for any and all claims that may arise from operations of this Contract.
 - b. Contractor shall furnish Owner and each other additional insured (as identified in herein or elsewhere in the Contract) certificates of insurance evidencing continuation of such insurance at final payment and for the period of the applicable statute of limitations and repose.
 2. Blanket contractual liability coverage, including but not limited to coverage of Contractor's contractual indemnity obligations in this Contract in accordance with ISO policy form CG 00 01.
 - a. Premises/Operations liability
 - b. Underground fault, explosion, and collapse coverage

- c. Independent Contractor's and Independent Subcontractor's coverage
 - d. Broad form property damage
 - e. Personal injury and advertising coverage
 - f. Cross Liability/Severability of Interest clause
 - g. Employer's Stop Gap Liability endorsement, if applicable
 - i. Amendment of the Pollution Exclusion Endorsement to allow coverage for bodily injury or property damage caused by heat, smoke, or fumes from a hostile fire
 - j. Designated General Aggregate Limit Endorsement, if required in Contract
 - k. Products completed operations including construction defect and contractual liability
 - l. Insurance coverage limits to be on a "per project" basis
- 3. Additional insured endorsements that include both ongoing operations and products and completed operations coverage through ISO Endorsements CG 20 10 10 01 and CG 20 37 10 01 (together). If Contractor demonstrates to Owner that the specified ISO endorsements are not commercially available, then Contractor may satisfy this requirement by providing equivalent endorsements.
 - 4. For design professional additional insureds, ISO Endorsement CG 20 32 07 13 "Additional Insured—Engineers, Architects or Surveyors Not Engaged by the Named Insured" or its equivalent.
- H. *Commercial General Liability—Excluded Content*: The commercial general liability insurance policy, including its coverages, endorsements, and incorporated provisions, must not include any of the following:
- 1. Any modification of the standard definition of "insured contract" (except to delete the railroad protective liability exclusion if Contractor is required to indemnify a railroad or others with respect to Work within 50 feet of railroad property).
 - 2. Any exclusion for water intrusion or water damage.
 - 3. Any provisions resulting in the erosion of insurance limits by defense costs other than those already incorporated in ISO form CG 00 01.
 - 4. Any exclusion of coverage relating to earth subsidence or movement.
 - 5. Any exclusion for the insured's vicarious liability, strict liability, or statutory liability (other than worker's compensation).
 - 6. Any limitation or exclusion based on the nature of Contractor's Work.

7. Any professional liability exclusion broader in effect than the most recent edition of ISO form CG 22 79.

I. *Commercial General Liability—Minimum Policy Limits*

Commercial General Liability	Policy limits of not less than:
General Aggregate	\$5,000,000
Products—Completed Operations Aggregate	\$5,000,000
Bodily Injury and Property Damage—Each Occurrence	\$2,000,000
Personal and Advertising Injury	\$2,000,000

- J. *Automobile Liability:* Contractor shall purchase and maintain automobile liability insurance for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance, or use of any motor vehicle owned, hired or otherwise operated or used by or on behalf of the Contractor or any of its Derivative Parties and as used in the execution of the Work. The automobile liability policy must be written on an occurrence basis.

Automobile Liability	Policy limits of not less than:
Combined Single Limit	
Combined Single Limit (Bodily Injury and Property Damage) (Any/Owned, Hired, and Leased)	\$1,000,000

- K. *Umbrella or Excess Liability:* Contractor shall purchase and maintain umbrella or excess liability insurance written over the underlying employer's liability, commercial general liability, and automobile liability insurance described in the Paragraphs above. The coverage afforded must be at least as broad as that of each and every one of the underlying policies using a follows form coverage for all layers and coverage shall remain continuously in effect and without interruption from the date of commencement of construction until the end of the applicable statute of limitations and repose.

Excess or Umbrella Liability	Policy limits of not less than:
Each Occurrence	\$2,000,000
General Aggregate	\$2,000,000

- L. *Using Umbrella or Excess Liability Insurance to Meet CGL and Other Policy Limit Requirements:* Contractor may meet the policy limits specified for employer's liability, commercial general liability, and automobile liability through the primary policies alone, or through combinations of the primary insurance policy's policy limits and limits of an umbrella or excess liability policy.
- M. *Contractor's Pollution Liability Insurance:* Contractor shall purchase and maintain a policy that must include Asbestos Legal Liability and Errors and Omissions due to potential environmental hazards.

1. Coverage shall apply to the scope of work described in this Contract including transportation and shall include coverage for bodily injury, property damage, including loss of use of damaged property, clean-up costs, mold, defense and investigative costs. Contractor shall maintain Completed Operations coverage for three (3) years following final acceptance of the project or termination of the Contract.
2. If the insurance policy is written on a claims-made basis, Contractor warrants that continuous coverage will be maintained or an extended discovery period will be exercised for a period of three (3) following final acceptance of the Work under the Contract is completed or termination of the Contract..
3. If coverage is canceled or non-renewed, and not replaced with another claims made policy form with a retroactive date prior to the Contract effective date or start of work date the Contractor must purchase an extended period coverage for a minimum of five (5) years following final acceptance of the Work or termination of the Contract.. A copy of the claims reporting requirements must be submitted to Owner for review. Pollution Liability shall not contain lead-based paint or asbestos exclusions.

This insurance must be maintained for no less than three years after final completion.

Contractor's Pollution Liability	Policy limits of not less than:
Each Occurrence/Claim	\$3,000,000
General Aggregate	\$3,000,000

N. *Contractor's Professional Liability Insurance:* If Contractor will provide or furnish professional services under this *Contract*, through a delegation of professional design services or otherwise, then Contractor shall be responsible for purchasing and maintaining applicable professional liability insurance to protect Owner from liability arising out of or resulting from the performance of professional services by Contractor or its Derivative Parties.

1. This insurance must cover negligent acts, errors, or omissions in the performance of professional design or related services by the insured or others for whom the insured is legally liable and shall contain full prior acts coverage.
2. Coverage shall not include any exclusions or limitations related to a) Scope of professional services; b) Delays in project completion or cost overruns; c) Who is authorized to notify the carrier of a claim or a potential claim; and d) Mold, fungus, asbestos, pollutants or hazardous substances.
3. The insurance must be maintained continuously throughout the duration of the Contract and through the applicable statute of limitations and repose.
4. Claims made coverage is permitted providing the retroactive date on the policy pre-dates the commencement of furnishing services on the Project.

Contractor's Professional Liability	Policy limits of not less than:
Each Claim	\$1,000,000
Annual Aggregate	\$3,000,000

- O. *Unmanned Aerial Vehicle Liability Insurance:* If Contractor or its Subcontractors uses unmanned aerial vehicles (UAV—commonly *referred* to as drones) at the Site or in support of any aspect of the Work, Contractor shall obtain UAV liability insurance in the amounts stated; name Owner, Engineer, and all individuals and entities identified herein as additional insureds; and provide a certificate to Owner confirming Contractor's compliance with this requirement.

1. Such insurance will provide coverage for property damage, bodily injury or death, and invasion of privacy. The operator of the aircraft and their insurer(s) must hold the Owner and all additional insureds harmless and waive subrogation with respect to damage to the aircraft. If the aircraft is to be used to perform lifts at the Site, a "slung cargo" endorsement must be included to cover the full replacement value of any equipment being lifted.

Unmanned Aerial Vehicle Liability Insurance	Policy limits of not less than:
Each Claim	\$1,000,000
General Aggregate	\$1,000,000

- P. *Other Required Insurance:* None.

SC-6.04 *Builder's Risk and Other Property Insurance*

- A. *Builder's Risk:* If applicable, Contractor shall purchase and maintain builder's risk insurance upon the Work on a completed value basis, in the amount of the Work's full insurable replacement cost (subject to such deductible amounts as may be provided in this Section or required by Laws and Regulations) and name the Owner a Loss Payee on the insurance coverage(s).
- B. *Property Insurance for Facilities of Owner Where Work Will Occur:* Owner is responsible for obtaining and maintaining property insurance covering each Owner owned structure, building, or facility in which any part of the Work will occur, or to which any part of the Work will attach or be adjoined. Such property insurance will be written on a special perils (all-risk) form, on a replacement cost basis, providing coverage consistent with that required for the builder's risk insurance, and will be maintained until the Work is complete, as set forth in Paragraph 15.06.D.
- C. *Property Insurance for Substantially Complete Facilities:* Promptly after Substantial Completion, and before actual occupancy or use of the substantially completed Work, Owner will obtain property insurance for such substantially completed Work, and maintain such property insurance at least until the Work is complete, as set forth in Paragraph 15.06.D. Such property insurance will be written on a special perils (all-risk) form, on a replacement cost basis, and provide coverage consistent with that required for the builder's risk insurance. The builder's risk insurance may terminate upon written confirmation of Owner's procurement of such property insurance.

- D. *Partial Occupancy or Use by Owner*: If Owner will occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work, as provided in Paragraph 15.04, then Owner (directly, if it is the purchaser of the builder's risk policy, or through Contractor) will provide advance notice of such occupancy or use to the builder's risk insurer, and obtain an endorsement consenting to the continuation of coverage prior to commencing such partial occupancy or use.
- E. *Insurance of Other Property; Additional Insurance*: If the express insurance provisions of the Contract do not require or address the insurance of a property item or interest, then the entity or individual owning such property item will be responsible for insuring it. If Contractor elects to obtain other special insurance to be included in or supplement the builder's risk or property insurance policies provided under this SC-6.04, it may do so at Contractor's sole expense.
- F. *Builder's Risk Requirements*: The builder's risk insurance must:
1. be written on a builder's risk "all risk" policy form that at a minimum includes insurance for physical loss or damage to the Work, temporary buildings, falsework, and materials and equipment stored and in transit, and must not exclude the coverage of the following risks:

Blasting and explosion, fire; windstorm; hail; flood; earthquake, volcanic activity, and other earth movement; lightning; riot; civil commotion; terrorism; vehicle impact; aircraft; smoke; theft; vandalism and malicious mischief; mechanical breakdown, boiler explosion, and artificially generated electric current; collapse of or structural injury to any structure due to the Contractor's operations; damage to underground structures, pipes or conduits; debris removal; demolition occasioned by enforcement of Laws and Regulations; and water damage (other than that caused by flood).

 - a. The builder's all-risk coverage shall not contain an exclusion for resulting damage caused by faulty workmanship, design or materials.
 - b. If insurance against mechanical breakdown, boiler explosion, and artificially generated electric current; earthquake, volcanic activity, and other earth movement; or flood, are not commercially available under builder's risk policies, by endorsement or otherwise, such insurance will be provided through other insurance policies acceptable to Owner and Contractor.
 2. cover, as insured property, at least the following: (a) the Work and all materials, supplies, machinery, apparatus, equipment, fixtures, and other property of a similar nature that are to be incorporated into or used in the preparation, fabrication, construction, erection, or completion of the Work, including Owner-furnished or assigned property; (b) spare parts inventory required within the scope of the Contract; and (c) temporary works which are not intended to form part of the permanent constructed Work but which are intended to provide working access to the Site, or to the Work under construction, or which are intended to provide temporary support for the Work under construction, including scaffolding, form work, fences, shoring, falsework, and temporary structures.

3. cover expenses incurred in the repair or replacement of any insured property (including but not limited to fees and charges of Contractors, Engineers, and Architects).
4. extend to cover damage or loss to insured property while in temporary storage at the Site or in a storage location outside the Site (but not including property stored at the premises of a manufacturer or Supplier).
5. extend to cover damage or loss to insured property while in transit.
6. allow for the waiver of the insurer's subrogation rights, as set forth in this Contract.
7. allow for partial occupancy or use by Owner by endorsement, and without cancellation or lapse of coverage.
8. include performance/hot testing and start-up, if applicable.
9. be maintained in effect until the Work is complete, or until written confirmation of Owner's procurement of property insurance following Substantial Completion, whichever occurs first.
10. include as named insureds the Owner, Contractor, Subcontractors (of every tier), all lenders with security interests in the Site or the Project, and any other individuals or entities required by this Contract to be insured under such builder's risk policy. For purposes of SC-6.04, SC-6.05, and SC-6.06 of this and all other corresponding Supplementary Conditions, the parties required to be insured will be referred to collectively as "insureds." In addition to Owner, Contractor, and Subcontractors of every tier, include as insureds the following:
 - a. None.
11. if applicable, include, in addition to the Contract Price amount, the value of the following equipment and materials to be installed by the Contractor but furnished by the Owner or third parties:
 - a. None.

G. *Installation Floater*

1. Not required.

H. *Builder's Risk and Other Property Insurance Deductibles:* The purchaser of any required builder's risk, installation floater, or other property insurance will be responsible for costs not covered because of the application of a policy deductible.

1. The builder's risk policy (or if applicable the installation floater) will be subject to a deductible amount of no more than **\$10,000** for direct physical loss in any one occurrence.

SC-6.05 *Property Losses; Subrogation/Waiver of Rights*

- A. The builder's risk insurance policy purchased and maintained in accordance with SC-6.04 (or an installation floater policy if new construction is limited and authorized by the Owner), will contain provisions to the effect that in the event of payment of any loss or damage the insurer will have no rights of recovery against any insureds thereunder, or against Engineer or its consultants, or their officers, directors, members, partners, employees, agents, consultants, or subcontractors.
 - 1. Owner and Contractor waive all rights against each other and the respective officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, for all losses and damages caused by, arising out of, or resulting from any of the perils, risks, or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Engineer, its consultants, all individuals or entities identified in the Supplementary Conditions as builder's risk or installation floater insureds, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, under such policies for losses and damages so caused.
 - 2. None of the above waivers extends to the rights that any party making such waiver may have to the proceeds of insurance held by Owner or Contractor as trustee or fiduciary, or otherwise payable under any policy so issued.
- B. Any property insurance policy maintained by Owner covering any loss, damage, or consequential loss to Owner's existing structures, buildings, or facilities in which any part of the Work will occur, or to which any part of the Work will attach or adjoin; to adjacent structures, buildings, or facilities of Owner; or to part or all of the completed or substantially completed Work, during partial occupancy or use pursuant to Paragraph 15.04, after Substantial Completion pursuant to Paragraph 15.03 as modified by these Supplemental Conditions, or after final payment pursuant to Paragraph 15.06 as modified by these Supplemental Conditions, will contain provisions to the effect that in the event of payment of any loss or damage the insurer will have no rights of recovery against any insureds thereunder, or against Contractor, Subcontractors, or Engineer, or the officers, directors, members, partners, employees, agents, consultants, or subcontractors of each and any of them, and that the insured is allowed to waive the insurer's rights of subrogation in a written contract executed prior to the loss, damage, or consequential loss.
 - 1. Owner waives all rights against Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, for all losses and damages caused by, arising out of, or resulting from fire or any of the perils, risks, or causes of loss covered by such policies.
- C. The waivers in this SC-6.05 include the waiver of rights due to business interruption, loss of use, or other consequential loss extending beyond direct physical loss or damage to Owner's property or the Work caused by, arising out of, or resulting from fire or other insured peril, risk, or cause of loss.

- D. Contractor shall be responsible for assuring that each Subcontract contains provisions whereby the Subcontractor waives all rights against Owner, Contractor, all individuals or entities identified in the Supplementary Conditions as insureds, the Engineer and its consultants, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, for all losses and damages caused by, arising out of, relating to, or resulting from fire or other peril, risk, or cause of loss covered by builder's risk insurance, installation floater, and any other property insurance applicable to the Work.

SC-6.06 *Receipt and Application of Property Insurance Proceeds*

- A. Any insured loss under the builder's risk and other policies of property insurance required by SC-6.04 will be adjusted and settled with the named insured that purchased the policy. Such named insured shall act as fiduciary for the other insureds and give notice to such other insureds that adjustment and settlement of a claim is in progress. Any other insured may state its position regarding a claim for insured loss in writing within 15 days after receipt of notice of such claim.
- B. Proceeds for such insured losses may be made payable by the insurer either jointly to multiple insureds, or to the named insured that purchased the policy in its own right and as fiduciary for other insureds, subject to the requirements of any applicable mortgage clause. A named insured receiving insurance proceeds under the builder's risk and other policies of insurance required by SC-6.04 shall maintain such proceeds in a segregated account and distribute such proceeds in accordance with such agreement as the parties in interest may reach, or as otherwise required under the dispute resolution provisions of this Contract or applicable Laws and Regulations.
- C. If no other special agreement is reached, Contractor shall repair or replace the damaged Work, using allocated insurance proceeds.

ARTICLE 7 - CONTRACTOR'S RESPONSIBILITIES

7.02 *Supervision and Superintendence*

SC-7.02 Add the following new paragraph immediately after Paragraph 7.02.B:

- C. Contractor's On-Site Supervision: For pipeline Contractors who have more than two construction crews performing work under one contract, a general superintendent shall be assigned to the Project Site to supervise all construction crews on site. The general superintendent shall be responsible for addressing any construction related issues from the Owner, the Engineer, and/or the Department of Transportation having jurisdiction.

7.03 *Labor; Working Hours*

SC-7.03 Add the following new paragraphs immediately after Paragraph 7.03.C:

- D. Regular Working Hours: 7:00 am to 5:00 pm, Eastern Standard Time.
- E. Overtime Work: If Contractor's Work requires inspection, as determined by the Owner, more than 10 hours in a work day or 40 hours in a work week, Monday through Friday

excluding holidays, or on the weekends, Contractor shall submit a written request to the Owner five (5) working days prior to the scheduled Work. Contractor shall pay for the Resident Project Representative's time beyond the above hours at the rate of \$85 / hour.

- F. Paragraph 7.03.C will not prevent the Contractor from working outside the regular working hours provided the work will not require the inspector to be present. Such work may include start up, clean up, seeding, painting (after the base surface has been approved by the inspector), and similar items. Contractor shall submit a written request to the Owner one (1) working day prior to the scheduled Work.
- G. Contractor shall not be charged for RPR's time for Work specifically identified by the Contract Documents to be performed outside the above Work time or on weekends.

7.05 *"Or Equals"*

SC-7.05 Add the following new paragraph immediately after Paragraph 7.05.E:

- F. Requirements for "or equals" shall be submitted prior to bidding. Reference Section 00100 (Advertisement for Bids) and Section 00200, Article 11 (Instructions to Bidders) for submission deadlines of requirements for "or equals".

7.07 *Concerning Subcontractors and Suppliers*

SC-7.07.C Add the following sentences to the end of Paragraph 7.07.C:

1. Bidder shall indicate subcontractors as required on the Bid Form.
2. Bidder shall indicate Minority Business Participation on the attachment to the Bid Forms. Low Bidder shall be required to submit the followings Affidavits as included in the City of Raleigh Business Assistance Program Guidelines:
 - a. Affidavit C, Portion of the Work to be Performed by Minority Firms.
 - b. Affidavit D, Good Faith Efforts
3. Contractor whose Bid is accepted shall not substitute any person as Subcontractor in the place of the Subcontractor listed in the Bid, except:
 - a. If the listed Subcontractor's bid is later determined by the Contractor to be non-responsible or non-responsive, or the listed Subcontractor refuses to enter into a contract for the complete performance of the bid work;
 - b. or with the approval of the City for good cause shown by the Contractor.

SC-7.07.K Delete Paragraph 7.07.K in its entirety and insert the following in its place:

- K. All work performed for Contractor by a Subcontractor shall be pursuant to an appropriate agreement between the Contractor and Subcontractor. The Subcontractor shall not commence work until the Contractor has obtained all insurance as required by Paragraphs 6.02 through 6.03 inclusive as amended by these Supplementary Conditions.

SC-7.07.N Add the following new paragraph immediately after Paragraph 7.07.M:

- N. Contractor shall not award work valued at more than fifty (50%) percent of the Contract Price to Subcontractor(s). Contractor shall perform at least fifty (50%) percent of the labor with own forces, unless prior written approval is provided by the Owner.

7.08 *Patent Fees and Royalties*

SC-7.08.B In the first line, insert "North Carolina" between "by" and "Laws".

SC-7.08.B Add the following language at the end of Paragraph 7.08.B:

The parties understand and acknowledge that no North Carolina case, statute, or Constitutional provision authorizes a local government to indemnify a Contractor and that this contract provision may be unenforceable.

SC-7.08.C Delete Paragraph 7.08.C in its entirety and insert the following in its place:

- C. Contractor's indemnity, defense and hold harmless obligations to the Indemnified Parties under SC-7.18 shall apply as to any and all Losses, liabilities, damages, expenses and costs caused by, arising out of, resulting from, or in connection with any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device not specified in the Contract Documents when the Fault of the Contractor or its Derivative Parties is a proximate cause of the Losses, liabilities, damages, expenses and costs so indemnified. Provided, however, nothing herein shall require the Contractor to indemnify the Indemnified Parties against any such Losses, liabilities, damages, expenses and costs arising out of, resulting from, or in connection with any negligent acts of one or more of the Indemnified Parties.

7.09 *Permits*

SC-7.09.A Amend the last sentence of Paragraph 7.09.A to read as follows:

Contractor shall pay all charges of utility owners for connections for providing permanent service to the Work.

SC-7.09.B Add the following new paragraphs after Paragraph 7.09.A:

- B. Owner obtained encroachment agreements and permits are included as part of the Contract Documents. The encroachment agreements and permits are

attached as an appendix to the specifications or project manual. This Paragraph does not relieve Contractor of responsibility to comply with applicable Laws and Regulations as stated in Paragraph 7.11.

- C. Contractor shall be responsible for compliance with the terms of the encroachment agreements and permits issued by Federal/State/Local regulatory agencies. Compliance with the terms listed in the encroachment agreements and permits shall be at no additional cost to the Owner. This shall include generating and submitting any reports that may be required as a condition of the encroachment agreements and permits. All costs shall be included in the bid prices of applicable items.

7.10 Taxes

SC-7.10 Add the following new paragraphs after Paragraph 7.10.A:

- B. Procedures for reporting sales tax are included in Section 00805.

7.11 Laws and Regulations

SC-7.11.B Delete Paragraph 7.11.B in its entirety and insert the following in its place:

- B. If Contractor observes that the Specifications or Drawings are at variance with any Laws or Regulations, Contractor shall give Engineer prompt written notice thereof. If Contractor performs any Work knowing it to be contrary to such Laws or Regulations, and without such notice to Engineer, Contractor shall bear all costs arising therefrom. Contractor shall, at all times, observe and comply with and shall cause its Derivative Parties to observe and comply with all such existing Laws or Regulations. Further, Contractor's indemnity, defense and hold harmless obligations to the Indemnified Parties under SC-7.18 shall apply as to any and all Losses, liabilities, damages, expenses and costs caused by, arising out of, resulting from, or in connection with any claim, civil penalty, fine or liability arising from or based on the violation of any such Law or Regulations by the Contractor or its Derivative Parties.

SC-7.11 Add the following new paragraphs after Paragraph 7.11.C:

- D. Contractor shall be responsible for conforming to the requirements of the approved sedimentation control plan, the rules and regulations of the Erosion Control Laws of the State of North Carolina, specifically the Sedimentation Pollution Control Act of 1973 (G.S. 113A) as amended, and the local jurisdiction where the Project is located as it relates to land disturbing activities undertaken by Contractor. Contractor shall be responsible to Owner for any fines imposed on Owner as a result of Contractor's failure to comply with the above as it is further described in the Erosion Control Section of the Specifications.
- E. Contractor shall be responsible for conforming to the requirements of the NC Department of Transportation Encroachment Agreement, if attached to the Contract Documents.

- F. Should the Contractor cause the Owner to receive a Notice of Violation from a governmental agency, Contractor shall pay costs associated with Notice of Violation within ten (10) days of receipt of written notification. Costs shall include, but not be limited to:
1. Fines imposed on the Owner by the agency.
 2. Required legal newspaper publications concerning violation.
 3. Required mailings to customers concerning notification of violation.
 4. Administrative and engineering costs associated with resolving the Notice of Violation.
- G. Notice of Violation may include, but not be limited to, the following problems:
1. Sewage spill.
 2. Inadequate erosion control measures.
 3. Equipment failure during the warranty period.
- H. In the event of a sewage spill during construction, Contractor shall take the following steps as a minimum:
1. Take immediate action to contain the spill.
 2. Notify the Owner and Engineer within 30 minutes of realizing a spill has occurred.
 3. Clean up the spill as directed by the Owner. Contractor shall bear all costs associated with the cleanup.

7.12 *Record Documents*

SC-7.12 Add the following new paragraph after Paragraph 7.12.A:

- B. Record Documents shall be updated daily. Should the Owner or Engineer determine that the Record Documents are not being properly maintained, approval of future payment requests shall be withheld.

7.13 *Safety and Protection*

SC-7.13.A Add the following new subparagraph after Paragraph 7.13.A:

1. When tasks (operating valves, lock out – tag out, etc.) must be accomplished by City staff to allow Contractor to perform or continue its Work, Contractor shall independently verify and confirm the performance of the tasks prior to performing the impacted Work.

SC-7.13.D Delete Paragraph 7.13.D its entirety and insert the following in its place:

- D. Contractor shall be responsible for remedying damage, injury, or loss to any property referred to in Paragraph 7.13.C.2 or 7.13.C.3 as follows:
 - 1. To the fullest extent allowed by Laws and Regulations, Contractor shall remedy at its own expense any and all damage, injury, or loss to any property referred to in Paragraph 7.13.C.2 or 7.13.C.3 arising out of, or resulting from the sole negligence of the Contractor, the Contractor's agents, the Contractor's employees, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable.
 - 2. In matters other than those covered by subsection SC-7.18.A, and to the fullest extent allowed by Laws and Regulations, Contractor shall remedy at its own expense any and all damage, injury, or loss to any property referred to in Paragraph 7.13.C.2 or 7.13.C.3 arising out of, resulting from, or in connection with the execution of the Work provided for in this Contract when the Fault of the Contractor or its Derivative Parties is a proximate cause of such damage, injury, or loss. For the purposes of this section, the terms "Fault" and "Derivative Parties" shall have the same meaning as that set forth in SC-7.18.E.

7.16 *Submittals*

SC-7.16D.2 In the first sentence, replace "two" with "three".

SC-7.16 Add the following new paragraph immediately after Paragraph 7.16.F:

- G. All materials or equipment delivered to the Site shall be accompanied by certificates, signed by an authorized officer of the supplier, and notarized guaranteeing that the materials or equipment conform to specification requirements. Such certificates shall be immediately turned over to the Engineer. Materials or equipment delivered to the Site without such certificates will be subject to rejection.

7.18 *Indemnification*

SC-7.18 Delete Paragraphs 7.18.A and 7.18.B in their entirety and insert the following in their place:

- A. To the fullest extent allowed by Laws and Regulations, Contractor shall indemnify, defend, and hold harmless the Owner, its officers, officials, employees, agents, or indemnities (collectively called "Indemnified Parties") from and against those Losses, liabilities, damages, and costs proximately caused by, arising out of, or resulting from the sole negligence of the Contractor, the Contractor's agents, or the Contractor's employees.
- B. In matters other than those covered by subsection 7.18A, above, and to the fullest extent allowed by Laws and Regulations, Contractor shall indemnify, defend, and hold harmless the Indemnified Parties from and against those Losses, liabilities, damages, and costs caused by, arising out of, resulting from, or in connection with

the execution of the Work provided for in this Contract when the Fault of the Contractor or its Derivative Parties is a proximate cause of the Loss, liability, damage, or expense indemnified.

- C. Costs and expenses shall include attorneys' fees, litigation or arbitration expenses, or court costs actually incurred by the Indemnified Parties to defend against third-party claims alleged in any court, tribunal, or alternative dispute resolution procedure required of any of the Indemnified Parties by Laws and Regulations or by contract, only if the Fault of the Contractor or its Derivative Parties is a proximate cause of the attorney's fees, litigation or arbitration expenses, or court costs to be indemnified.
- D. The Contractor's duty to indemnify, defend, and hold harmless described hereinabove shall survive the termination or expiration of this Contract.
- E. Definitions:
 - 1. For the purposes of SC-7.18, the term "Fault" shall mean any breach of contract; negligent, reckless, or intentional act or omission constituting a tort under applicable statutes or common law; or violation of applicable statutes or regulations.
 - 2. For the purposes of SC-7.18, the term "Loss" or "Losses" shall include, but not be limited to, fines, penalties, and/or judgments issued or levied by any local, state, or federal governmental entity.
 - 3. For the purposes of SC-7.18, the term "Derivative Parties" shall mean any of the Contractor's Subcontractors, agents, employees, or other persons or entities for which the Contractor may be liable or responsible as a result of any statutory, tort, or contractual duty.

ARTICLE 8 - OTHER WORK AT THE SITE

8.01 *Other Work*

SC-8.01.E Amend the first sentence of Paragraph 8.01.E to read as follows:

- E. If the proper execution or results of any part of Contractor's Work depends upon work performed by others, Contractor shall inspect such other work and within seven days report to Engineer in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of Contractor's Work.

SC-8.01 Add the following new paragraphs immediately after Paragraph 8.01.F.

- G. Prime contracts will be let in connection with the Project as outlined in Specification Section - Summary of Work.

- H. The Owner, Engineer, and Engineer's consultants shall not be liable to Contractor for any claims, costs, losses or damages incurred or sustained by Contractor on or in connection with any other project or anticipated project.

8.02 *Coordination*

SC-8.02 Add the following new Paragraph 8.02.C immediately after Paragraph 8.02.B:

- C. If Owner intends to contract with others for the performance of other work at or adjacent to the Site:

- 1. None.

8.03 *Legal Relationships*

SC-8.03 Delete Paragraph 8.03.C in its entirety and insert the following in its place:

- C. If Contractor or its Derivative Parties damage(s), delay(s), disrupt(s), or interfere(s) with the work of any other contractor, or any utility owner performing other work at or adjacent to the Site, through Contractor's or its Derivative Parties' failure to take reasonable and customary measures to avoid such impacts, or if any claim arising out of Contractor's or its Derivative Parties' action(s), inaction(s), or negligence in performance of the Work at or adjacent to the Site is made by any such other contractor or utility owner against Contractor or Owner, then Contractor shall promptly attempt to settle the claim as to all parties through negotiations with such other contractor or utility owner, or otherwise resolve the claim by arbitration or other dispute resolution proceeding, or in a court of competent jurisdiction. In addition, the Contractor's indemnity, defense and hold harmless obligations to the Indemnified Parties under SC-7.18 shall apply as to any and all Losses, liabilities, damages, expenses and costs arising out of, resulting from, or in connection with any and all claims brought by any such other contractor or utility owner against one or more of the Indemnified Parties that arise out of or relate to any such damage, delay, disruption or interference when the Fault of the Contractor or its Derivative Parties is a proximate cause of the Losses, liabilities, damages, expenses and costs so indemnified. Provided, however, nothing herein shall require the Contractor to indemnify the Indemnified Parties against any such claims arising out of, resulting from, or in connection with any negligent acts of one or more of the Indemnified Parties.

ARTICLE 9 - OWNER'S RESPONSIBILITIES

9.11 *Evidence of Financial Arrangements*

SC-9.11 Add the following new paragraph immediately after Paragraph 9.11.A:

- B. On request of Contractor, prior to the execution of any Change Order involving a significant increase in the Contract Price, Owner shall furnish to Contractor reasonable evidence that adequate financial arrangements have been made by Owner to enable Owner to fulfill the increased financial obligations to be undertaken by Owner as a result of such Change Order.

ARTICLE 10 - ENGINEER'S STATUS DURING CONSTRUCTION

10.01 *Owner's Representative*

SC-10.01.A Delete Paragraph 10.01.A in its entirety and replace with the following:

- A. Engineer will be Owner's representative during the construction period and Engineer's instructions shall be followed promptly and efficiently.

10.03 *Resident Project Representative*

SC-10.03.A Add the following new subparagraphs immediately following Paragraph 10.03.A:

1. The Resident Project Representative (RPR) will serve as the Engineer's liaison with the Contractor, working principally through the Contractor's superintendent to assist the Contractor in understanding the intent of the Contract Documents.
2. The RPR shall conduct on-site observations of the Work in progress to confirm that the Work is proceeding in accordance with the Contract Documents. They will verify that tests, equipment and systems start-ups and operating and maintenance instructions are conducted as required by the Contract Documents. They will have the authority to disapprove or reject defective Work in accordance with Article 14.
3. The RPR will be Engineer's representative at the Site. RPR's dealings in matters pertaining to the Work in general will be with Engineer and Contractor. RPR's dealings with Subcontractors will only be through or with the full knowledge or approval of Contractor. The RPR will:
 - a. *Conferences and Meetings:* Attend meetings with Contractor, such as preconstruction conferences, progress meetings, job conferences, and other Project-related meetings (but not including Contractor's safety meetings), and as appropriate prepare and circulate copies of minutes thereof.
 - b. *Safety Compliance:* Comply with Site safety programs, as they apply to RPR, and if required to do so by such safety programs, receive safety training specifically related to RPR's own personal safety while at the Site.
 - c. *Liaison*
 - i) Serve as Engineer's liaison with Contractor. Working principally through Contractor's authorized representative or designee, assist in providing information regarding the provisions and intent of the Contract Documents.
 - ii) Assist Engineer in serving as Owner's liaison with Contractor when Contractor's operations affect Owner's on-Site operations.

- iii) Assist in obtaining from Owner additional details or information, when required for Contractor's proper execution of the Work.
- d. *Review of Work; Defective Work*
 - i) Conduct on-Site observations of the Work to assist Engineer in determining, to the extent set forth in Paragraph 10.02, if the Work is in general proceeding in accordance with the Contract Documents.
 - ii) Observe whether any Work in place appears to be defective.
 - iii) Observe whether any Work in place should be uncovered for observation, or requires special testing, inspection or approval.
- e. *Inspections and Tests*
 - i) Observe Contractor-arranged inspections required by Laws and Regulations, including but not limited to those performed by public or other agencies having jurisdiction over the Work.
 - ii) Accompany visiting inspectors representing public or other agencies having jurisdiction over the Work.
- f. *Payment Requests: Review Applications for Payment with Contractor.*
- g. *Completion*
 - i) Participate in Engineer's visits regarding Substantial Completion.
 - ii) Assist in the preparation of a punch list of items to be completed or corrected.
 - iii) Participate in Engineer's visits to the Site in the company of Owner and Contractor regarding completion of the Work and assist in preparation of a final punch list of items to be completed or corrected by Contractor.
 - iv) Observe whether items on the final punch list have been completed or corrected.
- 4. Except upon written instructions of the Engineer, the RPR or Owner's field staff shall not have authority to:
 - a. Authorize any deviation from the Contract Documents or approve any substitute materials or equipment (including "or-equal" items).
 - b. Exceed limitations of Engineer's authority as set forth in the Contract Documents.
 - c. Undertake any of the responsibilities of Contractor, Subcontractors, or Suppliers.

- d. Advise on, issue directions relative to, or assume control over any aspect of the means, methods, techniques, sequences or procedures of construction.
 - e. Advise on, issue directions regarding, or assume control over security or safety practices, precautions, and programs in connection with the activities or operations of Owner or Contractor.
 - f. Participate in specialized field or laboratory tests or inspections conducted off-site by others except as specifically authorized by Engineer.
 - g. Authorize Owner to occupy the Project in whole or in part.
 - h. Supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work.
 - i. Be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.
 - j. Be responsible for the acts or omissions of Contractor or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.
5. Any decision made by RPR or Owner's field staff in good faith either to exercise or not exercise such authority or responsibility, or the undertaking, exercise, or performance of any authority or responsibility by RPR or Owner's field staff, will create, impose, or give rise to any duty in contract, tort, or otherwise owed by RPR or Owner's field staff to Contractor, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.
6. RPR's or Owner's field staff's review of the final Application for Payment and accompanying documentation, and all maintenance and operating instructions, schedules, guarantees, bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by Contractor under Paragraph 15.06.A, will only be to determine generally that their content complies with the requirements of, and in the case of certificates of inspections, tests, and approvals, that the results certified indicate compliance with, the Contract Documents.

SC-10.03.B Add the following new subparagraph immediately following Paragraph 10.03.B:

- 1. When the Owner assigns City field staff to monitor the project, such staff's limitations shall be as described in SC-10.03.A.4, SC-10.03.A.5 and SC-10.03.A.6.

ARTICLE 11 - CHANGES TO THE CONTRACT

11.07 *Change of Contract Price*

SC-11.07.B.2 Delete this subparagraph in its entirety and replace with the following:

2. Where the Work involved is not covered by unit prices contained in the Contract Documents, then by a mutually agreed lump sum (with allowances for overhead and profit in accordance with Paragraph 11.07.C.2); or"

11.08 *Change of Contract Times*

SC-11.08 Add the following paragraph after Paragraph 11.08.B:

- C. Time Extension: Contract time extensions for weather delays do not entitle Contractor to "extended overhead" recovery.

ARTICLE 12 - CLAIMS

No Supplementary Conditions in this Article.

ARTICLE 13 - COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

13.01 *Cost of the Work*

SC-13.01.B.1 Delete Paragraph 13.01.B.1 in its entirety and replace with the following:

Payroll costs for employees in the direct employ of Contractor in the performance of the Work under schedules of job classifications agreed upon by Owner and Contractor. Such employees shall include, without limitation, superintendents, foremen, and other personnel employed full time on the Work. Payroll costs for employees not employed full time on the Work shall be apportioned on the basis of their time spent on the Work. Payroll costs shall include, but not be limited to, salaries and wages plus the cost of fringe benefits, which shall include social security contributions, unemployment, excise, and payroll taxes, workers' compensation, health and retirement benefits, bonuses, sick leave, vacation and holiday pay applicable thereto. Labor will be based on direct labor cost, Contractor to provide certified payroll upon request. No claims for extra cost shall be considered based on an escalation of labor costs throughout the period of the Contract.

SC-13.01.B.2 Add the following language at the end of the Paragraph:

No claims for extra cost shall be considered based on an escalation of material costs throughout the period of the Contract.

SC-13.01.B.3 Delete the second sentence "If required...be acceptable."

SC-13.01.B.4 Delete in its entirety.

SC-13.01.B.5.a Delete Paragraph in its entirety.

SC-13.01.B.5.c Delete Paragraph 13.01.B.5.c in its entirety and insert the following in its place:

c. Construction Equipment and Machinery:

1. Rentals of all construction equipment and machinery, and the parts thereof in accordance with rental agreements approved by Owner with the advice of Engineer, and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs shall be in accordance with the terms of said rental agreements. The rental of any such equipment, machinery, or parts shall cease when the use thereof is no longer necessary for the Work.
2. Full rental cost for rented, leased, and/or owned equipment shall not exceed rates listed in the current version of Rental Rate Blue Book for Construction Equipment (Blue Book). If rental rates for the equipment being used for the Work are not listed in the Blue Book, the Contractor will receive the prevailing rental rates being paid for such equipment in the area where the Project is located. Computed durations will be based upon the Work completed. Computed rates will include all operating costs; costs will include the time the equipment or machinery is in use on the changed Work and the costs of transportation, loading, unloading, assembly, dismantling, and removal when directly attributable to the changed Work. The cost of any such equipment or machinery, or parts thereof, shall cease to accrue when the use thereof is no longer necessary for the changed Work. Equipment or machinery with a value of less than \$1,000 will be considered small tools. The Engineer/Owner reserves the right to request four rental quotes as backup.
3. The hours of operation shall be based upon actual equipment usage to the nearest full hour, as recorded by the Engineer.

<u>Usage</u>	<u>Blue Book Payment Category</u>
Less than 8 hours	Hourly Rate
8 or more hours but less than 4 days	Daily Rate
4 or more days but less than 16 days	Weekly Rate
16 or more days	Monthly Rate

SC-13.01.B.5.d Add the following language at the end of the Paragraph:

However, reimbursable sales and use taxes paid to the State of North Carolina or to local governments in North Carolina shall be included or excluded from the Cost of the Work as described in Section 00805.

SC-13.01.B.5.f Delete Paragraph in its entirety.

SC-13.01.B.5.g Delete Paragraph in its entirety.

SC-13.01.B.5.h Delete Paragraph in its entirety.

SC-13.01.C.1 Add the following language at the end of the Paragraph.

Project Management will not be included in the Cost of the Work.

13.03 *Unit Price Work*

SC-13.03.E.1.a Delete Paragraph 13.03.E.1.a in its entirety and insert the following in its place:

- a. The extended Bid price of a particular item of Unit Price Work (excluding rock excavation and undercut) amounts to five (5) percent or more of the Contract Price (based on estimated quantities at the time of Contract formation) and the variation in the quantity of that particular item of Unit Price Work actually furnished or performed by Contractor differs by more than twenty-five (25) percent from the estimated quantity of such item indicated in the Agreement at the time of Contract formation; and

ARTICLE 14 - TESTS AND INSPECTIONS; CORRECTION, REMOVAL, OR ACCEPTANCE OF DEFECTIVE WORK

14.02 *Tests, Inspections, and Approvals*

SC-14.02.B Delete Paragraph 14.02.B in its entirety and insert the following in its place:

- B. Owner shall employ and pay for inspections and testing services specifically noted as such in the Contract. All others required shall be the responsibility of the Contractor.

SC-14.02.C Delete Paragraph 14.02.C in its entirety and insert the following in its place:

- C. If the Contract Documents, laws, ordinances, rules, regulations or orders of any public authority having jurisdiction require any Work to be specifically inspected, tested, or approved by some public body, Contractor shall assume full responsibility therefore, pay all costs in connection therewith, and furnish Engineer the required certificates of inspection, testing or approval.

SC-14.02.G Add the following paragraph(s) immediately following Paragraph 14.02.F:

- G. Owner reserves the right to independently perform at its own expense, laboratory tests on random samples of material or performance tests on equipment delivered to the Site. These tests if made will be conducted in accordance with the appropriate referenced standards or Specification requirements. The entire shipment represented by a given sample, samples or piece of equipment may be rejected on the basis of the failure of samples or pieces of equipment to meet specified test requirements. All rejected materials or equipment shall be removed from the Site, whether stored or installed in the Work, and the required replacement shall be made, all at no additional cost to the Owner.

14.03 *Defective Work*

SC-14.03.G Add a new paragraph after Paragraph 14.03.F:

- G. At any time during the progress of the Work and up to the date of final acceptance, the Engineer shall have the right to reject any Work which does not conform to the requirements of the Contract Documents, even though such Work has been previously inspected and paid for. Any omissions or failure on the part of the Engineer to disapprove or reject any Work or materials at the time of inspection shall not be construed as an acceptance of any defective Work or materials.

14.06 *Owner May Stop the Work*

SC-14.06.A Add the following language to the first sentence of Paragraph 14.06.A after:

".....will conform to the Contract Documents," add "or if the Work interferes with the operation of the existing facility", and then continue "then Owner may order..."

ARTICLE 15 - PAYMENTS TO CONTRACTOR; SET-OFFS; COMPLETION; CORRECTION PERIOD

15.01 *Progress Payments*

SC-15.01.A Add the following paragraph immediately following Paragraph 15.01.A:

1. The Contractor shall submit for the Engineer's approval, a complete breakdown of all Lump Sum Items in the Bid. This breakdown, modified as directed by the Engineer, will be used as a basis for preparing estimates and establishing progress payments.

SC-15.01.B.4 Delete Subparagraph 15.01.B.4 in its entirety and replace with the following:

4. Progress payment request shall include the percentage of the total amount of the Contract which has been completed from the start-up of the Project to and including the last day of the preceding month, or other mutually agreed upon day of the month accompanied by such data and supporting evidence as Owner or Engineer may require.

SC-15.01.B. Add the following new subparagraphs after Subparagraph 15.01.B.4:

5. Forms shall be prepared by the Contractor and submitted to the Engineer for approval. Forms to be used are included in Section 00620 and will be supplied by the Engineer.
6. At the option of the Owner, partial payment up to the estimated value, less retainage, may be allowed for any materials and equipment not incorporated in the Work, pursuant to the following conditions:
 - a. Major equipment items stored off site shall be stored in a bonded warehouse and properly maintained during storage.
 - b. Equipment or materials stored on the Site shall be properly stored, protected and maintained.

- c. For any partial payment the Contractor shall submit, with the monthly progress payment from each material or equipment manufacturer, bills or invoices indicating actual material cost.
 - d. Contractor shall submit evidence that payment has been made for materials or equipment stored and for which the Engineer has authorized partial payment and previous progress payments, prior to submission of the next monthly payment request.
- 7. The Owner will retain five percent (5%) of the amount of each such estimate until Work covered by the Contract is 50% complete. When 50% of the Work of the original Contract has been completed and in the opinion of the Owner the Contractor continues to perform satisfactorily and nonconforming Work identified in writing prior to that time by the Engineer or Owner has been corrected by the Contractor and accepted by the Owner, the Owner with written consent of surety will adjust future partial payments so that two and one-half percent (2-1/2%) of the original Contract Price is retained.
 - 8. The Project shall be deemed 50% complete when the Contractor's gross project invoices, excluding the value of materials stored off-site, equals or exceeds 50% of the original value of the Contract, except the value of materials stored on-site shall not exceed 20% of the Contractor's gross invoices for the purpose of determining whether the project is 50% complete.
 - 9. If the Owner determines it is appropriate to reduce retainage, the method used for such adjustment shall be to fix retainage at two and one-half percent (2-1/2%) of the original Contract amount (when the Work is 50% complete) and to pay all subsequent Partial Payment Requests to the full approved amount. The intent of such an adjustment is to gradually reduce retainage to two and one-half percent (2-1/2%) of the original Contract amount when the Work is 100% complete. Following 50% completion of the Project, the Owner may also withhold additional retainage from any subsequent periodic payment, not to exceed five percent (5%), in order to allow the Owner to retain two and one-half percent (2-1/2%) total retainage through the completion of the Project.
 - 10. If the Owner determines the Contractor's performance is unsatisfactory, the Owner may reinstate retainage for each subsequent periodic payment application up to a maximum amount of five (5) percent of the original Contract amount.
 - 11. Within 60 days after the submission of a final pay application, the Owner with written consent of the surety shall release to the Contractor all retainage on payments held by the Owner if (1) the Owner receives a certificate of substantial completion from the Engineer, or (2) the Owner receives beneficial occupancy or use of the Project. However, the Owner may retain sufficient funds to secure completion of the Project or corrections on any Work. If the Owner retains funds, the amount retained shall not be more than 2.5 times the Engineer's estimated value of the Work to be completed or corrected. Any reduction in the amount of the retainage on payments shall be with the written consent of the Contractor's surety.

12. Retainer provisions contained in Contractor's subcontracts may not exceed the terms and conditions for retainage provided herein. Contractor is further required to satisfy the retainage provisions of N.C.G.S. 143-134.1(b2) with regard to subcontracts for early finishing trades (structural steel, piling, caisson, and demolition) and to coordinate the release of retainage for such trades from the retainage held by the Owner from the Contractor pursuant to statute.
13. Nothing shall prevent the Owner from withholding payment to the Contractor in addition to the amounts identified herein for unsatisfactory job progress, defective construction not remedied, disputed work, or third-party claims filed against the Owner or reasonable evidence that a third-party claim will be filed.

SC-15.01.C.6 Add the following new subparagraphs after Subparagraph 15.01.C.6.e:

- f. Sedimentation and erosion control are determined to be unsatisfactory or unacceptable. A deduction of up to 10% of the payment amount for bid items that include sedimentation and erosion control installed during the payment period may be withheld in order to ensure remediation of the unsatisfactory or unacceptable work. Upon remediation, Contractor may receive payment for the deduction in subsequent Application for Payment.
- g. Seeding and mulching are determined to be unsatisfactory or unacceptable. A deduction of up to 20% of the payment amount for bid items that include seeding and mulching installed during the payment period may be withheld in order to ensure remediation of the unsatisfactory or unacceptable work. Upon remediation, Contractor may receive payment for the deduction in subsequent Application for Payment.
- h. Record Documents are not maintained satisfactorily and in accordance with the Contract Documents. Payment requests shall not be approved until the deficiencies are satisfactorily corrected.

SC-15.01.D.1 Delete Paragraph 15.01.D.1 in its entirety and insert the following in its place:

1. Upon receipt from Engineer of an Application for Payment bearing Engineer's recommendation of payment, Owner shall set off against the amount recommended by Engineer any sums to which Owner is entitled pursuant to Sec. 15.01.E of the General Conditions and shall then approve the Application for Payment. Owner shall tender the resulting balance due to Contractor within thirty (30) days of Owner's approval of the Application for Payment

15.03 *Substantial Completion*

SC-15.03 Add the following new subparagraph to Paragraph 15.03.B:

1. If some or all of the Work has been determined not to be at a point of Substantial Completion and will require re-inspection or re-testing by Engineer, the cost of such re-inspection or re-testing, including the cost of time, travel and living expenses, will be paid by Contractor to Owner. If Contractor does not pay, or the

parties are unable to agree as to the amount owed, then Owner may impose a reasonable set-off against payments due under this Article 15.

15.06 *Final Payment*

SC-15.06.E Delete Paragraph 15.06.E in its entirety and insert the following in its place:

Final Payment Becomes Due: Upon receipt from Engineer of the final Application for Payment bearing Engineer's recommendation of payment, Engineer's notice of acceptability, and accompanying documentation, Owner shall set off against the amount recommended by Engineer for final payment any further sum to which Owner is entitled pursuant to Sec. 15.01.E of the General Conditions, and shall then approve the final Application for Payment. Owner shall tender the resulting balance due to Contractor within thirty (30) days of Owner's approval of the final Application for Payment.

ARTICLE 16 - SUSPENSION OF WORK AND TERMINATION

16.01 *Owner May Suspend Work*

SC-16.01 Add the following new paragraph immediately after Paragraph 16.01A:

- B. Should the Owner suspend Work due to unsafe Work conducted by the Contractor, the Contractor shall not be allowed any adjustment in Contract Price or extension of Contract Time attributed to this delay.

16.02 *Owner May Terminate for Cause*

SC-16.02.A.3 Add the following after "jurisdiction":

"(including those governing employee safety)"

SC-16.04.A Amend the first sentence of paragraph 16.04.A as follows:

Strike out the phrase "Owner fails for 30 days" and replace with "Owner fails for 45 days after Approval by Owner".

SC-16.04.B Amend the first sentence of paragraph 16.04.B as follows:

Strike out the phrase "Owner has failed for 30 days" and replace with "Owner has failed for 45 days after Approval by Owner".

ARTICLE 17 - FINAL RESOLUTION OF DISPUTES

SC-17.01.B Delete in its entirety and replace with the following:

- B. Either Owner or Contractor may request mediation of any claim submitted to Engineer for a decision under Article 12 - Claims before such decision becomes final and binding.

SC-17.01 Add the following new paragraphs after SC-17.01.B:

- C. In accordance with GS 143-128(f), any claim, dispute or other matter in question (involving greater than \$15,000) arising out of or related to this Agreement shall be subject to mediation as a condition precedent to the institution of legal or equitable proceeding by either party. The dispute resolution process adopted by the N.C. State Building Commission shall be followed. The process entitled "Rules Implementing Mediated Settlement Conferences in North Carolina Construction Projects" are included in Section 00810.
- D. All matters relating to this Contract shall be governed by the laws of the State of North Carolina, without regard to its choice of law provisions, and venue for any action relating to this Contract shall be Wake County Civil Superior Court or the United States District Court for the Eastern District of North Carolina, Western Division.

ARTICLE 18 - MISCELLANEOUS

18.01 *Giving Notice*

SC-18.01.A.3 Delete in its entirety and replace with the following:

- 3. by e-mail to the recipient, with the words "Formal Notice" in the e-mail's subject line.

SC-18.01 Add the following new paragraph after Paragraph 18.01.A:

- B. No oral statement of any person whomsoever shall in any manner or degree modify or otherwise affect the terms of this Contract. Any notice by a party to this Contract to another party or parties to this Contract relative to any part of this Contract shall be in writing.

18.07 *Controlling Law*

SC-18.07.A Delete in its entirety and replace with the following:

- A. All matters relating to this Contract shall be governed by the laws of the State of North Carolina, without regard to its choice of law provisions, and venue for any action relating to this Contract shall be Wake County Civil Superior Court or the United States District Court for the Eastern District of North Carolina, Western Division.

END OF SECTION

**PROCEDURE FOR REPORTING NORTH CAROLINA SALES TAX
EXPENDITURES ON CITY OF RALEIGH CONTRACTS**
(for projects with reimbursable sales tax excluded from Bid)

1. The following procedure in handling the North Carolina Sales Tax is applicable to this project. Contractors shall comply fully with the requirements outlined hereinafter, in order that the owner may recover the amount of the tax permitted under the law. For the purposes of this section, "Sales Taxes" shall mean sales and use taxes paid to the State of North Carolina or to local governments in North Carolina.
 - (a) Reimbursable Sales Taxes are to be excluded from the bid price for this project.
 - (b) The City is entitled to refunds from the State of North Carolina for these reimbursable sales taxes. The Contractor that performs work under this contract is allowed to obtain a reimbursement from the City for those Sales Taxes for which the State will grant a refund to the City. The City will reimburse the Contractor, and the City later obtains a refund from the State.
 - (c) It shall be the general contractor's responsibility to furnish the City documentary evidence showing the materials used and sales tax paid by the general contractor and each of his subcontractors. Any county sales tax included in the contractor's statements must be shown separately from the state sales tax. If more than one county is shown, each county shall be listed separately.
 - (d) The documentary evidence shall be the attached Reimbursable Sales and Use Tax Statement. This evidence shall consist of a certified statement, by the general contractor and each of his subcontractors individually, showing total purchases of materials from each separate vendor and total sales taxes by each county paid each vendor. The certified statement must show the invoice number (s) covered and inclusive dates of such invoices. State sales tax shall be listed separately from county sales tax. If more than one county is shown, each county shall be listed separately. The invoices shall be provided to substantiate the information on the statement.
 - (e) Materials used from general contractor's or subcontractor's warehouse stock shall be shown in a certified statement at warehouse stock prices.
 - (f) The general contractor shall not be required to certify the subcontractor's statements. However, the subcontractor may submit for reimbursement by certifying a Reimbursable Sales and Use Tax Statement, submitting it to the general contractor for the general contractor to submit with the pay application for the properties listed on that form. The City will make the reimbursement payable to the Contractor.
 - (g) The documentary evidence to be furnished to owners eligible for Reimbursable Sales Tax refunds covers sales and/or use taxes paid on building materials used by general contractors and subcontractors in the performance of contracts with churches,

orphanages, hospitals not for profit, educational institutions not operated for profit and other charitable or religious institutions or organizations not operated for profit and incorporated cities, towns and counties in this State. The documentary evidence is to be submitted to the above-named institutions, organizations and governmental units to be included in claims for refunds to be prepared and submitted by them to obtain refunds provided by G.S. 105-164.14 and is to include the purchase of building materials, supplies, fixtures and equipment which become a part of or annexed to buildings or structures being erected, altered or repaired under contracts with such institutions, organizations or governmental units.

- (h) The Contractor may seek reimbursement separately from, but at the same time as, the application for payment is made for the properties that were taxed. The Contractor shall not file for reimbursement for Sales Taxes before the Contractor has the right to file an application for payment for the properties that were taxed.
- 2. If the State refuses to refund any such Sales Tax to the City, or if after a refund is made, the City is told to return a refund to the State, the Contractor shall upon demand repay the City for the amount of the failed refunds.
- 3. The contractor or contractors to whom an award is made on this project will be required to follow the procedure outlined above.
- 4. The contractor is advised that all requests for payment, partial or final, for work completed under this contract must include a sales tax report submitted in accordance with the procedures outlined above.

North Carolina Reimbursable Sales and Use Tax Statement

(Paid During This Estimate Period)

Project _____ Project Location _____ County _____ Estimate No. _____

Name of Contractor _____ Period Ending _____

Date	Vendor	Type of Property Purchased	Invoice Number	Invoice Amount	State Tax 4.75%	County Tax 2.00%	Total Tax 6.75%	County
TOTALS								

The undersigned individual certifies (1) that he or she is an employee or principal of the Contractor that is filing this form with the City to request reimbursement for N.C. State and local sales and use taxes that the Contractor has paid, (2) that the above listed vendors were paid sales tax upon purchases of building materials during the period covered by the construction estimate, and the property upon which such taxes were paid with or will be used in the performance of this contract, (3) that no tax on purchases or rentals of tools and/or equipment is included in the above list, (4) that all of the material above became a part of or is annexed to the building or structure being erected, altered or repaired, and (5) that all of the information on this form, and any additional pages added to this page, if any, is true and accurate.

_____ County, North Carolina

Signed and sworn to (or affirmed) before this day by _____
(name of principal) (signature of principal)

Date: _____
Notary Public's Signature

(Notary's printed or typed name, Notary Public)

(Official Seal) My commission expires: _____

North Carolina Reimbursable Sales and Use Tax Statement by Subcontractor

(Paid During This Estimate Period)

Project _____ Project Location _____ County _____ Estimate No. _____

Name of Subcontractor _____ Period Ending _____

Date	Vendor	Type of Property Purchased	Invoice Number	Invoice Amount	State Tax 5.50%	County Tax 2.25%	Total Tax 7.75%	County
TOTALS								

The undersigned individual certifies (1) that he or she is an employee or principal of the Subcontractor that is submitting this form with the Contractor so that the Contractor may request reimbursement for N.C. State and local sales and use taxes that the Subcontractor has paid, (2) that the above listed vendors were paid sales tax upon purchases of building materials during the period covered by the construction estimate, and the property upon which such taxes were paid with or will be used in the performance of this contract,(3) that no tax on purchases or rentals of tools and/or equipment is included in the above list, (4) that all of the material above became a part of or is annexed to the building or structure being erected, altered or repaired, and (5) that all of the information on this form, and any additional pages added to this page, if any, is true and accurate.

_____ County, North Carolina

Signed and sworn to (or affirmed) before this day by _____
(name of principal) (signature of principal)

Date: _____
Notary Public's Signature

(Notary's printed or typed name, Notary Public)

(Official Seal) My commission expires: _____

RULES IMPLEMENTING MEDIATED
SETTLEMENT CONFERENCES IN
NORTH CAROLINA PUBLIC CONSTRUCTION PROJECTS

Adopted
February 26, 2002

Table of Rules

Rule

1. Initiating Mediated Settlement Conferences
 - A. Purpose of Mandatory Settlement Conferences.
 - B. Initiating the Dispute Resolution Process.
2. Selection of Mediator
 - A. Selection of Certified Mediator by Agreement of the Parties.
 - B. Nomination and Court Approval of a Non-Certified Mediator.
 - C. Appointment of Mediator by the SCO.
 - D. Mediator Information Directory.
 - E. Disqualification of Mediator.
3. The Mediated Settlement Conference
 - A. Where Conference is to be Held.
 - B. When Conference is to be Held.
 - C. Request to Extend Deadline for Completion.
 - D. Recesses.
 - E. The Mediated Settlement Conference shall not be cause for the Delay of the Construction Project which is the focus of the Dispute.
4. Duties of Parties and Other Participants in Formal Dispute Resolution Process
 - A. Attendance.
 - B. Finalizing Agreement.
 - C. The Mediation Fee shall be paid in accordance with G.S. 143-128(g).
 - D. Failure to Compensate Mediator.
5. Authority and Duties of Mediators
 - A. Authority of Mediator.
 - B. Duties of Mediator.
6. Compensation of the Mediator
 - A. By Agreement.
 - B. By Appointment.
7. Mediator Certification
8. Rule Making
9. Definitions
10. Time Limits

RULE 1. INITIATING MEDIATED SETTLEMENT CONFERENCES

A. Purpose of Mandatory Settlement Conferences. Pursuant to G.S. 143-128(g) 143-135.26(11), these Rules are promulgated to implement a system of settlement events which are designated to focus the parties' attention on settlement rather than on claim preparation and to provide a structured opportunity for settlement negotiations to take place. Nothing herein is intended to limit or prevent the parties from engaging in settlement procedures voluntarily at any time prior to or during commencement of the dispute resolution process.

B. Initiating the Dispute Resolution Process

- 1) Any party to a public construction contract governed by Article 8. Ch. 143 of the General Statutes and identified in G.S. 143-128(g) and who is a party to a dispute arising out of the construction process in which the amount in controversy is at least \$15,000 may submit a written request to the public owner for mediation of the dispute.
- 2) Prior to submission of a written request for mediation to the public owner, the parties requesting mediation,
 - a) If a prime contractor, must have first submitted its claim to the Project Designer for review as set forth in Exhibit A. If the dispute is not resolved through the Project Designer's instructions, then the dispute becomes ripe for mediation in the Formal Dispute Resolution Process, and the party may submit his written request for mediation to the public owner.
 - b) If the party requesting mediation is a subcontractor, it must first have submitted its claim for mediation to the prime contractor with whom it has a contract. If the dispute is not resolved through the Prime Contractor's involvement, then the dispute becomes ripe for mediation in the Formal Dispute Resolution Process, and the party may submit its written request for mediation to the public owner.
 - c) If the party requesting mediation is the Project Designer, then it must first submit its claim to the public owner to resolve. If the dispute is not resolved with the public owner's involvement, then the Project Designers' dispute is ripe for mediation in the Formal Dispute Resolution Process, and the Project Designer may submit its written request to the public owner for mediation.

RULE 2. SELECTION OF MEDIATOR

A. Selection of Certified Mediator by Agreement of the Parties. The parties may select a mediator certified pursuant to the Rules by agreement within 21 days of requesting mediation. The requesting party shall file with the State Construction Office (hereinafter collectively referred to as the "SCO") or public owner if a non-State project a Notice of Selection of Mediator by Agreement within 10 days of the request; however, any party may file the notice. Such notice shall state the name, address and telephone number of the mediator selected; state the rate of compensation of the mediator; state that the mediator and opposing counsel have agreed upon the selection and rate of compensation; and state that the mediator is certified pursuant to these Rules.

- B. **Nomination and Public Owner Approval of a Non-Certified Mediator.** The parties may select a mediator who does not meet the certification requirements of these rules but who, in the opinion of the parties and the SCO or public owner, is otherwise qualified by training or experience to mediate the action.

If the parties select a non-certified mediator, the requesting party shall file with the SCO a Nomination of Non-Certified Mediator within 10 days of the request. Such nomination shall state the name, address and telephone number of the mediator; state the training, experience or other qualifications of the mediator; state the rate of compensation of the mediator; and state that the mediator and opposing counsel have agreed upon the selection and rate of compensation.

The SCO or public owner shall rule on said nomination, shall approve or disapprove of the parties' nomination and shall notify the parties of its decision.

- C. **Appointment of Mediator by the SCO.** If the parties cannot agree upon the selection of a mediator, the party or party's attorney shall so notify the SCO or public owner and request, on behalf of the parties, that the SCO or public owner appoint a mediator. The request for appointment must be filed within 10 days after request to mediate and shall state that the parties have had a full and frank discussion concerning the selection of a mediator and have been unable to agree. The request shall state whether any party prefers a certified attorney mediator, and if so, the SCO or public owner shall appoint a certified attorney mediator. If no preference is expressed, the SCO or public owner may appoint a certified attorney mediator or a certified non-attorney mediator.
- D. **Mediator Information Directory.** To assist the parties in the selection of a mediator by agreement, the parties are free to utilize the list of certified mediators maintained in any county participating in the Superior Court Mediation Settlement Conference Program.
- E. **Disqualification of Mediator.** Any party may request replacement of the mediator by the SCO or public owner for good cause. Nothing in this provision shall preclude mediators from disqualifying themselves.

RULE 3. THE MEDIATED SETTLEMENT CONFERENCE

- A. **Where Conference is to be Held.** Unless all parties and the mediator otherwise agree, the mediated settlement conference shall be held in the county where the project is located. The mediator shall be responsible for reserving a place and making arrangements for the conference and for giving timely notice of the time and location of the conference to all attorneys, unrepresented parties and other persons and entities required to attend.
- B. **When Conference is to be Held.** The deadline for completion of the mediation shall be not less than 30 days nor more than 60 days after the naming of the mediator.
- C. **Request to Extend Deadline for Completion.** A party, or the mediator, may request the SCO or public owner to extend the deadline for completion of the conference. Such request shall state the reasons the extension is sought and

shall be served by the moving party upon the other parties and the mediator. If any party does not consent to the request, said party shall promptly communicate its objection to the SCO or public owner.

The SCO or public owner may grant the request by setting a new deadline for completion of the conference.

- D. **Recesses.** The mediator may recess the conference at any time and may set times for reconvening. If the time for reconvening is set before the conference is recessed, no further notification is required for persons present at the conference.
- E. **The mediated settlement conference shall not be cause for the delay of the construction project which is the focus of the dispute.**

RULE 4. DUTIES OF PARTIES AND OTHER PARTICIPANTS IN FORMAL DISPUTE RESOLUTION PROCESS

- A. **Attendance.**
 - 1) All parties to the dispute originally presented to the Designer or Prime Contractor for initial resolution must attend the mediation. Failure of a party to a construction contract to attend the mediation will result in the public owner's withholding of monthly payment to that party until such party attends the mediation.
 - 2) Attendance shall constitute physical attendance, not by telephone or other electronic means. Any attendee on behalf of a party must have authority from that party to bind it to any agreement reached as a result of the mediation.
 - 3) Attorneys on behalf of parties may attend the mediation but are not required to do so.
 - 4) Sureties or insurance company representatives are not required to attend the mediation unless any monies paid or to be paid as a result of any agreement reached as a result of mediation require their presence or acquiescence. If such agreement or presence is required, then authorized representatives of the surety or insurance company must attend the mediation.
- B. **Finalizing Agreement.** If an agreement is reached in the conference, parties to the agreement shall reduce its terms to writing and sign it along with their counsel.
- C. **The mediation fee shall be paid in accordance with G.S. 143-128(g).**
- D. **Failure to compensate mediator.** Any party's failure to compensate the mediators in accordance with G.S. 143-128(g) shall subject that party to a withholding of said amount of money from the party's monthly payment by the public owner.

Should the public owner fail to compensate the mediator, it shall hereby be subject to a civil cause of action from the mediator for the 1/3 portion of the mediator's total fee as required by G.S. 143-128(g).

RULE 5. AUTHORITY AND DUTIES OF MEDIATORS

A. Authority of Mediator.

- 1) *Control of Conference.* The mediator shall at all times be in control of the conference and the procedures to be followed.
- 2) *Private Consultation.* The mediator may communicate privately with any participant or counsel prior to and during the conference. The fact that private communications have occurred with a participant shall be disclosed to all other participants at the beginning of the conference.
- 3) *Scheduling the Conference.* The mediator shall make a good faith effort to schedule the conference at a time that is convenient with the participants, attorneys and mediator. In the absence of agreement, the mediator shall select the date for the conference.

B. Duties of Mediator.

- 1) The mediator shall define and describe the following at the beginning of the conference:
 - a) The process of mediation;
 - b) The difference between mediation and other forms of conflict resolution;
 - c) The costs of the mediated settlement conference;
 - d) That the mediated settlement conference is not a trial, the mediator is not a judge, and the parties retain their legal rights if they do not reach settlement;
 - e) The circumstances under which the mediator may meet and communicate privately with any of the parties or with any other person;
 - f) Whether and under what conditions communications with the mediator will be held in confidence during the conference;
 - g) The inadmissibility of conduct and statements as provided by G.S. 7A-38.1(1);
 - h) The duties and responsibilities of the mediator and the participants; and
 - i) That any agreement reached will be reached by mutual consent.
- 2) *Disclosure.* The mediator has a duty to be impartial and to advise all participants of any circumstance bearing on possible bias, prejudice or partiality.
- 3) *Declaring Impasse.* It is the duty of the mediator timely to determine that an impasse exists and that the conference should end.
- 4) *Reporting Results of Conference.* The mediator shall report to the SCO or public owner within 10 days of the conference whether or not an agreement was reached by the parties. If an agreement was reached, the report shall state the nature of said agreement. The mediator's report shall inform the SCO or public owner of the absence of any party known to the mediator to have been absent from the mediated settlement conference without permission. The SCO or public owner may require the mediator to provide statistical data for evaluation of the mediated settlement conference program.
- 5) *Scheduling and Holding the Conference.* It is the duty of the mediator to schedule the conference and conduct it prior to the deadline of completion set by the rules. Deadlines for completion of the conference shall be strictly observed by the mediator unless said time limit is changed by a written order of the SCO or public owner.

RULE 6. COMPENSATION OF THE MEDIATOR

- A. **By Agreement.** When the mediator is stipulated by the parties, compensation shall be as agreed upon between the parties and the mediator provided that the provision of G.S. 143-128(g) are observed.
- B. **By Appointment.** When the mediator is appointed by the SCO or public owner, the parties shall compensate the mediator for mediation services at the rate in accordance with the rate charged for Superior Court mediation. The parties shall also pay to the mediator a one-time per case administrative rate in accordance with the rate charged for Superior Court mediation, which is due upon appointment.

RULE 7. MEDIATOR CERTIFICATION.

All mediators certified in the Formal Dispute Resolution Program shall be properly certified in accordance with the rules certifying mediators in Superior Court in North Carolina. * When selecting mediators, the parties may designate a preference for mediators with a background in construction law or public construction contracting. Such requirements, while preferred, are not mandatory under these rules.

All mediators chosen must either demonstrate they are certified in accordance with the Rules Implementing Scheduled Mediated Settlement Conference in Superior Court or must gain the consent of the SCO or public owner to mediate any dispute in accordance with these rules.

* Except when otherwise allowed by the SCO or public owner upon the request of the parties to the mediation.

RULE 8. RULE MAKING

These Rules are subject to amendment by rule making by the State Building Commission.

These Rules are mandated for State projects when the contracting state entity has not otherwise adopted its own dispute resolution provision. These rules are optional for all other projects subject to Article 8, Ch. 143 of the General Statutes.

RULE 9. DEFINITIONS

When the phrase "SCO or public owner" is used in these rules, "SCO" shall apply to state projects, "public owner" shall apply to non-state public projects.

RULE 10. TIME LIMITS

On state contracts, any time limit provided for by these Rules may be waived or extended by the SCO for good cause shown.

On non-state contracts, any time limit provided for by these Rules may be waived or extended by the mediator it appoints for good cause shown. If the mediator has not yet been appointed, the designer of record shall decide all waivers or extensions of time for good cause shown.

Exhibit A

DISPUTE RESOLUTION






Exhibit A

DISPUTE RESOLUTION

STATE PROJECTS



DISPUTE RESOLUTION



AS AMENDED BY STATE BUILDING
COMMISSION (PLACED IN THE SPECIFICATIONS OC-58)

MEDIATION

NON-BINDING OR BINDING
☒ ARBITRATION

LITIGATION

- DISPUTE RESOLUTION:

WORK CHANGE DIRECTIVE NO.: [Number of Work Change Directive]

Owner: **City of Raleigh**

Owner's Project No.:

Engineer:

Engineer's Project No.:

Contractor:

Contractor's Project No.:

Project: Neuse River RRF Roof Replacements,
Filter & Blower Buildings

Contract Name:

Date Issued:

Effective Date of Work Change Directive:

Contractor is directed to proceed promptly with the following change(s):

Description:

[Description of the change to the Work]

Attachments:

[List documents related to the change to the Work]

Purpose for the Work Change Directive:

[Describe the purpose for the change to the Work]

Directive to proceed promptly with the Work described herein, prior to agreeing to change in Contract Price and Contract Time, is issued due to:

Notes to User—Check one or both of the following

☐ Non-agreement on pricing of proposed change. ☐ Necessity to proceed for schedule or other reasons.

Estimated Change in Contract Price and Contract Times (non-binding, preliminary):

Contract Price: \$ _____ **[increase] [decrease] [not yet estimated].**

Contract Time: _____ days **[increase] [decrease] [not yet estimated].**

Basis of estimated change in Contract Price:

☐ Lump Sum ☐ Unit Price ☐ Cost of the Work ☐ Other

Recommended by Engineer

Authorized by Owner

By:

Title:

Date:

City of Raleigh

00940

Work Change Directive

EJCDC® C-940, Work Change Directive.

Copyright© 2018 National Society of Professional Engineers, American Council of Engineering Companies,
and American Society of Civil Engineers. All rights reserved.

CHANGE ORDER NO.: [Number of Change Order]

Owner: **City of Raleigh**

Owner's Project No.:

Engineer:

Engineer's Project No.:

Contractor:

Contractor's Project No.:

Project: Neuse River RRF Roof Replacements,
Filter & Blower Buildings

Contract Name:

Date Issued:

Effective Date of Change Order:

The Contract is modified as follows upon execution of this Change Order:

Description:

[Description of the change]

Attachments:

[List documents related to the change]

Change in Contract Price	Change in Contract Times
Original Contract Price: \$ _____	Original Contract Times: Substantial Completion: _____ Ready for final payment: _____
[Increase] [Decrease] from previously approved Change Orders No. 1 to No. [Number of previous Change Order] : \$ _____	[Increase] [Decrease] from previously approved Change Orders No.1 to No. [Number of previous Change Order] : Substantial Completion: _____ Ready for final payment: _____
Contract Price prior to this Change Order: \$ _____	Contract Times prior to this Change Order: Substantial Completion: _____ Ready for final payment: _____
[Increase] [Decrease] this Change Order: \$ _____	[Increase] [Decrease] this Change Order: Substantial Completion: _____ Ready for final payment: _____
Contract Price incorporating this Change Order: \$ _____	Contract Times with all approved Change Orders: Substantial Completion: _____ Ready for final payment: _____

Recommended by Engineer (if required)

Accepted by Contractor

By: _____

Title: _____

Date: _____

Authorized by Owner

Approved by Funding Agency (if applicable)

By: _____

Title: _____

Date: _____

City of Raleigh

00941

Change Order

EJCDC® C-941, Change Order EJCDC® C-941, Change Order, Rev.1.

Copyright© 2018 National Society of Professional Engineers, American Council of Engineering Companies
and American Society of Civil Engineers. All rights reserved.

Attachment 1 - Final Change Order:

The Owner and Contractor intend that this Final Change Order incorporate and resolve all prior, pending, and unresolved change order requests, claims, and/or disputes which have been submitted or which could have been submitted prior to the date of execution of this Final Change Order. This Final Change Order represents full and final settlement of all disputes or claims between the Parties to the Contract, and by executing this Final Change Order and in consideration of the modifications agreed to herein, Contractor expressly releases and waives all further claims for equitable adjustment; compensation in the form of money or time (days) for additional work, services, labor, or materials; damages for delay including but not limited to claims for additional overhead, lost productivity, ripple effect, cumulative impact, or acceleration; and any direct, indirect, or impacts costs including but not limited to any costs, losses, damages, charges, fees, expenses, interest, or attorneys' fees arising from or in connection with the Contract or this Final Change Order.

FIELD ORDER NO.: [Number of Field Order]

Owner: **City of Raleigh** Owner's Project No.:
Engineer: Engineer's Project No.:
Contractor: Contractor's Project No.:
Project: Neuse River RRF Roof Replacements,
Filter & Blower Buildings
Contract Name:
Date Issued: Effective Date of Field Order:

Contractor is hereby directed to promptly perform the Work described in this Field Order, issued in accordance with Paragraph 11.04 of the General Conditions, for minor changes in the Work without changes in Contract Price or Contract Times. If Contractor considers that a change in Contract Price or Contract Times is required, submit a Change Proposal before proceeding with this Work.

Reference:

Specification Section(s):

Drawing(s) / Details (s):

Description:

[Description of the change to the Work]

Attachments:

[List documents supporting change]

Issued by Engineer

By: _____
Title: _____
Date: _____

RRD Wastewater Environmental Management System Memorandum of Understanding

The Raleigh Water Resource Recovery Division (RRD) is committed to managing our treatment plant activities in a responsible and publicly acceptable manner. We consider you, our contractor, to be a partner and an extension of our activities. This document is intended to summarize what contractors can expect from RRD in meeting our partnership commitment and the performance we expect our contractors to maintain so that we can meet those commitments. Many (if not all) of the items in this document are already in place and well established. This document is intended to clearly define for all observers and interested parties that RRD holds its contractors to the standards intended to promote continual improvement. All items are included in the scope of the current contract and should not be seen as additional tasks.

Furthermore, our Environmental Policy Statement guides us in the decisions we make:

The Resource Recovery Division recognizes the responsibility to protect the environment and public health focusing on products for beneficial reuse by:

- **Meeting or exceeding compliance obligations**
- **Seeking continual improvement**
- **Promoting positive relations with interested parties**
- **Protecting the environment, including prevention of pollution**

Raleigh Water RRD Responsibilities

As a fundamental principle in our commitment to our partnership with you, RRD understands and accepts our responsibilities to:

- Perform our activities consistent with the Wastewater Environmental Management System (WEMS), ISO 14001:2015 American National Standards, and any contracted agreements with you.
- Provide treatment that meets agreed quality, quantity and timing requirements.
- Advise you of any planned or actual changes or other circumstances that may affect your activities, with as much notice as reasonably possible.
- Review your performance from time to time and advise you of any concerns and/or improvement opportunities to help us both continually improve our partnership.
- Consider your advice and suggestions for improving our performance.
- Help you in meeting the Contractor Performance Expectations set out below.

Contractor Responsibilities

Consistent with our commitment to the Wastewater Environmental Management System and ISO 14001:2015 American National Standards we expect contractors who perform activities on our behalf to:

1. Have practices in place for compliance with all federal, state and local laws and requirements that apply to wastewater, reuse, and biosolids activities you do on our behalf. To meet this expectation, contractors should:
 - 1.1. Be aware of and take steps to ensure compliance with all applicable federal, state and local laws. Contractors can seek assistance from RRD in doing this.

- 1.2. Advise RRD of any noncompliance identified by regulatory agencies or others, including DOT, OSHA or EPA notices of violation, with plans to correct the noncompliance and prevent its recurrence.
2. Control operations and activities performed on behalf of RRD. To meet this expectation, contractors should:
 - 2.1. Maintain environmentally acceptable management practices and operations.
 - 2.2. Establish operational controls, including appropriate operating and maintenance procedures, for their activities performed on behalf of RRD.
 - 2.3. Follow RRD instructions for transporting, storing and using our biosolids or reuse, including but not limited to the transportation DOP developed by the RRD EMS team.
 - 2.4. Maintain good housekeeping practices in operations related to plant activities.
 - 2.5. Have a plan for emergencies involving plant equipment, reuse, and biosolids that has been reviewed and approved by RRD, which should include the jointly developed spill response plan.
 - 2.6. Ensure your personnel and/or subcontractors are competent on the basis of appropriate education, experience and/or training.
3. Communicate effectively with RRD and with interested parties about plant activities. To meet this expectation, contractors should:
 - 3.1. Have effective methods for communication with RRD and with interested citizens regarding plant activities.
 - 3.2. Communicate with users about the proper use of biosolids or reuse, including ensuring fact sheets and brochures are available.
 - 3.3. Refer requests or complaints from the public and interested parties about plant operations, reuse, or biosolids to RRD and advise us of any such requests/complaints.
 - 3.4. Meet regulatory reporting requirements.
 - 3.5. Communicate with RRD in a timely manner on any matter under your control that could affect our treatment plant, reuse, or biosolids programs.
4. Maintain pertinent documents and records. To meet this expectation, contractors should:
 - 4.1. Have copies of all permits and regulations that apply to your activities accessible.
 - 4.2. Develop and maintain appropriate documents that describe your activities to be performed on our behalf and requests for activities that you expect RRD to perform on your behalf.
 - 4.3. Maintain appropriate records to demonstrate work performed on our behalf.
5. RRD expects our contractors to work to continually improve their activities. To meet this expectation, contractors should:
 - 5.1. Seek continuous improvement in all aspects of work that the contractor performs.
 - 5.2. Allow designated RRD personnel to assess your performance on our behalf from time to time, including access to your site and records (audits).
 - 5.3. Develop corrective action plans with RRD to prevent the recurrence of any noncompliances or nonconformances identified by regulatory agencies or during RRD inspections.
 - 5.4. Meet with RRD periodically to discuss opportunities to improve our partnership and our respective activities. RRD will assist you in identifying improvement opportunities.



By signature below both RRD and the designated contractor indicate they understand the above performance expectations and agree to work together in performing activities for our mutual best interests.

Contractor Name / Address:

Signed By:

Contractor Representative

Date:

Raleigh Water RRD Representative

Date:

This page intentionally left blank.

SECTION 01 11 00
SUMMARY OF WORK

PART 1 GENERAL

1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. Work described in this Project Manual includes the provision of labor, materials, equipment, and services required to complete the Neuse River RRF Roof Replacements, Filter & Blower Buildings for the City of Raleigh, North Carolina.

1.02 CONTRACT DESCRIPTION

- A. The description of work, which follows, is not all inclusive in listing the work. The description is abbreviated to provide a summary of the scope of the project to aid in the understanding and coordination. The Contractor shall refer to the applicable sections of these specifications for detailed description of the work involved and also refer to the contract drawings for the division of work indicated thereon.

At the NRRRF Blower Building & Filter Building #1:

- Removal of existing curbs and roofing materials
- Installation of new roofing materials
- Removal and reinstallation of lightning protection features
- Misc. work

1.03 WORK SEQUENCE

- A. Construction activities that interfere with normal operation of existing facilities shall be specifically noted on construction schedule.
- B. Indicate switchovers and cut-ins between new Work and existing facility on the construction schedule. Submit proposed date for switchover in writing to Engineer and Owner a minimum of seven (7) days and again 24-hours in advance of actual field work. Owner shall have the right to delay Work due to operational requirements, without additional cost to Owner.
- C. The sequence of construction shall be in accordance with instructions included on the Drawings.

1.04 OWNER OCCUPANCY

- A. Owner will occupy site during entire period of construction.
- B. Contractors shall cooperate with Owner to minimize conflict, and to facilitate Owner's operations.

1.05 VIDEO AND PHOTOGRAPHIC INSPECTIONS

- A. Conduct video and photographic inspection of the pre-construction conditions and post-construction conditions for the entire project area, including off site material staging areas and other associated locations.
- B. Post-construction videos and photographs documenting areas/phases that have achieved milestones, substantial completion, and final completion.
- C. Submittal shall be in accordance with Section 01 33 00, Submittal Procedures.

1.06 CONTRACTOR USE OF SITE

- A. Only Owner's right to perform construction and maintenance operations with its own forces and to employ separate contractors on portions of the Project limits contractor's use of site during the construction period. Work at the Project site by Owner will be coordinated with the Contractor.
- B. Contractor shall provide his own staging area as necessary for his Work. Contractor is required to modify the appropriate permits or obtain new permit for additional area at the Contractor's expense.
- C. Contractor's use of the site during the construction period may be limited by Owner's necessity to operate the existing facilities.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 31 19
PROJECT MEETINGS

PART 1 GENERAL

1.01 MEETINGS

- A. Pre-construction conference shall be held prior to the beginning of the Work.
- B. Construction progress meetings shall be held monthly.
- C. Project close-out conference shall be held during the final phases of the Work.
- D. Engineer may schedule additional meetings.
- E. Meetings scheduled by the Engineer shall be held at the City of Raleigh Public Utilities Department or at the project site as set forth in the Pre-construction meeting.
- F. Contractor's project superintendent shall attend meetings.
- G. Notify suppliers and subcontractors to attend meetings as appropriate or as required by Engineer.
- H. Contractor shall schedule pre-installation conferences and material testing meetings as required in the individual specification sections.
- I. Notify Engineer of project meetings scheduled by the Contractor.
- J. Engineer will schedule and administer meetings throughout the progress of the Work, except for meetings held by the Contractor for normal coordination of the Work.
- K. Meeting agenda shall include, but not be limited to, the following: Project Administration, Submittals, Construction Schedules and Methods, Safety and Health Regulations, Project Coordination, Payment Application, RFI's, Field Orders, Change Orders, and Site Inspections.
- L. Engineer will prepare agenda with copies to participants, preside at meetings, prepare minutes and distribute to participants for meetings scheduled by the Engineer.
- M. Engineer will prepare sign-in sheet and obtain signatures, e-mail addresses, and phone numbers from each attendee for distribution with the meeting minutes.

1.02 RELATED SECTIONS

- A. The following Sections have work that is directly related to this Section. This does not relieve the Contractor of his responsibility of proper coordination of all the work:
 - 1. Section 01 35 13 Specific Project Requirements

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 33 00
SUBMITTAL PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. This Section includes, but is not limited to, requirements for the following:
 - 1. Submittal procedures.
 - 2. Construction progress schedule.
 - 3. Schedule of values.
 - 4. Video and photographic Inspection.
 - 5. Project record documents.
 - 6. Certificates of compliance.
 - 7. Catalog data.
 - 8. Shop drawings.
 - 9. Manufacturer's installation procedures.
 - 10. Samples.
 - 11. Warranties.

1.02 SUBMITTAL PROCEDURES

- A. Provide a PDF electronic copy of each submittal to the Owner's project manager. The electronic copy shall not exceed a file size of 5 MB unless otherwise approved by the Owner in advanced.
- B. Number transmittals sequentially beginning with 1. Resubmitted items should retain the original number but with an added suffix letter starting with "A".
- C. Each submittal shall include a transmittal form.
- D. Submittal cover sheet shall include the following information:
 - 1. Contractor's name:
 - 2. Owner's name: Raleigh Water
 - 3. Project name:
 - 4. Engineer's Job No.:
 - 5. Submittal reference number no.
 - 6. Specification section number.
 - 7. Drawing and detail number, when appropriate.
 - 8. Equipment or Item Description.
 - 9. Supplier.
 - 10. Manufacturer.
 - 11. Contractor Approval Stamp.
 - 12. Exceptions taken to Project Documents.
- E. Apply Contractor's stamp to each submittal, signed or initialed and dated, certifying that Contractor has reviewed submittal for conformance with requirements of the Contract Documents, and has coordinated submittal with related work.
- F. Schedule submittals to expedite the project and deliver to coordinate submission of related items. Allow a minimum of fifteen (15) working days for Owner/Engineer's review.
- G. Clearly identify variations from Contract Documents and Product limitations, as they relate to the satisfactory performance of the Project.
- H. Provide space for Contractor and Engineer review stamps.

- I. Revise and resubmit submittals electronically as required; identify changes made since previous submittal.
- J. Distribute PDF electronic copies of reviewed submittals to concerned parties. Instruct parties to promptly report inability to comply with provisions.
- K. Do not fabricate products or begin Work for which submittals are required until approved submittals have been received from Engineer.
- L. Engineer's review of submittals shall not relieve Contractor of responsibility for complete compliance with Contract Documents.

1.03 ADMINISTRATIVE SUBMITTALS

A. Construction Progress Schedule

- 1. Submit an electronic copy of the initial progress schedule 15 days after date of Owner-Contractor Agreement.
- 2. Progress schedule shall be, as a minimum, a horizontal bar chart with a separate line for each major section of Work. Identify the first work day of each week.
- 3. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the early and late start, early and late finish, float dates, and duration.
- 4. Indicate the expected anticipated monthly partial payment requests amounts for the duration of the project.
- 5. Submit revised schedule with each Application for Payment, as required for updating, identifying changes since previous version. Indicate estimated percentage of completion for each item of Work at each submission.
- 6. Indicate submittal dates required for critical shop drawings, product data, samples, and product delivery dates
- 7. Indicate specific work sequences and requirements as indicated in Section 01 11 00, Summary of Work.

B. Schedule of Values (lump sum contracts only)

- 1. Submit an electronic copy the schedule of values at least three (3) weeks prior to the first partial payment request. Schedule shall divide the lump sum contract items into major work tasks. Use the table of contents as a guide for itemizing the schedule. Schedule will be used only as a basis for review of the Contractor's request for payment.
- 2. Engineer may request additional delineation of work tasks and supporting data of the values, as he deems appropriate. Revise schedule and resubmit.
- 3. Revise schedule to list approved Change Orders, with each request for payment.

C. Video and Photographic Inspection

- 1. Submit two (2) copies of all video and photographic inspection. Pre-construction inspections shall be submitted prior to beginning work and post-construction inspections shall be submitted upon completion of milestones, substantial completion, and final completion as applicable.

D. Project Record Documents

- 1. Maintain on site, one set of the following record documents; record actual revisions to the Work:
 - a. Contract Drawings.
 - b. Project Manual.
 - c. Addenda.
 - d. Change Orders and other Modifications to the Contract.
 - e. Reviewed submittals.

2. Store Record Documents separate from documents used for construction.
3. Record information concurrent with construction progress.
4. Specifications: Legibly mark and record at each Product section description of actual Products installed, including the following:
 - a. Manufacturer's name and product model and number.
 - b. Product substitutions or alternates utilized.
 - c. Changes made by Addenda and Modifications.
5. Record Documents and Shop Drawings: Legibly mark each item to record actual construction including:
 - a. Measure elevations of structures in relation to bench mark datum.
 - b. Measure and reference horizontal and vertical locations of underground utilities and appurtenances to existing permanent surface improvements that are indicated on the Drawings.
 - 1) Provide top, invert, diameter and depth information on manholes.
 - c. Indicate on construction Drawings the pipe size, pipe material (including pipe class and coatings) and pipe length.
 - d. Field changes from construction Drawings.
 - e. Details not on original Contract Drawings.
 - f. Data on all utilities in the trench zone.
 - 1) Document infrastructure abandonment items.
 - 2) Include rock profile
6. Submit complete set of documents to City with final Application for Payment.
 - a. Partial set(s) documenting completed and in services phases shall be submitted with the first application of partial payment following start-up.

1.04 TECHNICAL SUBMITTALS

A. General

1. Submit the following as required by the individual sections of the technical specifications.

B. Certificates of Compliance

1. Certificates shall certify that the Products delivered to the project are in conformance with the specifications.
2. Certificates may be recent or previous test results on Product, but must be acceptable to Engineer.
3. Certification shall not relieve the Contractor of responsibility for complying with requirements of the specifications.

C. Catalog Data

1. When shop drawings are not required, the catalog data shall include the following as a minimum:
 - a. Parts schedule that identifies the materials to be used in each of the various parts.
 - b. Sufficient detail to serve as a guide for assembly and disassembly of the product and to serve as guide for ordering parts.
2. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information unique to this Work in the Shop Drawing submittal.

D. Shop Drawing

1. Shop drawings shall consist of drawings, diagrams, illustrations, schedules, performance charts, brochures and other data, prepared specifically for a portion of the Work.

2. Shop drawings shall indicate the type, size, quantity, arrangement, location, mode of operation, component materials, utility connections, wiring and control diagrams, anchorage's, supports, factory applied coatings, and other information necessary to ensure satisfactory fabrication, installation and operation of the completed Work.
 3. Shop drawings shall establish the actual detail of manufactured or fabricated items, indicate proper relation to adjoining work, amplify design details of mechanical and electrical equipment in proper relation to physical spaces in the structure, and incorporate minor changes to design and construction to suit actual requirements.
- E. Manufacturer's Installation Procedures
1. Installation procedures should indicate manufacturer's recommendations for proper installation of Product.
- F. Samples
1. Submit samples as required by the individual specification sections. Samples shall be physical examples to illustrate the materials and workmanship. Submit in sufficient size and quantity to clearly illustrate the functional characteristics of the Product, with integrally related parts and attachment devices, and the full range of color to be provided.
- G. Warranties
1. Provide duplicate notarized copies.
 2. Assemble documents from Subcontractors, suppliers, and manufacturers.
 3. Provide Table of Contents and assemble in three D side ring binder with durable plastic cover.
 4. Submit prior to final Application for Payment.
 5. For items of Work delayed beyond date of Substantial Completion, provide updated submittal within 10 days after acceptance, listing date of acceptance as start of warranty period.
 6. The warranty period for all new equipment shall commence the date of substantial completion, as specified by the City, and shall extend for a period of twelve (12) months.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 35 43.13
ENVIRONMENTAL PROCEDURES FOR HAZARDOUS MATERIALS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. General responsibilities and enforcement concerning Constituents of Concern at the Site.
2. Notifying Owner of Constituents of Concern at the Site.
3. Hazard communication plan.
4. Emergency/spill response plan.
5. Storage of materials containing Constituents of Concern and storage of non-hazardous materials.
6. Area for storing materials containing Constituent(s) of Concern.
7. Verification of compliance.

B. Scope:

1. Contractor shall provide all labor, materials, equipment, tools, services, and incidentals necessary and required to comply with requirements of this Section and related provisions of the General Conditions, as may be modified by the Supplementary Conditions.
2. In this Section's title, "hazardous materials" means "Constituents of Concern" as defined in the General Conditions.

1.2 BASIC RESPONSIBILITIES AND ENFORCEMENT REGARDING CONSTITUENTS OF CONCERN AT THE SITE

A. Scope – Basic Responsibilities:

1. Contractor shall develop, implement, and maintain throughout the Project a hazardous materials management program (HMMP) in accordance with Laws and Regulations and the Contract Documents.
2. Constituents of Concern Brought to Site by Contractor:
 - a. Transport, handle, store, label, use, and dispose of materials containing Constituents of Concern in accordance with this Section, other applicable provisions of the Contract Documents, and Laws and Regulations.
3. Constituents of Concern Generated by Contractor:
 - a. Materials containing Constituents of Concern shall be properly handled, stored, labeled, transported and disposed of by Contractor in accordance with Laws and Regulations, and this Section.
 - b. If Contractor will generate or has generated materials containing Constituents of Concern at the Site or adjacent areas, obtain a USEPA identification number listing Contractor's name and address of the Site as generator of the Constituents of Concern. Obtain identification number from state environmental agency or other authority having jurisdiction at the Site. Submit identification number within time limit indicated in this Section's "Submittals" Article.
 - c. Contractor is responsible for identifying, analyzing, characterizing, labeling, storing, transporting, and disposing of Constituents of Concern generated by Contractor.
4. Cost Responsibility:
 - a. Fines and civil penalties imposed on Owner or facility manager (if other than Owner) for Contractor's violations, whether at the Site or other locations, and other costs incurred by Owner and facility manager associated with cleanup of a Hazardous Environmental Condition created or exacerbated by Contractor shall be paid by Contractor.

- b. If Contractor has exacerbated a Hazardous Environmental Condition existing at the Site prior to the start of the Work, Contractor shall pay Contractor's appropriate share of costs associated with fines, civil penalties, and cleanup costs in proportion equal to the extent of costs for which Contractor caused or exacerbated the Hazardous Environmental Condition and fines and civil penalties associated therewith.
 - c. If Contractor fails or refuses to pay such costs, Owner may pay the costs and deduct from payments due Contractor a reasonable set-off.
- B. Owner's Environmental Representative:
 1. Owner's environmental representative is: Dan Williams
Resource Recovery Engineer
City of Raleigh, Raleigh Water
8550 Battle Bridge Road, Raleigh, NC 27610
dan.williams@raleighnc.gov
919-996-3473
- C. Enforcement of Laws and Regulations Regarding Constituents of Concern and Hazardous Environmental Conditions:
 1. To extent practicable, avoid creating or exacerbating situations causing or contributing to injury to persons, spills and emissions of Constituents of Concern, contamination of the Site and other areas, and damage (to property and the environment) caused by Hazardous Environmental Conditions.
 2. When Owner or facility manager (if other than Owner) is aware of or suspects violations may have occurred or may occur, Owner or facility manager will notify Contractor, and authorities having jurisdiction, when Owner or facility manager reasonably believes doing so is necessary or appropriate. However, no such right of Owner, facility manager, or any entity for whom Owner or facility manager is responsible, including Engineer (or its consultants and subcontractors), is for benefit of Contractor. Owner, facility manager, and any entity for whom Owner or facility manager is responsible, including Engineer, are not obligated to monitor presence of, use of, storage or handling of, Constituents of Concern at the Site or other areas, or present of a potential Hazardous Environmental Condition, or to act on behalf of Contractor or anyone for whom Contractor is responsible.
 3. Responsibilities regarding Laws and Regulations shall be in accordance with the General Conditions, as may be modified by the Supplementary Conditions.

1.3 SUBMITTALS

- A. Informational Submittals: Submit the following to the entity(ies) indicated for each:
 1. Indication of Constituents of Concern (including Chemicals) Proposed for Use at the Site:
 - a. Submit to Owner's environmental representative; do not submit to Engineer. Engineer will not accept, review, or retain such information or Submittals in Engineer's files.
 - b. Submit the information required in sufficient time for Owner's review and acceptance not later than three days before bringing associated Constituent of Concern to the Site.
 - c. Submittal Content:
 - 1) Current (dated within the past two years) safety data sheets (SDS, formerly "material safety data sheets") in accordance with 29 CFR 1910.1200 (OSHA Hazard Communication Standard).
 - 2) Manufacturer of material or equipment containing such substance.
 - 3) Supplier (if other than manufacturer).
 - 4) Container sizes and number of containers proposed to be at the Site.
 - 5) Minimum and maximum volume of material intended to be stored at the Site.

- 6) Description of process or procedures in which Constituent(s) of Concern will be used at the Site.
2. Other Documents Required for the HMMP:
 - a. Submit to Owner's environmental representative; do not submit to Engineer. Engineer will not accept, review, or retain such information or Submittals in Engineer's files.
 - b. Submit requested documents within 72 hours of Contractor's receipt of such request.
 - c. Submittal Content:
 - 1) Submit requested HMMP documents, which may include emergency/spill response plan, communication plan, and other documents.

1.4 HAZARDOUS MATERIALS MANAGEMENT

- A. Obtain Owner's environmental representative's acceptance before bringing to the Site each material containing a Constituent of Concern.
- B. Hazard Communication Plan:
 1. Develop and implement a communication plan relative to materials containing one or more Constituents of Concern.
 2. Safety Data Sheet (SDS) Notebooks:
 - a. Maintain at the Site not less than two notebooks containing:
 - 1) Inventory of materials containing a Constituent of Concern (including all chemicals).
 - 2) Current (dated within the past two years) SDS for all materials being used to accomplish the Work, whether or not defined as a Constituent of Concern.
 - b. Keep one notebook in Contractor's field office at the Site; keep second notebook at location acceptable to Owner's environmental representative.
 - c. Keep notebooks up-to-date as materials are brought to and removed from the Site.
- C. Emergency/Spill Response Plans:
 1. Develop, implement, and maintain an emergency/spill response plan, for each Constituent of Concern or each class or group of material containing a Constituent(s) of Concern, as applicable.
 2. Response plan shall include not less than the following:
 - a. Description of materials and equipment available at the Site to contain or respond to emergencies related to or spills of the materials containing one or more Constituents of Concern.
 - b. Procedures for notifying, and contact information for:
 - 1) Authorities having jurisdiction.
 - 2) Emergency responders.
 - 3) Owner.
 - 4) Engineer.
 - 5) Resident Project Representative (RPR) and Owner's Site Representative (OSR).
 - 6) Other entities as necessary or required.
 - c. Response coordination procedures between Contractor, Owner or facility manager (if other than Owner), and others as appropriate.
 - d. Description of Constituent of Concern handling and emergency/spill response training provided to Contractor's and Subcontractors' workers, in accordance with 29 CFR 1926.21(b) ("Employer Responsibility") and other Laws and Regulations.
- D. Storage of Materials Containing Constituents of Concern and Storage of Non-Hazardous Materials:
 1. Vessels containing materials with a Constituent of Concern shall bear applicable, clearly visible NFPA hazard diamonds.

2. Container Labeling:
 - a. Properly label each container of combustible materials, whether or not classified as containing a Constituent of Concern.
 - b. Each container shall have securely-attached label clearly identifying contents. Also label containers that are filled from larger containers.
 - c. If Owner or facility manager (if other than Owner) becomes aware of unlabeled containers at the Site, Owner's environmental representative will so advise Contractor, although Owner's and facility manager's personnel are not obligated to do so. Properly label each container within one hour of receipt of such notice from Owner or facility manager or remove container from the Site and adjacent areas.
 - d. Properly dispose of materials containing Constituents of Concern, in accordance with Laws and Regulations, at a location other than the Site and adjacent areas.
 3. To greatest extent possible, store at offsite location materials containing a Constituent of Concern until required for use in the Work.
- E. Area for Storing Materials Containing Constituent(s) of Concern:
1. Maintain designated storage area for materials containing one or more Constituents of Concern. Storage area shall include secondary containment to prevent release of spilled or leaking substances. Storage area shall include protection from environmental effects such as elements, temperature, sunlight, and other environmental effects.
 2. Provide signage in accordance with Laws and Regulations, clearly identifying the storage area.

PART 2 - PRODUCTS - (NOT USED)

PART 3 - EXECUTION - (NOT USED)

END OF SECTION

SECTION 01 41 50

HEALTH AND SAFETY REQUIREMENTS

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This Section includes requirements for health and safety during performance of work, including identification of applicable regulations, submittals, notification requirements, and health and safety execution specifications.

1.2 REFERENCES

- A. Applicable regulations and publications include, but are not limited to, the following:
1. Occupational Safety and Health Administration (OSHA), Title 29 CFR Part 1910, Occupational Safety and Health Standards, and Title 29 CFR Part 1926, Safety and Health Regulations for Construction Sites.
 2. National Fire Protection Association (NFPA), Flammable and Combustible Liquids Code, NFPA 30, most recent revision.
 3. United States Environmental Protection Agency (USEPA), Standard Operating Safety Guidelines, November 1984.
 4. Department of Health and Human Services (DHHS), "Manual of Analytical Methods", 3rd edition Volumes I and II, DHHS (National Institute for Occupational Safety and Health (NIOSH) Publication 84-100.
 5. American National Standards Institute (ANSI), Practices for Respiratory Protection, Z88.2, most recent version.
 6. ANSI, Emergency Eyewash and Shower Equipment, Z358.1, 1981.
 7. ANSI, Protective Footwear, Z41.1, 1983.
 8. ANSI, Respirator Use Physical Qualification for Personnel, Z88.6, 1984.
 9. ANSI, Practice for Occupational and Educational Eye and Face Protection, Z87.1, 1979.
 10. NIOSH/OSHA/ United States Coast Guard (USCG)/USEPA, Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities, DHHS/ Public Health Service (PHS)/ Centers for Disease Control (CDC)/NIOSH, October 1985.
 11. NIOSH Pocket Guide to Chemical Hazards, DHHS/PHS/CDC/NIOSH, June 2000 or most recent.
 12. USEPA, Health and Safety Requirements for Personnel Engaged in Field Activities, USEPA Order No. 14402.
 13. Department of Transportation (DOT) Standards and Regulations, 49 CFR 171 and 49 CFR 172.
 14. American Conference of Governmental Industrial Hygienists (ACGIH), Threshold Limit Values and Biological Exposure Indices (most recent version).
 15. Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air, Environmental Protection Agency (EPA)/600/4-87-006, September 1986.
- B. Where two or more regulations/documents conflict, the one(s) offering the greatest degree of protection shall apply.

1.3 CONTRACTOR'S RESPONSIBILITY FOR HEALTH AND SAFETY

- A. Contractor shall comply with any and all state, federal, and local ordinances and Regulations.
- B. Contractor shall be responsible for the Health and Safety of Contractor's employees, its Subcontractors, suppliers, agents, inspectors, visitors, the general public, and any others associated with or interacting with Contractor who provides labor, goods, or other services on the Site.

- C. Contractor shall be responsible for emergency response planning and notification, and for actual response to any and all emergencies that may occur during the course of the Work, including emergencies that may occur when Contractor is not present at the Site.
- D. Contractor is responsible for communicating daily with the Construction Manager regarding Health and Safety issues for the Construction Manager's safe conduct of the Construction Manager's duties, but such communication shall not imply any duty or responsibility on the part of the Construction Manager with regard to Health and Safety of Contractor's employees, its Subcontractors, suppliers, the general public, or Others. The Construction Manager's responsibility and duty with regard to Health and Safety shall be limited to the Construction Manager's employees. Contractor shall have responsibility and duty to the Construction Manager to communicate Health and Safety issues accurately and in a timely manner to allow the Construction Manager to take appropriate actions to protect the Construction Manager's employees.
- E. The SSHO shall enforce the requirements of safety for all Contractor personnel on site at all times. The SSHO shall ensure that all Contractor personnel, Subcontractor personnel, and Contractor visitors, follow the Health and Safety Plan (HASP), including wearing the designated level of personal protective equipment (PPE). If the SSHO elects to require a higher level of protection than that specified in the HASP, the extra costs associated with such higher level shall be borne by Contractor, unless such extra costs are approved in advance in writing by the Construction Manager.
- F. Prior to mobilization and continually through the duration of the Work, the SSHO shall inspect the Site and document area-specific and worker-specific protection requirements.
- G. After mobilization, the SSHO shall monitor activities and shall document the need for additional worker protection as required, based on activities performed and Action Levels specified in the HASP.
- H. The SSHO shall, on a daily basis, verify that all activities are performed in accordance with the HASP and all federal, state, local, and Health and Safety standards, regulations, and guidelines.
- I. In the event of a health or safety risk, as determined by the SSHO or by other Contractor personnel or by the Construction Manager, Contractor shall not proceed with the Work until a method for handling the risk has been determined in consultation with the Construction Manager and implemented. Any health or safety risk resulting in a stoppage of Work shall be reported immediately to the Construction Manager.
- J. Contractor shall be responsible for providing site training, observation, and feedback for Contractor personnel employed at the Site.

1.4 SUBMITTALS

- A. The Contractor shall prepare and submit a Health and Safety Plan (HASP) for review and approval, as part of its startup. The Contractor will not be able to perform any work on the Project until the HASP is approved.
- B. The Contractor shall follow all applicable local, State, and Federal Health and Safety standards, regulations, and guidelines implemented through, but not limited to, the OSHA, NIOSH, ACGIH, and USEPA. Where these are in conflict, the most stringent requirement shall be followed. The following points shall be addressed in the Contractor's HASP:
 - 1. Names of key personnel and alternates responsible for Health and Safety, including a Contractor Health and Safety Representative and SSHO.
 - 2. A Health and Safety risk or Job Safety and Hazard Analysis (JSHA) associated with each portion of the Work (i.e., list potential chemical and physical hazards), including JSAs for excavation work around active utilities, excavation safety, and truck traffic into and out of the Site.
 - 3. Personal protective equipment (PPE) to be used for each of the site tasks and operations being conducted, as required by the PPE program in 29 CFR 1926.
 - 4. Measures to prevent the spread of COVID-19.

5. Site control measures in accordance with the control program required in 29 CFR 1926.
 6. An emergency response plan meeting federal, state, and local requirements for safe and effective responses to emergencies, including the necessary PPE and other equipment must be incorporated into the HASP. Explanation of potential emergencies and contingency plan of action, including description of the route to the nearest appropriate hospital, hospital route map, and posting of emergency telephone numbers at the Site.
 7. A spill containment program meeting the requirements of all applicable local, state, and federal Health and Safety standards.
 8. A list of Health and Safety and emergency equipment available on the Site.
 9. A description of engineering controls used to reduce the hazards of equipment operation and exposure to site hazardous chemicals.
 10. Training for emergency response procedures, Heat stress program consistent with the references, Cold stress program consistent with the references, Lockout/Tagout where the operation of machinery and/or equipment in which the unexpected energization on start up or the release of stored energy could cause injury to personnel.
- C. Contractor's Daily Construction Report shall include a summary of daily safety issues and a summary of Contractor's Daily Safety Meeting.
 - D. Contractor shall maintain all required and applicable training and medical monitoring rerecords on-site.
 - E. Contractor shall conduct a JSHA for significant activities and submit the documentation to the Construction Manager for review prior to the start of the activities. Contractor's JSHA shall be submitted on the JSHA forms attached to this Section, or other form acceptable to the Construction Manager.

1.5 NOTIFICATIONS

- A. Contractor shall immediately (within 30 minutes) verbally report to the Construction Manager the occurrence of any and all Health and Safety incidents. An Incident Report form or Near-Miss Report form, as appropriate, attached to this Section, shall be submitted within 24 hours of occurrence of the incident or issue.
- B. Contractor shall immediately and fully investigate any such incident or near miss and conduct a root cause analysis, and shall submit to the Construction Manager, the Contractor's written corrective action plan for such incident within one day after the incident occurs.
- C. Contractor shall notify the Construction Manager in writing at least five (5) days prior to bringing any hazardous material, equipment, or process to the Site, or using the same on the Site. Contractor shall provide the Construction Manager with a Safety Data Sheet (SDS) for all chemicals brought on to the Site.
- D. Contractor shall immediately notify the Construction Manager in writing of any hazard that Contractor discovers or observes on the Site and corrective measures planned or taken to eliminate or minimize such hazard. Hazard reporting will be completed as a Near Miss Report as described in of this Section.

PART 2 - PRODUCTS

2.1 EQUIPMENT AND FACILITIES

- A. Contractor shall provide all equipment, temporary facilities, and personnel required to perform activities on site safely in accordance with all Regulations and standards, and with the Contractor's HASP.

2.2 PERSONAL PROTECTIVE EQUIPMENT

- A. The appropriate level of PPE shall be determined by the Contractor for specific tasks as described in the Contractor's HASP. Contractor shall determine and document the

appropriateness of suggested minimum PPE requirements for Contractor's employees and others at the Site.

- B. Contractor shall furnish and maintain materials and equipment for the Health and Safety of Contractor employees, its subcontractors, suppliers, the Construction Manager, and visitor personnel. Contractor shall provide all required Health and Safety equipment, first aid equipment, tools, monitoring equipment, PPE, and ancillary equipment and methods required to ensure workers' Health and Safety and to comply with the Contractor's HASP.
- C. Modified Level D protection will be required at all times while on site by all personnel and visitors on the Site, except in Support Zone areas. Level D PPE consists of:
 - 1. Hard hat.
 - 2. Safety-toed boots (chemical resistant).
 - 3. Safety glasses with permanent side shields.
 - 4. Work clothes (long pants, shirts with sleeves).
 - 5. Work gloves.
 - 6. High visibility reflective safety vests.
 - 7. Hearing protection (as needed to prevent exposure exceeding 85 dB level).
- D. If additional protection consisting of Level C PPE is required during the Work, Level C PPE shall include protection from organic compounds and consist of Level D protection with the following additions:
 - 1. Air purifying respirator, half-face or full-face (depending on required protection factor) with organic vapor/High Efficiency Particulate Air cartridges meeting NIOSH/Mine Safety and Health Administration Specifications.
 - 2. Disposable poly-coated chemically protective coveralls.
 - 3. Disposable chemically resistant outer gloves (nitrile).
 - 4. Disposable chemically resistant inner gloves (nitrile).
 - 5. Chemically resistant, steel-toed, and steel-shanked boots (PVC, neoprene, or nitrile), or outer booties.

2.3 OTHER HEALTH AND SAFETY EQUIPMENT

- A. Contractor is required to have the following equipment available on the Site for the Health and Safety of Contractor, subcontractors, suppliers, the Construction Manager, and visitors:
 - 1. First aid kits.
 - 2. Fire suppression equipment (appropriate to location and type of flammable materials present).
 - 3. OSHA-approved emergency eyewash facilities.
 - 4. Personnel decontamination facilities and equipment.
 - 5. Other equipment or supplies as determined to be necessary or prudent by Contractor or the Construction Manager.
 - 6. Flammable liquids storage cabinet, if necessary.
 - 7. Fall protection equipment.
 - 8. Heavy Blankets.

PART 3 - EXECUTION

3.1 TRAINING

- A. Contractor shall provide the following training to each worker except those who will be restricted to the Support Zone:
 - 1. If highly impacted or hazardous material is encountered, each Contractor worker scheduled to work in or with regulated material as specified in OSHA 29 CFR 1910:

- a. Initial 40-hour (or 80-hour where appropriate) OSHA hazardous waste Health and Safety training and current annual 8-hour refresher training.
 - b. Eight-hour OSHA hazardous waste supervisory training (required for the Contractor's Superintendent and SSHO).
 - c. Enrollment in a medical monitoring program, with clearance within the previous 12 months from a licensed physician allowing the worker to participate in field activities and use respiratory protective equipment. Contractor shall not submit detailed medical information for employees.
 - d. Current respiratory fit testing certification.
2. Current cardiopulmonary resuscitation (CPR) and first aid certification for at least two workers assigned to Work on the Site.
 3. For one who is assigned the role of a "competent person," documentation of sufficient and relevant training and experience to perform the assigned duties and responsibilities of that role. As defined in 29 CFR 1926.31, the competent person shall be "one who is capable of identifying existing and predictable hazards, and who has authority to take prompt corrective measures to eliminate them." Relevant training and experience shall be in the same type of Project activities included in the Work under this Contract.

3.2 WORK PLANNING AND MEETINGS

- A. Contractor shall conduct a daily Health and Safety meeting, prior to beginning Work for that day, to address Health and Safety issues, changing site conditions, activities and personnel. All Contractor and Subcontractor employees working on the site on that day shall attend the meeting. All meetings shall be documented, and attendees shall sign acknowledgement of their presence at the meeting.
- B. Subcontractor personnel who are not in attendance for the daily Health and Safety meeting shall be briefed on the meeting notes upon arrival at the site and prior to commencing their Work activities. Employees shall sign acknowledgement of briefings prior to commencing Work.
- C. Contractor shall hold and document additional safety meetings at the start of each major task and whenever site conditions affecting personnel safety change. Any major task undertaken shall require the completion of a JSHA as described in Paragraph 1.05.H of this Section.

3.3 ENGINEERING CONTROLS

- A. Contractor shall, at a minimum, provide the following engineering controls to reduce the hazards of equipment operation and exposure to site hazardous chemicals:
 1. Back-up alarms for all trucks and moving equipment.
- B. Contractor shall post ground level warning signs every 50 feet below all overhead utilities on site.

3.4 MONITORING

- A. Contractor shall perform heat exposure and cold exposure monitoring activities as required by weather conditions.

3.5 EVALUATION OF PERFORMANCE

- A. Contractor shall routinely conduct internal safety audits on Subcontract and Sub-subcontract Work sites in accordance with the Contractor's HASP. The focus of these routine audits will be on compliance with OSHA and local occupational safety regulations.
- B. Contractor shall conduct routine behavioral observations and provide immediate feedback during Work activities to promote safe behavior of Contractor employees and Subcontractor employees. Contractor behavioral observation and feedback sampling will be conducted in accordance with the Contractor's BEST observation and feedback process which is attached at the end of this Section.

END OF SECTION

This page intentionally left blank.

SECTION 01 50 00
TEMPORARY FACILITIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Temporary Utilities: Electricity, lighting, water, and sanitary facilities.
- B. Traffic control.
- C. Temporary Controls: Barriers, enclosures and fencing, water control, dust control, erosion and sediment control, and protection of the work.
- D. Construction Facilities: Access roads, parking, progress cleaning, and project signage.

1.02 TEMPORARY UTILITIES

- A. Electricity
 - 1. Provide and pay for required power service for construction from Utility source.
- B. Lighting
 - 1. Provide and maintain lighting for construction operations.
 - 2. Provide and maintain lighting to exterior staging and storage areas after dark for security purposes.
- C. Water
 - 1. Where practical, Owner will provide access to water for use during construction.
- D. Sanitary Facilities
 - 1. Provide and maintain required facilities and enclosures, as necessary to comply with the laws and ordinances of the authority having jurisdiction and the State of North Carolina.
 - 2. General Contractor shall provide the above sanitary facilities for all contractors, sub-contractors, Owner and Engineer at the Project Site.
 - 3. Existing facilities shall not be used.

1.03 CONSTRUCTION FACILITIES

- A. General
 - 1. Construction facilities shall be the responsibility of each Contractor for their respective work unless noted otherwise.
- B. Parking
 - 1. When site space is not adequate arrange for temporary off-site surface parking areas to accommodate construction personnel.
 - 2. Do not allow vehicle parking to block existing drives.
 - 3. Do not allow vehicle parking on private property without prior approval.
- C. Progress Cleaning
 - 1. Maintain areas to be free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
 - 2. Remove waste materials, debris, and rubbish from site periodically and dispose off site.

1.04 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary above grade or buried utilities, equipment, facilities, and materials, prior to Final Inspection.
- B. Clean and repair damage caused by installation or use of temporary work.
- C. Restore existing facilities used during construction to original or better condition.
Restore permanent facilities used during construction to specified condition.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 57 05
TEMPORARY CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Requirements for temporary controls during construction, including:
 - a. Noise control.
 - b. Temporary pest and rodent controls.
 - c. Pollution control, including solid waste, water pollution, atmospheric pollution, and other types of pollution.
 - d. Odor control.

B. Scope:

1. Contractor shall provide and maintain materials, equipment, labor, services, and temporary construction as necessary and required to control environmental conditions at the Site and adjacent areas during construction.
2. Contractor shall pay all costs, including fines and civil penalties, if any, for failure to implement and maintain temporary controls in accordance with the Contract Documents and Laws and Regulations. Contractor is not eligible for increase in Contract Price or Contract Times due to failure to comply with requirements for temporary controls.
3. Maintain temporary controls until no longer necessary or required. Provide temporary controls at all times when Contractor is working at the Site.

C. Related Requirements:

1. Section 01 74 00 - Cleaning.

1.2 SUBMITTALS

A. Informational Submittals:

1. Submit the following:
 - a. Procedural Submittals:
 - 1) Proposed dust control measure, when Submittal is requested by Engineer.
 - b. Field Quality Control:
 - 1) When requested by Engineer, promptly obtain and submit results of field measurements and field test data substantiating compliance of Contractor's temporary controls with the Contract Documents.

PART 2 - PRODUCTS – (NOT USED)

PART 3 - EXECUTION

3.1 NOISE CONTROL

A. Noise Control – General:

1. Contractor's vehicles, construction equipment, and machinery shall minimize noise emissions to greatest degree practicable. When necessary, provide mufflers and silencers on construction equipment, machinery, and vehicles, and provide temporary sound barriers sound-absorbing blankets, sound-reducing enclosures, modified backup alarms, and other mitigation measures when necessary.
2. Noise threshold levels shall comply with Laws and Regulations, including (a) OSHA requirements and recommendations, and (b) local ordinances or other Laws or Regulations.

3. Noise emissions shall not interfere with the work of Owner, facility manager (if other than Owner), or others. The use of noise-producing signals, including horns, whistles, alarms, and bells shall be for safety warning and emergency purposes only.
4. Music or entertainment systems, including personal and vehicle radios, media players, and the like, when used, shall not be audible at the property line and shall not disturb others at the Site.
5. Field Quality Control of Noise:
 - a. If Owner or Engineer believes potential exists that allowable noise levels are being exceeded, Contractor will be required to, and shall promptly perform, appropriate noise monitoring in presence of Owner or Engineer and shall submit written results to Engineer.
 - b. Owner and Engineer reserve the right to perform independent noise monitoring at any time during the Work.
6. If noise level exceeds allowable maximum, Contractor shall immediately cease the activity emitting the excessive noise and promptly implement noise-mitigating measures to comply with noise limitations.

3.2 DUST CONTROL

A. Dust Control – General:

1. Control objectionable dust caused by Contractor's operation of vehicles and construction equipment and machinery, site clearing, demolition, cleaning, and other actions. To minimize airborne dust, apply water or use other methods subject to acceptance of Engineer and approval of authorities having jurisdiction.

B. Dust Control Methods:

1. Apply dust controls as frequently as necessary or required without creating inconveniences, nuisances, or hazards, such as excessive mud and ponding of water at or adjacent to the Site. Do not use water for dust control when water will cause hazardous or objectionable conditions such as ice, mud, ponds, and pollution.
2. Provide dust control that is non-polluting and does not contribute to tracking-out of dirt, mud, and dust onto pavement.
3. Do not allow water used for dust control to discharge to storm water drainage system or surface waters.
4. Where appropriate, reduce travel speed of construction vehicles and construction equipment to reduce the potential for dust emissions arising from vehicle and equipment passage.

C. Removal of Dust and Dirt from Pavement and Other Travelled Ways:

1. Remove dust, mud, and dirt from roads, parking areas, and other travelled ways not less than the frequency indicated in Section 01 74 00 - Cleaning.

D. Removal of Dust and Dirt from Buildings and Structures:

1. When dust and dirt from Contractor's activities has accumulated to a noticeable or objectionable extent (compared with preconstruction conditions) on buildings or structures, remove the dust and dirt caused by Contractor's operations by appropriate methods, including power-washing using mild detergent. Remedy damage caused by dust, dirt, and power-washing.
2. Dust in sensitive equipment, such as electrical and control panels, instruments, HVAC systems and other equipment shall be cleaned by a Subcontractor specializing in cleaning such items.
3. During the Project, remove objectionable and noticeable dust, dirt, and mud in areas occupied by Owner or facility manager, and Contractor's work areas, resulting from Contractor's activities. Owner and facility manager will take reasonable measures to avoid tracking dust, dirt, and mud into their occupied areas.

4. Comply with Section 01 74 00 - Cleaning.

3.3 PEST AND RODENT CONTROL

A. Pest and Rodent Control – General:

1. Provide pest and rodent controls as necessary to prevent infestation of the Site, storage areas, and adjacent areas.
2. Pests and rodents include, but are not limited to: flies, mosquitoes, gnats, midges, stinging insects, other insects and the like, worms, rats, mice, moles, voles, similar animals, raccoons, skunks, objectionable numbers and species of birds, and others.
3. Implement appropriate pest and rodent controls when pests, rodents, or both are apparent at the Site or offsite storage, staging, or laydown areas.

B. Methods, Materials, and Equipment for Pest and Rodent Control during Construction:

1. Employ methods and use materials and equipment for pest and rodent control that do not adversely affect conditions at the Site or on adjacent and nearby properties.
2. Do not use control methods or poisons injurious to household pets or animals other than targeted pests and rodents.
3. Avoid control methods that present hazards to humans, including children.

C. Disposal of Pests and Rodents:

1. In accordance with Laws and Regulations, promptly and properly dispose of pests and rodents trapped or otherwise controlled. Do not bury or dispose of deceased animals at the Site or in adjacent areas.

3.4 POLLUTION CONTROL

A. Pollution Control – General:

1. Provide means, methods, and facilities necessary and required to prevent contamination of soil, water, and atmosphere caused by accumulation or discharge of substances and materials that are either noxious, polluting, or both, from or caused by construction and related activities.
2. Construction equipment and machinery shall comply with Laws and Regulations.
3. Comply with Section 01 35 43.13 - Environmental Procedures for Hazardous Materials.

B. Spills and Contamination:

1. Perform emergency containment, cleanup, and remedy of spills and contamination resulting from construction and related activities. Promptly remove and properly dispose of contaminated soils and liquids.
2. Comply with Owner's hazard control procedures as indicated in the Supplementary Conditions.

C. Protection of Surface Water and Groundwater:

1. Provide and maintain appropriate, temporary measures to prevent harmful substances from entering surface water, groundwater, and drinking water. Prevent disposal of wastes, effluents, chemicals, and the like into or adjacent to groundwater, surface water, drainage routes (including swales, ditches, and storm sewers) and drinking water.
2. Obtain sewerage system owner's consent and approval prior to discharging into sanitary sewers or combined sewers. Do not discharge pollutants not in accordance with Laws and Regulations into combined sewers, or sewers tributary to combined sewers, when wet weather overflows to receiving waters may occur.

D. Atmospheric Pollutants:

1. Provide and maintain temporary controls for atmospheric pollutants resulting from construction and related activities, whether to outdoor or indoor atmospheres.

2. Prevent harmful dispersal of pollutants into atmosphere.
3. Do not discharge exhaust from internal combustion engines or combustion operations into buildings, structures, or near ventilation intakes for buildings or structures.
4. Prevent toxic and noxious concentrations of chemicals, fumes, and vapors.

E. Solid Waste:

1. Provide and maintain temporary controls for managing solid waste related to the Work.
2. Prevent solid waste from:
 - a. Becoming airborne or blowing in the wind.
 - b. Being inadvertently transmitted to adjacent, offsite properties, and areas of the Site not part of the Project.
 - c. Being deposited in or discharging to surface waters, open process tanks, and drainage routes.
3. Properly handle and dispose of solid waste. Burning or burying solid waste, including unused materials, at the Site or adjacent areas is prohibited.
4. Cleaning and Disposal of Debris: Comply with applicable requirements of the General Conditions, as may be modified by the Supplementary Conditions, and Section 01 74 00 - Cleaning.
5. Do not mix or store in the same container solid waste containing Constituents of Concern (and constitutes, or may constitute, a Hazardous Environmental Condition) with solid waste that does not contain Constituents of Concern.
6. Store solid waste in appropriate, covered, containers.
7. Promptly, and at regular intervals, remove solid waste from the Site for transport and disposal in accordance with Laws and Regulations.

3.5 ODOR CONTROL DURING CONSTRUCTION

A. Odors – General:

1. Avoid discharges of unpleasant or noxious odors from construction and related activities. Whether nature of the Work is such that odor generation is unavoidable, provide appropriate temporary controls for odors.
2. Give priority to avoiding odor generation, followed by:
 - a. Counteracting (treating the cause of) odors.
 - b. Containing odors.
 - c. Odor masking as the last resort for odor control.

3.6 REMOVAL OF TEMPORARY CONTROLS

A. Removals – General:

1. Unless otherwise indicated elsewhere in this Section in requirements for respective temporary controls, upon completion of the associated Work and when temporary controls are no longer necessary, remove temporary controls and restore the Site to condition in accordance with the Contract Documents; if condition is not shown or indicated, restore the Site to pre-construction condition.

END OF SECTION

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Products.
- B. Transportation and handling.
- C. Storage and protection.
- D. Product options.
- E. Substitutions.

1.02 RELATED SECTIONS

- A. The following Sections have work that is directly related to this Section. This does not relieve the Contractor of his responsibility of proper coordination of all the work:
 - 1. Section 01 35 13 Specific Project Requirements

1.03 PRODUCTS

- A. Products: Means New material, machinery, components, equipment, fixtures, and systems forming the Work. Does not include machinery and equipment used for preparation, fabrication, conveying, and erection of the Work. Products may also include existing materials or components specified in the Contract Documents for reuse.

1.04 TRANSPORTATION AND HANDLING

- A. Transport and handle Products in accordance with manufacturer's instructions.
- B. Ship fabricated assemblies in largest sections permitted by carrier regulations and properly marked for ease of field erection.
- C. Promptly inspect shipments to assure that Products comply with specified requirements, quantities are correct, and Products are undamaged.
- D. Provide equipment and personnel to handle Products by methods to prevent soiling, disfigurement, or damage.

1.05 STORAGE AND PROTECTION

- A. Keep on site storage of material to a minimum. Owner shall approve of any onsite storage in advance.
- B. Store and protect Products in accordance with manufacturer's instructions in unopened original packages, with seals and labels intact and legible. Store sensitive Products in weather-tight, light blocking, or climate-controlled enclosures, as required.
- C. For exterior storage of fabricated Products, place on sloped supports, above ground.
- D. Provide off site storage and protection when site does not permit on site storage.
- E. Cover Products subject to deterioration with impervious sheet covering. Provide ventilation to avoid condensation.

- F. Store loose granular Products on solid flat surfaces in a well drained area. Prevent mixing with foreign matter.
- G. Arrange storage of Products to permit access for inspection. Periodically inspect to assure Products are maintained under specified conditions.

1.06 DAMAGED PRODUCTS

- A. Remove damaged Products from Project site.

1.07 PRODUCT OPTIONS

- A. Products Specified by Reference Standards: Product meeting standard and specific requirements of these specifications.
- B. Products Specified by Naming One or More Manufacturers: Products of manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming Three Manufacturers with an "or equal." Provision for Substitutions: Submit a request for substitution for manufacturer not named during the shop drawing submittal.

1.08 SUBSTITUTIONS

- A. Substitutions may be considered when a product becomes unavailable through no fault of the Contractor.
- B. Document each request with complete data substantiating compliance of proposed Substitution with Contract Documents.
- C. Request constitutes a representation that Contractor:
 - 1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product.
 - 2. Shall provide same warranty for Substitution as for specified product.
 - 3. Shall coordinate installation and make changes to other Work which may be required for the Work to be complete with no additional cost to Owner.
 - 4. Waives claims for additional costs or time extension that may subsequently become apparent.
 - 5. Shall reimburse Owner for review or redesign services associated with reapproval by authorities.
- D. Substitutions will not be considered when they are indicated or implied on shop drawing or product data submittals, without separate written request, or when acceptance will require revision to the Contract Documents.
- E. Substitution Submittal Procedure:
 - 1. Submit three copies of request for Substitution for consideration. Limit each request to one proposed Substitution.
 - 2. Submit shop drawings, product data, and certified test results attesting to proposed product equivalence.
 - 3. Engineer will notify Contractor, in writing, of decision to accept or reject request.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 70 00
EXECUTION REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Examination.
- B. Cutting and patching.
- C. General installation provisions.
- D. Cleaning and protection.
- E. Final inspection and tests.
- F. Close out procedures.

1.02 RELATED SECTIONS

- A. The following Sections have work that is directly related to this Section. This does not relieve the Contractor of his responsibility of proper coordination of all the work:
 - 1. Section 01 35 13 Specific Project Requirements

1.03 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent Work. Beginning new Work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new Work being applied or attached.
- C. Examine and verify specific conditions described in individual specifications sections.
- D. Verify that utility services are available, of the correct characteristics, and in the correct locations.

1.04 CUTTING AND PATCHING

- A. General
 - 1. Do not cut, or alter the work of other contractors without written approval of the Engineer.
 - 2. Work removed shall be replaced or repaired by the Contractor who removed or damaged the work, and a craftsman, skilled in the trade that the particular replacement requires, shall do the work. (i.e.: A mason, not an electrician, shall replace masonry removed by the Electrical Contractor.)
 - 3. Conduct removal operations in a manner that will eliminate hazards to persons and property and prevent the release of dust and rubbish into the air. Existing work, which is to remain and is damaged by Contractor's operations shall be replaced with new materials at no additional cost to the Owner.
 - 4. For replacement of work removed, comply with specifications for type of work to be done.
- B. Inspection
 - 1. Inspect existing conditions of work including elements subject to movement or damage during cutting and patching, and excavating and backfilling.
 - 2. After uncovering work, inspect conditions affecting installation of new products.

- C. Preparation prior to cutting
 - 1. Provide shoring, bracing, and support as required to maintain structural integrity of project and in compliance with OSHA requirements.
 - 2. Provide protection for other portions of project.
 - 3. Provide protection from elements.
- D. Performance
 - 1. Execute fitting and adjustment of products to provide finished installation to comply with specified tolerances, finishes.
 - 2. Execute cutting and demolition by methods to prevent damage to other work and provide proper surfaces to receive installation of repairs and new work.
 - 3. Execute excavating and backfilling as specified in Section 31 23 33, Trenching for Utilities.
 - 4. Restore work, which has been cut or removed; install new products to provide completed work in accordance with requirements of contract documents.
 - 5. Refinish entire surfaces as necessary to provide an even finish.
 - a. Continuous Surfaces: To nearest intersections.
 - b. Assembly: Entire Refinishing.

1.05 GENERAL INSTALLATION PROVISIONS

- A. Require Installer of each major component to inspect conditions under which Work is to be performed. Clean substrate surfaces prior to applying next material or substance. Do not proceed until unsatisfactory conditions have been corrected.
- B. Comply with manufacturer's recommendations to the extent that they are more explicit or stringent than requirements contained in Contract Documents.
- C. Provide attachment and connection devices and methods necessary for securing Work. Secure Work true to line and level. Allow for expansion and building movement.
- D. Provide uniform joint widths in exposed Work. Arrange joints in exposed Work to obtain the best visual effect. Refer questionable choices to the Engineer for final decision.
- E. Check dimensions before starting each installation.
- F. Install each component during optimum weather conditions and at the appropriate point in the project in order to ensure the best possible results. Isolate each part of the completed construction from incompatible material as necessary to prevent deterioration.
- G. Coordinate temporary enclosures with required inspections and tests, to minimize the necessity of uncovering completed construction for that purpose.
- H. Where mounting heights are not indicated, install individual components at standard mounting heights recognized within the industry for the particular application indicated. Refer questionable mounting height decisions to the Engineer for final decision.

1.06 CLEANING AND PROTECTION

- A. During handling and installation, clean and protect construction in progress and adjoining materials in place. Apply protective covering where required to ensure protection from damage or deterioration.
- B. Clean and maintain completed construction as frequently as necessary through the construction period. Adjust and lubricate components as required to ensure proper operation.
- C. Limiting Exposures: Supervise construction activities to ensure that no part of the construction, completed or in progress, is subject to harmful, or dangerous exposure during the construction period. Where applicable, such exposures include, but are not limited to, the following:
 - 1. Excessive static or dynamic loading.
 - 2. Excessive internal or external pressures.
 - 3. Excessively high or low temperatures.
 - 4. Thermal shock.
 - 5. Air contamination or pollution.
 - 6. Water or ice.
 - 7. Abrasion.
 - 8. Heavy traffic.
 - 9. Misalignment.
 - 10. Improper shipping or handling.
 - 11. Theft.
 - 12. Vandalism.
 - 13. Direct sunlight
- D. Clean Project prior to final inspection. Project clean up shall include, but not be limited to, the following:
 - 1. Clean surfaces exposed to view as recommended by manufacturer.
 - 2. Remove temporary labels.
 - 3. Clean debris from drainage systems.
 - 4. Sweep paved areas.
 - 5. Rake clean landscaped surfaces.
 - 6. Remove waste, and surplus materials.
 - 7. Remove temporary construction facilities.

1.07 FINAL INSPECTION AND TESTS

- A. Complete punch list items within 30 days of receipt from Engineer. Owner may have work not completed within 30 days performed by others with the cost deducted from Contractor's final payment. Additional engineering and inspection services required as a result of Contractor not completing punch list within 30 days shall be at Contractor's expense.

1.08 CLOSE OUT PROCEDURES

- A. Submit written certification that Contract Documents have been reviewed, Work has been inspected, and is complete in accordance with Contract Documents and ready for Engineer's inspection.
- B. Provide submittals to Engineer that are required by governing or other authorities.
- C. Submit set of Record Documents indicating changes during construction as required in Section 01 33 00, Submittal Procedures.

- D. Submit final Application for Payment identifying total adjusted Contract Sum, previous payments, and final amount due.
- E. Submit the following with final Application for Payment:
 - 1. Contractor's Affidavit of Release of Liens to Owner
 - 2. Consent of Surety for Final Payment
 - 3. Affidavit of Payment of Debts and Claims
 - 4. Final Certified Payroll Information
 - 5. Affidavits of Release of Liens from Subcontractors and Suppliers to Contractor.
 - 6. As-built Drawings
 - 7. Certified statement that all final punchlist items have been completed with punchlist attached.
 - 8. Written releases of liability and claims from property owners, for which the Contractor negotiated temporary easements/right-of-entry with for laydown, staging and/or access.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01 74 00

CLEANING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Requirements for keeping the Site free of accumulations of waste materials during construction ("progress cleaning").
2. Cleaning for Substantial Completion and prior to final inspection (collectively, "closeout cleaning").

B. Scope:

1. Contractor shall perform cleaning during the Project, including progress cleaning, as condition precedent to Substantial Completion, upon completion of the Work, and as required by the General Conditions, as may be modified by the Supplementary Conditions, this Specifications section, and elsewhere in the Contract Documents.
2. Maintain in a clean manner the Site, the Work, and areas adjacent to or affected by the Work.

1.2 QUALITY ASSURANCE

A. Referenced Standards:

1. National Fire Protection Association (NFPA):
 - a. 241, Safeguarding Construction, Alteration, and Demolition Operations.

PART 2 - PRODUCTS - (NOT USED)

PART 3 - EXECUTION

3.1 PROGRESS CLEANING

A. Progress Cleaning – General:

1. Clean the Site, work areas, and other areas occupied by Contractor not less than weekly. Dispose of waste materials in accordance with the General Conditions, as may be modified by the Supplementary Conditions, and the following:
 - a. Comply with NFPA 241 for removing combustible waste materials and debris.
 - b. Do not hold non-combustible materials at the Site more than three days if the ambient air temperature is expected to rise above 80 degrees F. When ambient air temperature is less than 80 degrees F, dispose of non-combustible materials within seven days of their generation.
 - c. Provide suitable containers for storage of waste materials and debris. Avoid generation of odors and creation of nuisances.
 - d. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately.

B. Progress Cleaning – Site:

1. Keep outdoor, dust-generating areas wetted down or otherwise control dust emissions.
2. Not less than weekly, brush-sweep roadways and paved areas at the Site and adjacent areas used by construction vehicles or otherwise affected by construction activities.
3. Comply with dust control requirements of Section 01 57 05 - Temporary Controls.

C. Progress Cleaning – Work Areas:

1. Clean areas where the Work is in progress to maintain an extent of cleanliness necessary for proper execution of the Work and safety of personnel.
 2. Remove liquid spills promptly. Where spills may have harmful effects on health, safety, protection of facilities, or the environment, immediately report spills to Owner, Engineer, and authorities having jurisdiction, in accordance with the Contract Documents and Laws and Regulations.
 3. Where dust would impair proper execution of or quality of the Work, broom-clean or vacuum entire work area, as necessary.
 4. Concealed Spaces: Remove waste material and debris from concealed spaces before enclosing the space.
- D. Progress Cleaning – Installed Work:
1. Keep installed Work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of installed materials and equipment, using only cleaning agents and methods specifically recommended by material or equipment Supplier.
 2. If Supplier does not recommend specific cleaning agents or methods, use cleaning agents and methods that are not hazardous to health and property and that will not damage or mar exposed surfaces.
- E. Progress Cleaning – Exposed Surfaces:
1. Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration until Substantial Completion.
- F. Waste Disposal:
1. Properly dispose of waste materials (including surplus materials, debris, rubbish, and other waste) off the Site.
 2. Do not burn or bury waste materials at the Site.
 3. Remove waste material and rubbish from excavations before backfilling.
 4. Do not discharge volatile or hazardous substances, such as mineral spirits, oil, or paint thinner, into storm sewers, gutters, sanitary sewers, or other location in the environment. Dispose of such materials in accordance with Laws and Regulations.
 5. Do not discharge wastes to surface waters, drainage routes, or groundwater.
 6. Contractor is solely responsible for complying with Laws and Regulations regarding storing, transporting, and disposing of waste generated by Contractor's operations or brought to the Site by Contractor.
- G. During handling and installation of materials and equipment, clean and protect construction in progress and adjoining materials and equipment already in place. Apply protective covering where necessary or required for protection from damage or deterioration, until Substantial Completion.
- H. Clean completed construction as frequently as necessary throughout the construction period.

3.2 CLOSEOUT CLEANING

- A. Complete the following prior to requesting inspection for Substantial Completion:
1. Clean and remove from the Site waste material (including rubbish and debris) and other foreign and undesirable items and substances.
 2. Sweep broom-clean paved areas suitable for access by vehicles.
 3. Remove spills and stains or petroleum, oils, solvents, other chemicals, and other foreign and undesirable deposits.
 4. Hose-clean sidewalks and loading areas.
 5. Repair pavement, roads, sod, and other areas affected by construction operations and restore to specified condition; if condition is not specified, restore to preconstruction condition.

6. Clean exposed exterior and interior hard-surfaced finishes to dirt-free condition, free of spatter, grease, stains, fingerprints, films, and similar foreign and undesirable substances.
 7. Remove waste material and surface dust from limited-access spaces, including roofs, plenums, shafts, trenchway, equipment vaults, manholes, and similar spaces.
 8. In unoccupied spaces, sweep concrete floors broom-clean.
 9. Clean transparent materials, including mirrors and glazing in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials.
 10. Remove non-permanent tags and labels.
 11. Surface Finishes:
 - a. Touch-up and otherwise repair and restore chipped, scratched, dented or otherwise marred surfaces to specified finish and match adjacent surfaces.
 - b. Do not paint over "UL" or similar labels, including mechanical and electrical nameplates.
 12. Wipe surfaces of mechanical and electrical equipment, and similar equipment. Remove excess lubrication, paint, and mortar droppings, and other foreign or undesirable substances.
 13. Clean plumbing fixtures to sanitary condition, free of stains, including stains resulting from water exposure.
 14. Leave the Site clean, and in neat, orderly condition, satisfactory to Owner and Engineer.
- B. Complete the following prior to requesting final inspection:
1. After Substantial Completion of all the Work, following completion of items of incomplete or damaged Work ("punch list Work"), clean "punch list Work areas in accordance with Paragraph 3.2.A of this Specifications Section.
 2. Remove field offices, Contractor's storage sheds, and remaining stockpiles and clean all such areas in accordance with Paragraph 3.2.B of this Specifications Section.

END OF SECTION

This page intentionally left blank.

SECTION 02 41 00

DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. General provisions applicable to all demolition and removals.
2. Architectural and structural demolition and removals.
3. Mechanical demolition and removals
4. Electrical demolition and removals.
5. Disposal of demolition debris, materials, and equipment.

1.2 REFERENCES

A. Reference Standards: Standards referenced in this section include, but are not necessarily limited to, the following:

1. National Fire Protection Association (NFPA):
 - a. 241 - Safeguarding Construction, Alteration, and Demolition Operations.

1.3 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Review procedures under this and other Sections and coordinate the Work that will be performed with, or before, demolition and removals.

1.4 QUALITY ASSURANCE

A. Regulatory Requirements:

1. Comply with requirements of authorities having jurisdiction and relevant permits, if any, required and obtained for demolition Work.

1.5 SUBMITTALS

A. Informational Submittals: Submit the following:

1. Procedure Submittals:
 - a. Demolition and Removal Plan: Not less than ten days prior to starting demolition Work, submit acceptable plan for demolition and removal Work, including:
 - 1) Plan for coordinating shut-offs, capping, temporary services, and continuing utility services.
 - 2) General indication of intended approach for performing demolition Work, including how proposed demolition will affect Owner and others, including owners and occupants of properties at and adjacent to the Site and the public.
 - 3) Disposal and recycling facilities proposed, including facility owner, facility name, location, and processes. Include copy of appropriate permits and licenses, and compliance status.
 - 4) Planned demolition operating sequences, relative to their effect on Owner and others, including owners and occupants of properties at and adjacent to the Site and the public.
 - 5) Detailed schedule of demolition Work in accordance with the Progress Schedule accepted by Engineer.
 - 6) Copy of demolition permit (when required) obtained from authorities having jurisdiction.

- b. Engineer's review, comments upon, and acceptance of Contractor's procedure Submittals for demolition are only for the limited purposes indicated in the Contract Documents. Engineer's review, comments upon, action, or inaction concerning such Submittals, shall not, in any way, reduce or mitigate Contractor's sole responsibility for construction means, methods, techniques, procedures, and sequences, or associated safety and protection measures.
- 2. Notification of Intended Demolition Start: Submit in accordance with Paragraph 3.1.B of this Section.
- 3. Field Quality Control Test Results:
 - a. Results of megger-testing of existing motors that will remain Owner's property.

1.6 FIELD CONDITIONS

A. Existing Conditions:

- 1. Owner and Engineer make no representation of condition or structural integrity of areas to be demolished or where removals are required by the Contract Documents.

PART 2 - PRODUCTS - (NOT USED)

PART 3 - EXECUTION

3.1 PREPARATION

A. Notification:

- 1. Not less than 48 hours prior to commencing demolition or removal, advise Engineer in writing of planned start of demolition Work. Do not start removals when either Owner or Engineer furnishes reasonable objection in a timely manner.
- 2. Where demolition or removal has potential to affect adjacent properties, occupants, streets, or other public thoroughfare, transportation facilities, utilities, water courses, or any combination thereof, furnish required notices to owners and occupants of properties, buildings, and structures that may be affected by the demolition or removal.
- 3. In accordance with Laws and Regulations, and applicable permits, furnish to authorities having jurisdiction, including emergency services as necessary, appropriate notices of planned demolition and removals.
- 4. Submit to Engineer copies of notices furnished to adjacent property owners, occupants, and authorities having jurisdiction.

B. Protection of In-Place Conditions:

- 1. Perform demolition and removal Work in manner that prevents damage and injury to property, structures, occupants, the public, and facilities. Do not interfere with use of, and free and safe access to and from, buildings, structures, and properties, unless allowed by the Contract Documents or otherwise allowed in writing by Owner.
- 2. Closing or obstructing roads, drives, sidewalks, and passageways adjacent to the Work is not allowed unless indicated otherwise in the Contract Documents. Perform the Work with minimum interference to vehicular and pedestrian traffic.
- 3. Provide temporary partitions between demolition work areas and (a) areas that will be occupied during demolition and removals, and (b) areas accessible to the public or visitors. Temporary partitions shall be sturdy, braced plywood in good condition, of dimensions sufficient to adequately screen demolition work from view of occupants, public, and visitors. Maintain temporary partitions in place until demolition and removal Work in the subject area is complete or until other work requires removal of temporary partitions.
- 4. Provide appropriate temporary barriers, lighting, sidewalk sheds, and other necessary protection.
- 5. Repair damage to facilities not subject to demolition or removal when such damage results from Contractor's action or inaction.

C. Remediation:

1. If unanticipated Hazardous Environmental Condition is believed to be encountered during demolition and removals, comply with requirements of the General Conditions, as may be modified by the Supplementary Conditions.

3.2 DEMOLITION - GENERAL

A. General, Common Requirements for Demolition and Removal Work:

1. Contractor shall provide all labor, materials, construction equipment and machinery, tools, services (including professional services when necessary), and incidentals as shown, specified and required for demolition, removals, and disposal Work.
2. The Work under this Section includes, but is not necessarily limited to:
 - a. Demolition and removal of existing materials and equipment as shown or indicated in the Contract Documents. The Work includes demolition of roofs, attachments, appurtenances, piping, electrical and mechanical systems and equipment, and similar existing materials, equipment, and items.
3. Demolition and removals indicated in other Sections shall comply with requirements of this Section.
4. Perform demolition Work as shown or indicated on the Drawings and as indicated elsewhere in the Contract Documents.
5. Pay for transporting and, as applicable, disposing of materials and equipment resulting from demolition and removals Work.
6. Locate construction equipment used for demolition Work and remove demolished materials and equipment to avoid imposing excessive loading on supporting and adjacent walls, floors, framing, facilities, and Underground Facilities.
7. Comply with NFPA 241.

B. Pollution Controls:

1. Use water sprinkling, temporary enclosures, and other suitable methods to limit emissions of dust and dirt to lowest practical level. Comply with Section 01 57 05 - Temporary Controls, and Laws and Regulations.
2. Do not use water when water may create hazardous or objectionable conditions such as icing, flooding, or pollution.
3. Clean adjacent structures, facilities, properties, and improvements of dust, dirt, and debris caused by demolition Work, in accordance with the General Conditions and Section 01 74 00 - Cleaning.

C. Explosives:

1. Explosives are not allowed at the Site. Do not use explosives for demolition and removal Work.

D. Building or Structure Demolition and Removals:

1. Unless otherwise acceptable to Engineer, proceed with demolition from top of building or structure to the ground. Complete demolition Work above each floor or tier before disturbing supporting members of lower levels.
2. Demolish concrete and masonry in small sections.
3. Remove structural framing members and lower to ground using hoists, cranes, or other suitable methods. Do not throw or drop to the ground.
4. Temporary Bracing and Supports:
 - a. Provide temporary bracing and supports sufficient to maintain safety, stability, and resist all loads to which the structure may be subject during demolition and removals, until entirety is permanently removed or permanently stabilized.

- b. Temporary bracing and supports shall be sufficient for associated dead load, live load, transient loading, and dynamic loads such as wind, seismic, and other loads to which the temporary bracing or support may be subject.
- E. Salvage and Ownership:
- 1. The following applies to materials and equipment to remain Owner's property:
 - a. Contractor shall carefully remove and appropriately handle materials and equipment to remain Owner's property in manner avoids damaging and invalidating warranties in effect for such items. Brace motors attached to flexible mountings until reinstallation or delivery to Owner's storage location. Fully remedy to pre-construction condition or replace items damaged during removal, handling, or storage by Contractor.
 - b. Remove, as functional units, together with all appurtenances required for operation.
 - c. Clean and tag for storage, items to remain Owner's property, and maintain comprehensive, detailed listing of such items. Update such listing when items are relocated.
 - d. Protect from damage.
 - e. Deliver to designated storage location at the Site, or other site, indicated in the Contract Documents, at place designated by Engineer or Owner.
 - 2. Preparation of Owner's existing equipment for storage:
 - a. Where appropriate, identify each component with markings or tags to indicate its position in the assembly and the assembly of which it is part.
 - b. Place small parts in appropriate, durable boxes and clearly mark contents on the outside of box or container.
 - c. Remove oil from oil-lubricated bearings and gear boxes and replace with storage oil.
 - d. Provide grease for grease-lubricated bearings.
 - e. Replace breather plugs with solid plugs.
 - f. Megger-test motor windings: Attach report of the test results to the associated motor and submit copy to Engineer.
 - g. Attach unit to suitable crate bottom.
 - h. Enclose unit in polyethylene film and seal all seams and the film to the base of the unit with tape.
 - i. Construct crate of wood slats around top and sides of unit.
 - j. Attach permanent instruction tag to outside of crate stating: "This unit has been prepared for storage. Replace oil, vent plugs, and lubricant in accordance with manufacturer's instructions before start-up."

3.3 STRUCTURAL REMOVALS

- A. Remove structures to lines and grades shown or indicated, unless otherwise directed by Engineer. Where limits are not shown or indicated, limits shall be four inches outside item to be installed. Removals beyond limits shown or indicated shall be at Contractor's risk and expense and such excess removals shall be reconstructed to satisfaction of Engineer without additional cost to Owner.
- B. Recycling and Reuse of Demolition Materials:
 - 1. All concrete, brick, tile, masonry, roofing materials, reinforcing steel, structural metals, miscellaneous metals, plaster, wire mesh, and other items contained in, or upon, building or structure to be demolished, shall be removed, transported, and disposed of away from the Site, unless otherwise approved by Engineer.
 - 2. Do not use demolished materials as fill or backfill adjacent to buildings and structures, in pipeline trenches, or as subbase under buildings, structures, or pavement.

- C. After removing concrete and masonry walls or portions thereof, mats, slabs, and similar construction that ties in to the Work or to existing construction, neatly repair the junction point to leave exposed only finished edges and finished surfaces.
- D. Where parts of existing structures are to remain in service following demolition:
 - 1. Where parts of existing structures are to remain in service following demolition, remove the portions shown or indicated for removal, repair damage, and leave the building or structure in proper condition for the intended use.
 - 2. Remove concrete and masonry to the lines shown or indicated by sawing, drilling, chipping, and other suitable methods. Leave the resulting surfaces true and even, with sharp, straight corners, resulting in neat joints with new construction and be satisfactory for the purpose intended.
 - 3. Do not damage reinforcing bars beyond the area of concrete and masonry removal. Do not saw-cut beyond the area to be removed.
 - 4. Reinforcing bars that are exposed at surfaces of removed concrete and masonry that will not be covered with new concrete or masonry shall be removed to 1.5 inches below the final surface. Repair resulting hole, with repair mortar (for concrete), or grout (for masonry), so that filled hole is flush with adjacent surface.
 - 5. Where existing reinforcing bars are shown or indicated to extend into new construction, remove existing concrete so that reinforcing bars are clean and undamaged.
- E. Removal of Anchorages and Protruding Metals:
 - 1. Where equipment or material anchored to concrete or masonry are removed, and anchors are not to be re-used, and where existing metals (and to be removed) protrude from concrete, remove anchors and other metal to not less than 1.5 inches beneath surface of concrete or masonry member. Repair resulting hole, with repair mortar (for concrete), or grout (for masonry), so that filled hole is flush with adjacent surface.
 - 2. At Contractor's option, when anchor is stainless steel, anchor may be cut flush with surface of concrete or masonry, when so approved by Engineer.
- F. Jambs, sills and heads of windows, passageways, doors, or other openings (as applicable) cut-in to the Work or to existing construction, shall be dressed with masonry, concrete, or metal to provide smooth, finished appearance.
- G. Where anchoring materials, including bolts, nuts, hangers, welds, and reinforcing steel, are required to attach the Work to existing construction, provide such materials under this Section, unless specified elsewhere in the Contract Documents.

3.4 MECHANICAL REMOVALS

- A. Life-Safety Systems:
 - 1. Retain existing life-safety systems, including but not limited to fire suppression systems, in place for as long as possible prior to performing associated demolition and removals.
 - 2. Where demolishing buildings or structures equipped with life-safety systems, remove or deactivate life-safety systems only in the area where active demolition operations are in progress.
- B. Equipment Demolition and Removals:
 - 1. Remove equipment supports as applicable, anchorages, base, grout, and piping. Remove anchorage systems in accordance with the "Structural Removals" Article in this Section.
 - 2. Remove access platforms, ladders, and stairs related to equipment being removed, unless otherwise shown or indicated.

3.5 ELECTRICAL REMOVALS

- A. Electrical Removals – General:
 - 1. Comply with Laws and Regulations, including applicable electrical construction codes.

2. Lock Out and Tagging:
 - a. Contractor shall lock out and tag circuit breakers and switches operated by Owner or facility manager (if other than Owner), and shall verify that affected cabling are de-energized to ground potential before commencing electrical removals Work.
 - b. Upon completion of Work in proximity to electrical services, remove locks and tags and promptly advise Engineer and Owner that existing facilities are available for use.

3.6 DISPOSAL OF DEMOLITION DEBRIS

A. Disposal – General:

1. Promptly remove from the Site all debris, waste, rubbish, material, and equipment resulting from demolition and removal Work. Promptly upon completion of demolition and removal Work, remove from the Site construction equipment used in demolition Work.
2. Do not sell at, or adjacent to, the Site demolition materials or removed equipment and items. If materials, equipment or debris will be sold by Contractor, remove the items from the Site and adjacent areas, and perform the sale or transaction elsewhere, in accordance with Laws and Regulations.
3. Cleaning and Removal of Debris: Comply with the General Conditions and Supplementary Conditions.

B. Transportation and Disposal:

1. Non-Hazardous Materials, Equipment, and Debris: Properly transport and dispose of non-hazardous demolition materials, equipment, and debris at appropriate landfill or other suitable location, in accordance with Laws and Regulations. Non-hazardous material does not contain Constituents of Concern such as (but not limited to) asbestos, PCBs, petroleum, hazardous waste, radioactive material, or other material designated as hazardous in Laws or Regulations.
2. Hazardous Materials, Equipment, and Debris: When handling and disposal of items containing Constituents of Concern is included in the Work, properly transport and dispose of such items in accordance with the Contract Documents and Laws and Regulations.

END OF SECTION

SECTION 03 00 05 CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Cast-in-place concrete and grout, including:
 - a. Materials.
 - b. Placing and curing.
 - c. Finishing.
 - d. Field quality control.
 2. Schedules of concrete Work for Project-specific concrete areas.

1.2 REFERENCES

- A. Abbreviations and Terminology:
1. "Place" and "placing", when used in conjunction with the word, "concrete", mean installing concrete or grout.
 2. Terminology used in this Section is consistent with ACI CT-13, unless otherwise indicated in this Section.
 3. Terminology indicated below are not defined terms and are not indicated with initial capital letters, but when used in this section have the meaning indicated below:
 - a. "Specified strength" means required compressive strength 28 days after concrete or grout placing.
- B. Reference Standards: Standards referenced in this section include, but are not necessarily limited to, the following:
1. American Concrete Institute (ACI):
 - a. 117, Specification for Tolerances for Concrete Construction and Materials.
 - b. 211.1, Selecting Proportions for Normal-Density and High-Density Concrete—Guide.
 - c. 212.3R, Report on Chemical Admixtures for Concrete.
 - d. 301, Specifications for Concrete Construction.
 - e. 304R, Guide for Measuring, Mixing, Transporting, and Placing Concrete.
 - f. 304.2R, Guide to Placing Concrete by Pumping Methods.
 - g. 305.1, Specification for Hot Weather Concreting.
 - h. 306.1, Specification for Cold Weather Concreting.
 - i. 318, Building Code Requirements for Structural Concrete.
 - j. 347, Guide to Formwork for Concrete.
 - k. CT-13, Concrete Terminology.
 2. ASTM International (ASTM):
 - a. C33, Standard Specification for Concrete Aggregates.
 - b. C39, Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.
 - c. C94/C94M, Standard Specification for Ready-Mixed Concrete.
 - d. C138, Standard Method of Test for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete.
 - e. C143, Standard Test Method for Slump of Hydraulic Cement Concrete.
 - f. C150, Standard Specification for Portland Cement.

- g. C172, Standard Practice for Sampling Freshly Mixed Concrete.
 - h. C173, Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method.
 - i. C231, Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method.
 - j. C260, Standard Specification for Air-Entraining Admixtures for Concrete.
 - k. C309, Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete.
 - l. C494, Standard Specification for Chemical Admixtures for Concrete.
 - m. C618, Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete.
 - n. C1293, Standard Test Method for Determination of Length Change of Concrete Due to Alkali-Silica Reaction.
 - o. C1315, Standard Specification for Liquid Membrane-Forming Compounds Having Special Properties for Curing and Sealing Concrete.
 - p. C1602, Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete.
 - q. E96, Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials.
 - r. E329, Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection.
3. National Ready Mixed Concrete Association (NRMCA).
- a. Checklist for Certification of Ready Mixed Concrete Production Facilities.

1.3 QUALITY ASSURANCE

A. Qualifications:

- 1. Concrete Testing Laboratory:
 - a. Contractor shall retain the services of and pay concrete testing laboratory.
 - b. Concrete testing laboratory shall comply with ASTM E329. Upon Engineer's request, furnish testing laboratory qualifications as Submittal.
 - c. Concrete testing laboratory responsibilities include the following:
 - 1) Testing proposed materials and mixes for compliance with the Contract Documents, including testing revised materials and mixes in the event of changes.
 - 2) Additional testing and inspection required because of changes in materials or proportions requested by Contractor.

1.4 SUBMITTALS

A. Action Submittals: Submit the following:

- 1. Shop Drawings:
 - a. Scaled (minimum 1/8 inch per foot) drawings showing proposed locations of construction joints, control joints, expansion joints (as applicable) and joint profile dimensions for each joint type.
- 2. Product Data:
 - a. For each proposed admixture and type of grout material (including non-shrink grouts, and grout cure/seal compound), submit manufacturer's published technical data (except safety data sheets).
 - b. Manufacturers, product name, and types of materials for the following:
 - 1) Joint fillers.
 - 2) Curing agents.

- 3) Chemical sealers.
- 4) Bonding and patching mortar.
- 5) Construction joint bonding adhesive.
- 6) Prefabricated waterstops.

B. Informational Submittals: Submit the following:

1. Supplier's Instructions: Submit concurrent with, but separate from, associated product data Submittals:
 - a. Manufacturer's written instructions on proper storage, handling, mixing, and use of materials furnished.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Concrete Grout:

1. Non-shrink, non-metallic grout:
 - a. Products and Manufacturers: Subject to compliance with the Contract Documents, provide required quantity of one of the following:
 - 1) Sika, SikaGrout 212.
 - 2) Euclid Chemical, NS Grout.
 - 3) Five Star, Grout
 - 4) Or equal.
 - b. Non-metallic, noncorrosive, nonstaining, premixed, requiring only water as an additive.
 - c. Grout shall produce positive, controlled expansion.
 - d. Gas liberation shall not result in mass expansion.
 - e. Minimum compressive strength at 28 days: 8,000 psi.

PART 3 - EXECUTION

3.1 EXAMINATION

- A.** Installing the Work constitutes Contractor's approval of underlying work, subgrades, substrates, and field conditions prevailing at the time of the Work.

3.2 FORMING AND PLACING CONCRETE

A. Placing Concrete or Grout:

1. Prior to placing concrete or grout, coordinate the Work with the Work of other trades and other contractors. Do not place concrete until such other construction is properly completed.
2. Place concrete or grout in accordance with ACI 304R and ACI 304.2R.
3. Place concrete or grout in continuous operation within planned joints or sections.
4. Place concrete or grout by methods preventing aggregate segregation.
5. During placing, do not allow concrete or grout to free fall more than four feet.
6. Where free fall of concrete or grout would otherwise exceed four feet, place concrete by means of tremie pipe or chute.

B. Protection:

1. Protect concrete or grout from physical damage and from reduced strength due to environmental extremes, including weather and other ambient conditions.
2. In cold weather, comply with ACI 306.1, except as modified in this provision.

- a. Do not place concrete or grout on frozen material or in contact with forms or material coated with frost, ice, snow, or other frozen matter.
 - b. Do not place heated concrete or grout warmer than 80 degrees F.
 - c. If freezing temperatures are expected during curing, maintain concrete or grout temperature at or above 50 degrees F, for seven days or 70 degrees F for three days.
 - d. Do not allow concrete or grout to cool suddenly.
3. In hot weather, comply with ACI 305.1, except as modified in this provision.
- a. At air temperature of 90 degrees F and above, maintain concrete or grout as cool as possible during placing and curing.
 - b. Do not allow concrete or grout temperature to exceed 90 degrees F during placing.
 - c. Prevent plastic shrinkage cracking due to rapid evaporation of moisture.
 - d. Do not place concrete or grout when actual or anticipated evaporation rate equals or exceeds 0.2 pounds per square foot per hour, determined in accordance with ACI 305.1, Figure 2.1.5.
- C. Installation Tolerances:
- 1. Other tolerances for concrete Work shall be in accordance with ACI 117.

3.3 GROUTING

- A. Preparation:
- 1. Non-shrink, non-metallic grout:
 - a. Clean concrete surfaces receiving grout.
 - b. Saturate concrete with water for not less than 24 hours prior to grouting.
- B. Application:
- 1. Non-shrink, non-metallic grout:
 - a. Mix using mechanical mixer.
 - b. Provide quantity of water on as necessary to provide flowable grout.
 - c. Place in accordance with grout manufacturer's written instructions.
 - d. Completely fill spaces and cavities below baseplates.
 - e. Provide forms for grouting where grout is not confined.
 - f. Where exposed to view, finish grout edges smooth.
 - g. Except where slope is shown or indicated on the Drawings, finish edges flush at structural element, or equipment item.
 - h. Protect installed grout against rapid moisture loss by covering with wet rags or polyethylene sheets.
 - i. Wet-cure grout for not less than seven days.

3.4 FIELD QUALITY CONTROL

- A. Field Tests and Inspections:
- 1. Testing Laboratory Retained by Owner:
 - a. Owner has the option to employ and pay for services of grout testing laboratory to perform testing of grout Work at the Site.
 - b. Contractor shall cooperate and coordinate with concrete or grout testing laboratory relative to obtaining and testing samples.
 - c. Strength Testing:
 - 1) Frequency of testing:
 - a) All other concrete or grout:

- (1) One strength test specimen will be obtained not less than once per day during which concrete or grout is placed, and not less than once for each 30 cubic yards of material or fraction thereof placed in any one day during which concrete or grout is placed.
 - (2) In accordance with ASTM C109.
 - d. Slump test:
 - 1) In accordance with ASTM C143.
 - 2) Slump test will be performed for each strength test specimen.
 - 3) Additional slump tests may be performed.
 - e. Temperature: Concrete or grout temperature will be obtained for each strength test specimen.
- 2. Evaluation of Tests:
 - a. Strength Test Results:
 - 1) Average of 28-day strength of two specimens from each sample.
 - a) If one specimen evidences improper sampling, molding, handling, consolidation, curing, or testing, results reported shall be for other, properly made test specimens obtained at the same time and location as the improper specimen.
 - b) If both specimens evidence defects, test will be discarded.
- 3. Acceptance of Concrete or Grout:
 - a. Reported strength of each type of concrete will be acceptable when the following are satisfied:
 - 1) Average of all sets of three consecutive strength tests equals or exceeds required 28-day compressive strength.
 - 2) No individual strength test falls below required 28-day compressive strength by more than 500 psi.
 - b. If tests do not indicate acceptable strength, perform additional tests, and implement remedial measures, as required by Engineer.
 - 1) Perform additional testing and implement remedial measures, at no additional cost to Owner. Contractor is solely responsible for costs and time impacts arising from unacceptable concrete test results and defective Work.

3.5 SCHEDULES

A. Grout:

- 1. Non-shrink, non-metallic grout: General use.

END OF SECTION

This page intentionally left blank.

SECTION 03 15 19

ANCHORAGE TO CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Requirements for anchorages in concrete, including: cast-in-place anchor bolts, anchor rods, reinforcing anchorage adhesive, and post-installed concrete anchors required for the Project but not specified elsewhere in the Contract Documents.
2. Delegated design requirements for concrete anchors not expressly shown or indicated on the Drawings or elsewhere in the Contract Documents, including, but not limited to, anchorages in concrete for the following structural and nonstructural components:
 - a. Structural members and accessories.
 - b. Metal, wood, and plastic fabrications.
 - c. Architectural Work, including building components, finishes, specials, facility equipment and conveying equipment, furnishings, and special construction Work.
 - d. Mechanical and electrical Work, including process-mechanical Work, site and infrastructure Work, electrical Work, communications Work, electronic safety and security systems Work, and others.
 - e. Fire suppression, plumbing, and HVAC Work.
 - f. Other components requiring anchorages to concrete.

1.2 REFERENCES

A. Definitions and Terminology:

1. This provision presents definitions and terminology, which have the meanings indicated in this provision, applied to the singular or plural thereof, and without regard to use of initial capital letters.
 - a. Adhesive Anchors:
 - 1) Post-installed anchors developing their strength primarily from chemical bond between the concrete and the anchor.
 - 2) Includes anchors using acrylics, epoxy and other similar adhesives.
 - b. Anchor Bolt: Any cast-in-place anchorage that is made of a headed (i.e. bolt) material.
 - c. Anchor Rod: Any cast-in-place or post-installed anchorage made from unheaded, threaded, rod or deformed bar material.
 - d. Concrete Anchor: Generic term for either an anchor bolt or an anchor rod.
 - e. Galvanizing: Hot-dip galvanizing in accordance with ASTM A123, ASTM A153 or ASTM F2329 with minimum coating of 2.0 ounces of zinc per square foot of metal (average of specimens) unless noted otherwise or dictated by reference standard.
 - f. Hardware: As defined in ASTM A153.
 - g. MP11: Manufacturer's printed installation instructions.
 - h. Mechanical Anchors:
 - 1) Post-installed anchors developing their strength from attachment other than thru adhesives or chemical bond to concrete.
 - 2) Includes expansion anchors, expansion sleeve, screw anchors, undercut anchors, specialty inserts and other similar types of anchorages.
 - 3) Drop-in anchors and other similar non-ICC ES approved anchors are unacceptable.
 - i. Post-Installed Anchor: Adhesive or mechanical anchor installed into previously placed and adequately cured concrete.

B. Reference Standards:

1. American Concrete Institute (ACI):
 - a. 318, Building Code Requirements for Structural Concrete and Commentary.
2. American Concrete Institute/Concrete Reinforcing Steel Institute (ACI-CRSI):
 - a. Adhesive Anchor Installation Certification Program: Adhesive Anchor Installer.
3. American Institute of Steel Construction (AISC):
 - a. 303, Code of Standard Practice for Steel Buildings and Bridges.
 - b. 355.2, Seismic Testing of Post-Installed Concrete and Masonry Anchors in Cracked Concrete.
 - c. 355.4, Qualification of Post-Installed Adhesive Anchors in Concrete.
4. ASTM International (ASTM):
 - a. A36, Standard Specification for Carbon Structural Steel.
 - b. A108, Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished.
 - c. A123, Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
 - d. A153, Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
 - e. A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - f. A496, Standard Specification for Steel Wire, Deformed, for Concrete Reinforcement.
 - g. A563, Standard Specification for Carbon and Alloy Steel Nuts.
 - h. A780, Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings.
 - i. F436, Standard Specification for Hardened Steel Washers.
 - j. F593, Standard Specification for Stainless Steel Bolts, Hex Cap Screws, and Studs.
 - k. F594, Standard Specification for Stainless Steel Nuts.
 - l. F1554, Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength.
 - m. F2329, Standard Specification for Zinc Coating, Hot-Dip, Requirements for Application to Carbon and Alloy Steel Bolts, Screws, Washers, Nuts, and Special Threaded Fasteners
5. International Code Council Evaluation Service (ICC-ES):
 - a. AC193, Acceptance Criteria for Mechanical Anchors in Concrete Elements.
 - b. AC308, Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements.

1.3 ADMINISTRATIVE REQUIREMENTS

A. Pre-Design Conference:

1. Pre-design conference for anchorages to concrete (where such anchorages are delegated design Work) is not required.

1.4 QUALITY ASSURANCE

A. Regulatory Requirements:

1. Code-required Special Instructions:
 - a. Special Inspection is required in accordance with the building code for all concrete anchorages.
 - b. Notify the Special Inspector that an inspection is required prior to concrete placement (or during post-installed anchorage installation).
 - c. See the "Field Quality Control" Article in "Part 3 – Execution" of this Section for additional requirements.

B. Qualifications:

1. Installer:

- a. Installer for post-installed anchors shall be trained by the manufacturer or certified by a training program approved by the Engineer.
- b. Installer for adhesive anchors installed in horizontal, upward incline, or overhead applications shall be certified by ACI-CRSI Adhesive Anchor Installation Certification Program.

1.5 SUBMITTALS

A. Action Submittals: Submit the following:

1. Shop Drawings:

- a. Submit schedule (table or listing) of types, sizes (diameter, length, embedment length), material, finish, and proposed manufacturers of anchorages to concrete to be provided. Apportion by Project-specific application (for example, "Anchorages for cooling water pumps in basement") and indicate where anchorages are fully-designed by Engineer and those for which final design was prepared by delegated design professional.
- b. Engineer's approval of such Shop Drawing will be only for anchorages fully designed by Engineer. For anchorages for which final design is by delegated design professional, include on such Shop Drawing delegated design professional's approval stamp.

2. Product Data: Submit as Action Submittals product data for anchorages to concrete fully designed by Engineer. For anchorages to concrete for which final design is by delegated design professional, submit as Informational Submittals bearing approval stamp of delegated design professional.

- a. Manufacturer's express, written acknowledgement that proposed items comply with referenced standards indicated in this Section and, as applicable, by delegated design professional.
- b. Manufacturer published data and information for each anchor.
 - 1) Clearly indicate items that are proposed for the Work. Neatly strike out or obscure materials and products not proposed.
- c. Manufacturer's published installation instructions and instructions for code-required special inspections and tests.
- d. Post-Installed Anchors: In addition, submit for each post-installed anchor system current ICC-ES report, indicating the following:
 - 1) Manufacturer's certification that anchors comply with requirements indicated in the Contract Documents.
 - 2) Performance data indicating that anchor is approved by its manufacturer for use in cracked concrete.
 - 3) Seismic design categories for which anchor system is approved by ICC-ES report.
- e. Anchorage layout drawings and details:
 - 1) Drawings showing location, configuration, spacing and edge distance.

3. Samples:

- a. Submit representative Samples of anchorages to concrete, when requested by Engineer. Engineer's approval of Samples will be for type and finish only.

B. Informational Submittals: Submit the following:

1. Supplier's Instructions:

- a. Submit manufacturer's published instructions for installation.

2. Field Quality Control Submittals:

- a. Submit written results of required field quality control activities indicated in this Section.

3. Reports of Supplier's Visits to Site:

- a. Submit each written report of visit to the Site by Supplier's factory trained representative and delegated design professional. For each, indicate date and time of visit, purpose of visit, observations made, decisions made, problems encountered, and other pertinent information.
4. Qualifications Statements:
 - a. Each installer.

PART 2 - PRODUCTS

2.1 MATERIALS – ALL ANCHORAGES

A. Materials – General:

1. This Article applies to all anchorages to concrete, regardless of whether fully designed by Engineer
2. Additional requirements for anchorages fully designed by Engineer are indicated in the following Article.
3. For structural applications, do not use powder actuated fasteners and other types of bolts or fasteners not specified in this Section unless approved by Engineer or otherwise required by the Contract Documents.

B. Description:

1. Provide anchorages to concrete, of the types shown or indicated, to secure to concrete materials, equipment, and appurtenances installed as part of the Work.
2. Locations where anchorages are required are generally shown or indicated on the Drawings. Where not shown or indicated on the Drawings provide anchorages or the types required for materials, equipment, and systems where such materials, equipment, and systems are shown on the Drawings.
3. Anchorages required include those for materials, equipment, and systems shown on the structural Drawings and Drawing other than the structural Drawings.

C. Cast-in-place Concrete Anchors:

1. Buildings, non-building structures, and equipment, unless otherwise specified:
 - a. ASTM F1554, Grade 36 or Grade 55 with weldability supplement S1 for galvanized threaded rods.
 - b. ASTM A307, Grade A for galvanized headed bolts.
2. All other cast-in-place concrete anchors:
 - a. Stainless steel with matching nut and washer.
 - b. Non-submerged application: ASTM F593, Type 316, minimum yield strength of 45,000 psi.

D. Post-Installed Mechanical and Adhesive Concrete Anchors:

1. Non-submerged application: ASTM F593, Type 316, minimum yield strength of 45,000 psi with matching nut and washer.
2. Post-installed anchors and related materials shall be listed by ICC-ES or Engineer-approved equivalent.

E. Reinforcing: Comply with Section 03 00 05 - Concrete.

F. Washers:

1. ASTM F436 unless indicated otherwise, finish to match bolt.
2. When stainless steel anchorage is provided for cast-in-place anchorages, provide washers of the same material and alloy as in the associated anchorage.
3. Plate washers: Minimum 1/2 inch thick fabricated ASTM A36 square plates as required.
4. Comply with manufacturer's written instructions for all post-installed anchorages.

G. Nuts:

1. ASTM A563 for cast-in-place anchorages.
2. When stainless steel anchorages are provided for cast-in-place anchorages, nuts shall comply with ASTM F594 and shall match material and alloy of the associated anchorage.
3. Follow manufacturer's requirements if using post-installed anchorage.

H. Galvanizing Repair Paint:

1. High zinc dust content paint for regalvanizing welds and abrasions.
2. ASTM A780.
3. Zinc content: Minimum 92 percent in dry film.
4. Products and Manufacturers: "ZRC Cold Galvanizing", by ZRC; or "High Performance Zinc Spray", by Clearco; or equal.

2.2 ANCHORAGES FULLY DESIGNED BY ENGINEER

A. When size, length, and details of anchorage are shown or indicated on the structural Drawings, such anchorages are considered as fully designed by Engineer of such anchorage is not required.

B. Manufacturers:

1. For post-installed anchor systems regardless of whether proposed manufacturer is indicated below, furnish as Submittal current evaluation agency report and anchor system is certified by ICC-ES for cracked concrete conditions.
2. Screw Anchors for Concrete:
 - a. Hilti:
 - 1) Kwik HUS-EZ Screw (ICC-ES ESR-3027).
 - b. Dewalt:
 - 1) Screw-Bolt+ (ICC-ES ESR-3889).
 - c. Simpson Strong-Tie:
 - 1) Titen HD (ICC-ES ESR-2713).
 - d. Or equal.
3. Requests, if any, for Engineer's approval of "or-equals" or substitutes shall indicate proposed anchor has at least the same tension and shear strength as the associated anchorage products indicated by name in this Article.

PART 3 - EXECUTION

3.1 PREPARATION

- A. For cast-in-place concrete anchorages, allow adequate time for proper installation, inspection, and observation prior to placing concrete.
- B. Prior to installation, inspect and verify areas and conditions under which concrete anchorages will be installed.
1. Notify Engineer of conditions detrimental to proper and timely completion of the Work.
 2. Do not proceed with the Work until unsatisfactory conditions are properly remedied.

3.2 INSTALLATION

A. Installation Requirements - General:

1. Install items in accordance with the Contract Documents, manufacturer's written instructions, and Laws and Regulations. Where such requirements conflict, obtain interpretation or clarification from Engineer prior to commencing the associated Work.
2. Perform the following unless shown or indicated otherwise:

- a. Provide stainless steel anchorages for connecting aluminum and steel members to concrete and masonry.
 - b. Provide washers for all anchorages.
 - c. Where exposed, extend threaded anchorage a minimum of 0.5 inch above top of fully-engaged nut. If anchorage is cut off to required maximum height, dress the threads to allow nuts to be removed without damage to nuts.
 - 3. Tightening of nuts: Do the following after nuts are snug-tightened down:
 - a. Upset anchorage threads to prevent nuts from backing off. Provide double nut or lock nut in lieu of upset threads for items that may require future removal.
 - b. For cast-in-place anchorages (excluding post-installed anchorages), tighten nuts an additional 1/8 turn beyond snug tight to prevent nuts from backing off.
 - c. When two nuts are used per concrete anchor above the base plate, tighten top nut an additional 1/8 turn to "lock" the two nuts together.
 - d. For post-installed anchorages, comply with MPII.
 - 4. Secure architectural components to avoid aesthetic distortion and to avoid overstressing fasteners from expansion, contraction, or installation.
- B. Cast-in-Place Anchorages:
- 1. Provide where anchor rods or anchor bolts are indicated on the Drawings, unless another anchor type is approved by Engineer.
 - 2. Provide concrete anchorages as shown on the Drawings or as required to secure the Work to concrete.
 - 3. Tie cast-in-place anchorage in position to embedded reinforcing steel using wire.
 - 4. Tack welding of anchorage is prohibited.
 - 5. Chase threads as required and coat projected portion of carbon steel anchors and nut threads with a heavy coat of clean grease after concrete has cured.
 - 6. Anchorage location Tolerance: in accordance with AISC 303.
 - 7. Provide steel or durable wood templates for all column and equipment anchorages. Place templates above top of concrete; do not impede proper concrete placement and consolidation.
- C. Mechanical Anchorages:
- 1. Use only where specifically indicated on the Drawings or when approved for use by the Engineer.
 - 2. Do not use where subjected to vibration.
 - 3. May be used in overhead applications.
 - 4. Contact Engineer for clarification when anchors will not be installed in compliance with manufacturer's printed installation requirements.
- D. Post-installed Anchorages:
- 1. For post-installed anchors, comply with MPII regarding hole diameter and depth required to fully develop the tensile strength of anchor or reinforcing bar.
 - 2. Use hammer drills to create holes.
 - 3. Properly clean out holes in accordance with the associated ICC-ES report using non-metallic, fiber bristle brush and compressed air, or as otherwise necessary to remove all loose material from each hole prior to installing anchor in the presence of Special Inspector.
 - 4. Adhesive Anchorages:
 - a. Provide only where specifically indicated on the Drawings or when approved for use by Engineer.
 - b. May be provided where subjected to vibration or at buried or submerged locations.

- c. Do not install for overhead applications or sustained tension loading conditions such as utility hangers.
 - d. Install adhesive anchors in concrete aged not less than 21 days.
- E. Finishes:
 - 1. Repair of damaged galvanized surfaces:
 - a. Prepare damaged surfaces by abrasive blasting or power sanding.
 - b. Repair damaged galvanized surfaces in accordance with ASTM A780.
 - c. Apply galvanizing repair paint to not less than 6 mils dry film thickness in accordance with galvanizing repair material manufacturer's instructions and ASTM A780.
- F. Ensure that embedded items are protected from damage and are not filled in with concrete or related materials.

3.3 FIELD QUALITY CONTROL

- A. Field Tests and Inspections:
 - 1. Tests and inspections of anchorages shall comply with ACI 355.2 and/or ACI 355.4 as applicable.
 - 2. Owner reserves the right to inspect and test completed anchorages at a minimum of 25 to 50 percent of provided anchorages.
- B. Supplier's services:
 - 1. Post-installed anchor manufacturer's representative shall demonstrate and observe the proper installation procedures for the post-installed anchors.
- C. Defective Work:
 - 1. Anchorages that do not successfully pass required field tests and inspections or that are otherwise deemed defective by Engineer shall be remedied, in accordance with the Contract Documents, at no cost to Owner.

3.4 CLEANING

- A. After concrete has been placed, remove protection and clean all anchorage of all concrete, dirt, and other foreign matter.

END OF SECTION

This page intentionally left blank.

SECTION 05 50 00
METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Custom fabricated metal items and certain manufactured units not otherwise indicated to be supplied under work of other Specification Sections.
 - a. Steel Grating.
 - b. Heavy-Duty Castings, Trench Covers, and Accessories.
 - c. Access Cover.
2. Design of all temporary bracing not indicated on Drawings.
3. Delegated design systems and components, including but not limited to:
 - a. Metal Stairs.
 - b. Landings.
 - c. Ladders.
 - d. Landing and Ladder gates.

B. Related Specification Sections include but are not necessarily limited to:

1. Section 03 00 05 - Concrete.
2. Section 03 15 19 - Anchorage to Concrete.

1.2 REFERENCES

A. Definitions:

1. Fasteners: As defined in ASTM F1789.
2. Galvanizing: Hot-dip galvanizing per ASTM A123/A123M or ASTM A153/A153M with minimum coating of 2.0 oz of zinc per square foot of metal (average of specimens) unless noted otherwise or dictated by standard.
3. Hardware: As defined in ASTM A153/A153M.
4. Installer or Applicator:
 - a. Installer or applicator is the person actually installing or applying the product in the field at the Project site.
 - b. Installer and applicator are synonymous.
5. PQR: Procedure Qualification Record.
6. MIC: Microbiologically induced corrosion.

B. Referenced Standards: Standards referenced in this section include, but are not necessarily limited to, the following:

1. American Institute of Steel Construction (AISC):
 - a. 325, Manual of Steel Construction.
 - b. 360, Specifications for Structural Steel Buildings (referred to herein as AISC Specification).
2. The American Ladder Institute (ALI):
 - a. A14.3, Ladders - Fixed - Safety Requirements.
3. American Society of Civil Engineers (ASCE):
 - a. 7, Minimum Design Loads for Buildings and Other Structures.
4. ASTM International (ASTM):

- a. A6, Standard Specification for General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling.
- b. A36, Standard Specification for Carbon Structural Steel.
- c. A47, Standard Specification for Ferritic Malleable Iron Castings.
- d. A48, Standard Specification for Gray Iron Castings.
- e. A53, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless.
- f. A108, Standard Specification for Steel Bar, Carbon and Alloy, Cold Finished.
- g. A123/A123M, Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- h. A153/A153M, Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- i. A197, Standard Specification for Cupola Malleable Iron.
- j. A269, Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service.
- k. A276, Standard Specification for Stainless Steel Bars and Shapes.
- l. A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 psi Tensile Strength.
- m. A312, Standard Specification for Seamless, Welded, and Heavily Cold Worked Austenitic Stainless Steel Pipes.
- n. A380/A380M, Standard Practice for Cleaning, Descaling, and Passivation of Stainless Steel Parts, Equipment, and Systems.
- o. A500, Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes.
- p. A501, Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing.
- q. A536, Standard Specification for Ductile Iron Castings.
- r. A554, Standard Specification for Welded Stainless Steel Mechanical Tubing.
- s. A572, Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Structural Steel.
- t. A563, Standard Specification for Carbon and Alloy Steel Nuts.
- u. A666, Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar.
- v. A668, Standard Specification for Steel Forgings, Carbon and Alloy, for General Industrial Use.
- w. A780, Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings.
- x. A786, Standard Specification for Hot-Rolled Carbon, Low-Alloy, High-Strength Low-Alloy, and Alloy Steel Floor Plates.
- y. A992, Standard Specification for Steel for Structural Shapes.
- z. A1064, Standard Specification for Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete.
- aa. A1011, Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength.
- bb. F436, Standard Specification for Hardened Steel Washers Inch and Metric Dimensions.
- cc. F467, Standard Specification for Nonferrous Nuts for General Use.
- dd. F468, Standard Specification for Nonferrous Bolts, Hex Cap Screws, and Studs for General Use.

- ee. F593, Standard Specification for Stainless Steel Bolts, Hex Cap Screws, and Studs.
- ff. F835, Standard Specification for Alloy Steel Socket Button and Flat Countersunk Head Cap Screws.
- gg. F879, Standard Specification for Stainless Steel Socket Button and Flat Countersunk Head Cap Screws.
- hh. F1789, Standard Terminology for F16 Mechanical Fasteners.
- ii. F3125, Standard Specification for High Strength Structural Bolts, Steel and Alloy Steel, Heat Treated, 120 ksi (830 MPa) and 150 ksi (1040 MPa) Minimum Tensile Strength, Inch and Metric Dimensions.
- 5. American Welding Society (AWS):
 - a. A5.1/A5.1M, Specification for Carbon Steel Electrodes for Shielded Metal Arc Welding.
 - b. B2.1, Specification for Welding Procedure and Performance Qualification.
 - c. D1.1, Structural Welding Code - Steel.
 - d. D1.2, Structural Welding Code - Aluminum.
 - e. D1.6/D1.6M, Structural Welding Code - Stainless Steel.
- 6. National Association of Architectural Metal Manufacturers (NAAMM):
 - a. AMP 510, Metal Stairs Manual.
 - b. AMP 555, Code of Standard Practice for the Architectural Metal Industry (Including Miscellaneous Iron).
 - c. MBG 531, Metal Bar Grating Manual.
- 7. NACE International (NACE).
- 8. Nickel Development Institute (NiDI):
 - a. Publication 11 007, Guidelines for the Welded Fabrication of Nickel-Containing Stainless Steels for Corrosion Resistant Services.
- 9. Occupational Safety and Health Administration (OSHA):
 - a. 29 CFR 1910, Occupational Safety and Health Standards, referred to herein as OSHA Standards.

1.3 SUBMITTALS

A. Action Submittals: Submit the following:

- 1. Shop Drawings:
 - a. Fabrication and/or layout drawings and details:
 - 1) Submit drawings for all fabrications and assemblies.
 - a) Include erection drawings, plans, sections, details and connection details.
 - 2) Identify materials of construction, shop coatings and third party accessories.
- 2. Product technical data (for fabrications not delegated design) including:
 - a. Acknowledgement that products submitted meet requirements of standards referenced.
 - b. Manufacturer's installation instructions.
 - c. Provide manufacturer's standard allowable load tables for the following:
 - 1) Grating and checkered plate.
 - 2) Castings, trench covers and accessories.
- 3. Delegated Design Professional's "Instruments of Service" Submittals:
 - a. Design drawings sealed and signed by delegated design professional, including:
 - 1) Design drawings deemed appropriate and necessary by delegated design professional.
 - 2) Show or indicate necessary details establishing the method of fastening throughout system and attachments to supporting primary structure including anchorage to concrete as required.

- 3) Coordinate drawings and details with delegated design professional's calculations required in this Section.
 - 4) At option of Contractor or fabricator, design drawings may be combined with the Shop Drawings required in this Section, although delegated design professional's seal and signature is required on the Shop Drawings in the event of a combined Submittal.
 - b. Design specifications, sealed and signed by delegated design professional.
 - c. Provide the following with Delegated Designs:
 - 1) List of design loads and load combinations used to design structural systems and components.
 - 2) List of loads transmitted to the supporting structural elements.
 - 3) Compliance with project performance and design criteria specified in the Contract Documents.
 - 4) Expressly indicate where structural element reaction forces to Engineer-designed supporting elements or existing construction differ from reaction forces indicated in the Contract Documents.
- B. Informational Submittals:
1. Supplier's Instructions:
 - a. Fabricator's instructions for handling, storing, and installing structural elements furnished.
 - b. Galvanizing repair paint manufacturer's installation instructions.
 2. Qualifications Statements:
 - a. Delegated design professional.
 - b. Fabricator, when requested by Engineer, including:
 - 1) Qualifications and experience.
 - 2) Qualifications of welders to be employed in fabricating the structural elements for the Project.
 - 3) Qualifications of welders to be employed during erection of the structural elements for the Project.
 - c. Installer, when requested by Engineer, including fabricator's approval of installer.
 3. Delegated design Shop Drawings approved by delegated design professional:
 - a. Detailed structural elements erection drawings, shop details, erection detail.
 - b. Indicate member type, location, spacing, size, and gauge of members; method of attachment to supporting members; and necessary erection details.
 - c. Show and indicate supplemental bracing, strapping, splices, bridging, accessories, and details necessary for proper installation.
 - d. Structural element Placement Diagram: Diagram showing and indicating assumed location of each structural element and references the corresponding structural element design drawing.
 4. Delegated design product data approved by delegated design professional:
 - a. Fabricator's published product data for each type of structural element and accessory required.
 - b. Expressly indicate compliance with applicable reference standards. If not addressed in fabricator's published information, submit as special certification addressing compliance with reference standards indicated in this Section.
 - c. Published product data for galvanizing repair paint.
 5. Provide the following with Delegated Designs calculations
 - a. Complete set of design calculations, indicating:
 - 1) Basis of design, including a list of codes and standards used for design.

- 2) List of design loads and load combinations.
- 3) Design moments, shear forces, and axial compression/tension forces.
- 4) Design of connections, including splices, if required.
- 5) Bridging and bracing design, including attachments to trusses and anchorage to supporting structural elements, if required.
- 6) Special requirements, if any.

1.4 QUALITY ASSURANCE

A. Regulatory Requirements:

1. Applicable construction codes including building code, are indicated –in the contract documents..

B. Qualifications:

1. Welders:
 - a. Each welder employed on the Work shall possess current, valid certification in accordance with AWS D1.1/D1.1M and AWS B2.1/B2.1M.
 - b. Upon Engineer's request, submit documentation of welders' qualifications, in accordance with requirements of this provision.
2. Fabricator shall have minimum of 10 years of experience in fabrication of metal items specified.
3. Engineer for contractor-designed systems and components: Professional structural engineer licensed in the State of North Carolina.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and handle fabrications to avoid damage.
- B. Store above ground on skids or other supports to keep items free of dirt and other foreign debris and to protect against corrosion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Subject to compliance with the Contract Documents, the following manufacturers are acceptable:
 1. Mechanical anchor bolts:
 - a. See Section 03 15 19.
 2. Epoxy adhesive anchor bolts:
 - a. See Section 03 15 19.
 3. Concrete screw anchors:
 - a. See Section 03 15 19.
 4. Galvanizing repair paint:
 - a. Aervoe Industries, Inc.
 - b. ZRC Products.

2.2 MATERIALS

A. Steel:

1. Structural:
 - a. W-shapes and WT-shapes: ASTM A992, Grade 50.
 - b. All other plates and rolled sections: ASTM A36.
2. Pipe: ASTM A53, Types E or S, Grade B or ASTM A501.

3. Structural tubing:
 - a. ASTM A500, Grade B (46 ksi minimum yield).
 4. Bolts, high strength:
 - a. ASTM F3125, Grade A325.
 5. Nuts, high strength:
 - a. ASTM A563.
 6. Washers (hardened):
 - a. ASTM F436.
 - b. Provide two (2) washers with all bolts.
 7. Bolts and nuts (unfinished):
 - a. ASTM A307, Grade A.
 8. Welding electrodes: AWS D1.1, E70 Series.
 9. Steel forgings: ASTM A668.
- B. Iron:
1. Ductile iron: ASTM A536.
 2. Gray cast iron: ASTM A48 (minimum 30,000 psi tensile strength).
 3. Malleable iron: ASTM A47, ASTM A197.
- C. Stainless Steel:
1. Stainless steel in welded applications: Low carbon 'L' type.
 2. Minimum yield strength of 30,000 psi and minimum tensile strength of 75,000 psi.
 - a. Bars, shapes: ASTM A276, Type 316.
 - b. Tubing and pipe: ASTM A269, ASTM A312 or ASTM A554, Type 316.
 - c. Strip, plate and flat bars: ASTM A666, Type 316.
 - d. Bolts and nuts: ASTM F593, Type 316.
 3. Welding electrodes: In accordance with AWS for metal alloy being welded.
- D. Washers: Same material and alloy as found in accompanying bolts and nuts.
- E. Mechanical Anchor Bolts and Adhesive Anchor Bolts:
1. See Specification Section 03 15 19.
- F. Iron and Steel Hardware: Galvanized in accordance with ASTM A153/A153M when required to be galvanized.
- G. Galvanizing Repair Paint:
1. High zinc dust content paint for regalvanizing welds and abrasions.
 2. ASTM A780.
 3. Zinc content: Minimum 92% in dry film.
 4. ZRC "ZRC Cold Galvanizing" or Aervoe "Crown Cold Galvanize Coating 93% Zinc Rich."

2.3 FABRICATION

- A. Verify field conditions and dimensions prior to fabrication.
- B. Form materials to shapes indicated with straight lines, true angles, and smooth curves.
 1. Grind smooth all rough welds and sharp edges.
 - a. Round all corners to approximately 1/32 inches nominal radius.
- C. Provide drilled or punched holes with smooth edges.
 1. Punch or drill for field connections and for attachment of work by other trades.

D. Weld Shop Connections:

1. Connections subject to the following visual and welding requirements:
 - a. Fabricator
 - 1) Fabricator shall have QC program and procedures in place to avoid cross contamination of stainless-steel products with carbon steel products and material if shop fabricates products other than stainless steel.
 - b. Weld Procedures
 - 1) Weld procedures shall be qualified for all positions that will be welded, qualified by testing in accordance with applicable welding codes AWS D1.1, D1.2 and D1.6 requirements.
 - 2) Procedure Qualification Record (PQR) shall document all essential variables to perform consistent quality welds. PQR shall include maximum heat input per pass and shall be tested for CVN properties, macro hardness, and macro/micro hardness testing.
2. Welds shall be continuous fillet type unless indicated otherwise.
3. Full penetration butt weld at bends in stair stringers and ladder side rails.
4. Weld structural steel in accordance with AWS D1.1 using Series E70 electrodes conforming to AWS A5.1/A5.1M.
5. Weld aluminum in accordance with AWS D1.2.
6. Weld stainless steel in accordance with AWS D1.6.
7. Grind smooth welds that will be exposed.
8. Make provisions to prevent carbon steel/free iron contamination of stainless steel surfaces (i.e., contact between carbon steel or iron and stainless steel component). Do not use cutting/grinding/drilling tools, wire brushes, or wire wheels on stainless steel that have been previously used on carbon steel or iron. Do not support or hang stainless steel weldments or fixtures with carbon steel cables or dunnage.
9. Passivate stainless steel items and stainless steel welds after they have been ground smooth, in accordance with ASTM A380/A380M.
10. Passivation Requirements:
 - a. For components/assemblies to be used only in indoor conditioned spaces:
 - 1) No post-fabrication passivation treatments are required for external corrosion control.
 - b. Components for use in environments other than indoor conditioned spaces, shall be subjected to a post-fabrication passivation treatment in accordance with ASTM A380. Following cleaning/passivation, the passivated area shall be evaluated for the effectiveness of cleaning/passivation per one of the Tests for Free Iron shown in Section 7 of ASTM A380 (e.g., Water-Wetting and Drying test, Copper Sulfate test, etc.).

E. Conceal fastenings where practicable.

F. Fabricate work in shop in as large assemblies as is practicable.

G. Tolerances:

1. Rolling:
 - a. ASTM A6.
 - b. When material received from the mill does not satisfy ASTM A6 tolerances for camber, profile, flatness, or sweep, the Contractor is permitted to perform corrective work by the use of controlled heating and mechanical straightening, subject to the limitations of the AISC Specification.
2. Fabrication tolerance:
 - a. Member length:

- 1) Both ends finished for contact bearing: 1/32 inches.
 - 2) Framed members:
 - a) 30 feet or less: 1/16 inches.
 - b) Over 30 feet: 1/8 inches.
 - b. Member straightness:
 - 1) Compression members: 1/1000 of axial length between points laterally supported.
 - 2) Non-compression members: ASTM A6 tolerance for wide flange shapes.
 - c. Specified member camber (except compression members):
 - 1) 50 feet or less: -0/+1/2 inches.
 - 2) Over 50 feet: -0/+1/2 inches (+1/8 inches per 10 feet over 50 feet).
 - 3) Members received from mill with 75% of specified camber require no further cambering.
 - 4) Beams/trusses without specified camber shall be fabricated so after erection, camber is upward.
 - 5) Camber shall be measured in fabrication shop in unstressed condition.
 - d. At bolted splices, depth deviation shall be taken up by filler plates.
 - 1) At welded joints, adjust weld profile to conform to variation in depth.
 - 2) Slope weld surface per AWS requirements.
 - e. Finished members shall be free from twists, bends and open joints.
 - 1) Sharp kinks, bends and deviation from above tolerances are cause for rejection of material.
- H. Fabricate grating, checkered plate, stairs, ladders and accessories using stainless steel unless shown otherwise on Drawings.
1. Finish:
 - a. Mill, unless noted otherwise.
 - b. Coat surfaces in contact with dissimilar materials.

2.4 SOURCE QUALITY CONTROL

- A. Surface Preparation:
1. All miscellaneous metal fabrication item surfaces shall be observed and approved, prior to application of shop-applied coatings, by a NACE Certified Coatings Specialist (CIP-3) with at least 4 years of experience in similar inspections.
 - a. Inspection shall be performed to determine depth of blast profile and cleanliness of surface.
 - b. Fabricator shall reblast and or re-clean surfaces as required until acceptable.
- B. Shop Applied Coating Application:
1. After surface has been accepted in writing by NACE certified coatings inspector, fabricator may proceed with application of coatings.
 2. Application of coatings shall be observed and certified by NACE certified coatings inspector.
- C. Shop Inspection and Testing:
1. Owner will employ and pay for the services of a qualified independent testing agency to inspect and test all structural steel work for compliance with Contract Documents.
 2. Contractor responsible for testing to qualify shop and field welders and as needed for Contractor's own quality control to ensure compliance with Contract Documents.
 3. Independent testing agency shall have a minimum of five years performing similar work and shall be subject to Owner's approval.
- D. Responsibilities of Testing Agency:

1. Inspect shop and field welding in accordance with AWS Code including the following non-destructive testing:
 - a. Visually inspect all welds.
 - b. In addition to visual inspection, test 50% of full penetration welds and 20% of fillet welds with liquid dye penetrant or mag particle.
 - c. Test 20% of liquid dye penetrant tested full penetration welds with ultrasonic or radiographic testing.
 - d. For all surfaces intended to be immersed or intended to be watertight:
 - 1) 100% of all fillet welds shall be PT tested to ensure water-tight surfaces are free of surface defects that would create areas for MIC.
 - 2) 100% of all completed SS welds and material shall be passivated in accordance with ASTM A380/A380M.
2. Inspect high-strength bolting in accordance with the RCSC Specification for Structural Joints Using High-Strength Bolts, Section 9.
 - a. Verify direct tension indicator gaps, if applicable.
3. Inspect structural steel which has been erected.
4. Inspect stud welding in accordance with AWS Code.
5. Prepare and submit inspection and test reports to Engineer.
 - a. Assist Engineer to determine corrective measures necessary for defective work.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Provide items to be built into other construction in time to allow their installation.
 1. If such items are not provided in time for installation, cut in and install.
- B. Prior to installation, inspect and verify condition of substrate.
- C. Correct surface defects or conditions which may interfere with or prevent a satisfactory installation.
 1. Field welding aluminum is not permitted unless approved in writing by Engineer.

3.2 INSTALLATION

- A. Set metal work level, true to line, plumb.
 1. Shim and grout as necessary.
- B. Contractor is solely responsible for safety.
 1. Construction means and methods and sequencing of work is the prerogative of the Contractor.
 2. Take into consideration that full structural capacity of many structural members is not realized until structural assembly is complete; e.g., until slabs, decks, and diagonal bracing or rigid connections are installed.
 3. Partially complete structural members shall not be loaded without an investigation by the Contractor.
 4. Until all elements of the permanent structure and lateral bracing system are complete, temporary bracing for the partially complete structure will be required.
- C. Adequate temporary bracing to provide safety, stability and to resist all loads to which the partially complete structure may be subjected, including construction activities and operation of equipment is the responsibility of the Contractor.
 1. Plumb, align, and set structural steel members to specified tolerances.

2. Use temporary guys, braces, shoring, connections, etc., necessary to maintain the structural framing plumb and in proper alignment until permanent connections are made, the succeeding work is in place, and temporary work is no longer necessary.
 3. Use temporary guys, bracing, shoring, and other work to prevent injury or damage to adjacent work or construction from stresses due to erection procedures and operation of erection equipment, construction loads, and wind.
 4. Contractor shall be responsible for the design of the temporary bracing system and must consider the sequence and schedule of placement of such elements and effects of loads imposed on the structural steel members by partially or completely installed work, including work of all other trades.
 - a. If not obvious from experience or from the Drawings, confer with the Engineer to identify those structural steel elements that must be complete before the temporary bracing system is removed.
 5. Remove and dispose of all temporary work and facilities off-site.
- D. Examine work-in-place on which specified work is in any way dependent to ensure that conditions are satisfactory for the installation of the work.
1. Report defects in work-in-place which may influence satisfactory completion of the work.
 2. Absence of such notification will be construed as acceptance of work-in-place.
- E. Field Measurement:
1. Take field measurements as necessary to verify or supplement dimensions indicated on the Drawings.
 2. Contractor responsible for the accurate fit of the work.
- F. Check the elevations of all finished footings or foundations and the location and alignment of all anchor bolts before starting erection.
1. Use surveyor's level.
 2. Notify Engineer of any errors or deviations found by such checking.
- G. Framing member location tolerances after erection shall not exceed the frame tolerances listed in the FIELD QUALITY CONTROL Article in PART 3 of this Specification Section.
- H. Erect plumb and level; introduce temporary bracing required to support erection loads.
- I. Use light drifting necessary to draw holes together.
1. Drifting to match unfair holes is not allowed.
- J. Welding:
1. Comply with AWS D1.1, AWS D1.2, and AWS D1.6 (as applicable for the material welded) and requirements of this Section's "Fabrications" Article in "Part 2 - Products".
 2. When joining two sections of steel of different ASTM designations, welding techniques shall be in accordance with a qualified AWS D1.1 procedure.
 3. 100% of all completed stainless steel welds and material shall be passivated in accordance with ASTM A380/A380M.
- K. Shore existing members when unbolting of common connections is required.
1. Use new bolts for rebolting connections.
- L. Clean stored material of all foreign matter accumulated prior to the completion of erection.
- M. Bolt Field Connections: Where practicable, conceal fastenings.
- N. Field Welding:
1. Follow AWS procedures.
 2. Grind welds smooth where field welding is required.

3. 100% of all completed stainless steel welds and material shall be passivated in accordance with ASTM A380/A380M.
- O. Field cutting grating or checkered plate to correct fabrication errors is not acceptable.
1. Replace entire section.
- P. Remove all burrs and radius all sharp edges and corners of miscellaneous plates, angles, framing system elements, etc.
- Q. Unless noted or specified otherwise:
1. Connect steel members to steel members with 3/4 inches diameter ASTM F3125, Grade A325 high strength bolts.
 2. Connect aluminum to aluminum with 3/4 inches diameter stainless bolts.
 3. Connect aluminum to structural steel using 3/4 inches diameter stainless steel bolts.
 - a. Provide dissimilar metals protection.
 4. Connect aluminum and steel members to concrete and masonry using stainless steel mechanical anchor bolts or adhesive anchor bolts unless shown otherwise.
 - a. Provide dissimilar materials protection.
 5. Provide washers for all bolted connections.
 6. Where exposed, bolts shall extend a maximum of 3/4 inches and a minimum of 1/2 inches above the top of installed nut.
 - a. If bolts are cut off to required maximum height, threads must be dressed to allow nuts to be removed without damage to the bolt or the nuts.
- R. Install and tighten ASTM F3125, Grade A325 high-strength bolts in accordance with the AISC 325, Allowable Stress Design (ASD).
1. Provide hardened washers for all Grade A325 bolts.
 - a. Provide the hardened washer under the element (nut or bolt head) turned in tightening.
- S. After bolts are tightened, upset threads of ASTM A307 bolts or anchor bolts to prevent nuts from backing off.
- T. Secure metal to wood with lag screws of adequate size with appropriate washers.
- U. Do not field splice fabricated items unless said items exceed standard shipping length or change of direction requires splicing.
1. Provide full penetration welded splices where continuity is required.
- V. Provide each fabricated item complete with attachment devices as indicated or required to install.
- W. Anchor such that work will not be distorted nor fasteners overstressed from expansion and contraction.
- X. Set beam and column base plates accurately on nonshrink grout as indicated on Drawings.
1. See Division 03 Specification Sections for non-shrink grout and anchorage.
 2. Set and anchor each base plate to proper line and elevation.
 - a. Use metal wedges, shims, or setting nuts for leveling and plumbing columns and beams.
 - 1) Wedges, shims and setting nuts to be of same metal as base plate they support.
 - 2) Tighten nuts on anchor bolts.
 - b. Fill space between bearing surface and bottom of base plate with nonshrink grout.
 - 1) Fill space until voids are completely filled and base plates are fully bedded on wedges, shims, and grout.
 - c. Do not remove wedges or shims.

- 1) Where they protrude, cut off flush with edge of base plate.
 - d. Fill sleeves around anchor bolts solid with non-shrink grout.
- Y. Repair damaged galvanized surfaces in accordance with ASTM A780.
1. Prepare damaged surfaces by abrasive blasting or power sanding.
 2. Apply galvanizing repair paint to minimum 6 mils DFT in accordance with manufacturer's instructions.

3.3 FIELD QUALITY CONTROL

- A. Owner Pays for Field Inspection and Testing:
1. Owner will employ and pay for services of an independent testing agency to inspect and test structural elements shop and field work for compliance with this Specification Section.
 2. Contractor provides sufficient notification and access so inspection and testing can be accomplished.
 3. Contractor pays for retesting of failed tests and for additional testing required when defects are discovered.

3.4 CLEANING

- A. After fabrication, erection, installation, or application, clean all miscellaneous metal fabrication surfaces of all dirt, weld slag and other foreign matter.

END OF SECTION

SECTION 06 10 00
ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Furnish labor, materials, tools, equipment, and services for Rough Carpentry, as indicated, in accordance with provisions of Contract Documents.
- B. Completely coordinate with work of other trades.

1.2 REFERENCES

- A. Lumber Grading Rules and Species:
 - 1. US Department of Commerce (DOC):
 - a. PS 20 American Softwood Lumber Standard.
 - 2. Western Wood Products Association (WWPA).
 - 3. Southern Forest Products Association (SFPA).
- B. Plywood Grading Rules and Recommendations:
 - 1. US Department of Commerce (DOC):
 - a. Softwood plywood: PS1 Structural Plywood.
 - 2. American Plywood Association (APA).
- C. Preservative and Fire Retardant Treatment Standards:
 - 1. American Wood Protection Association (AWPA):
 - a. AWPA U1 User Specification for Treated Wood.
 - b. AWPA T1 Processing and Treatment Standard.
 - 2. Underwriters Laboratories (UL)
 - 3. ASTM International requirements:
 - a. ASTM E84 Standard Test Method for Surface Burning Characteristics
 - b. ASTM D2898 Standard Method of Accelerated Weathering of Fire Retardant Treated Wood for Fire Testing
 - c. ASTM D3201 Standard Test Method for Hygroscopic Properties of Fire-Retardant Wood and Wood-Based Products

1.3 SUBMITTALS

- A. Product Data:
 - 1. For each type of material and accessory.
- B. Shop Drawings:
 - 1. Fabricated items.
 - 2. Fastener Patterns: Full-size templates for fasteners in exposed framing.
- C. Project Information:
 - 1. Certification of fire retardant treated material.
 - 2. Certification of preservative treated material.

1.4 QUALITY ASSURANCE

- A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having jurisdiction that

periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.

B. Factory Marking:

1. Identify type, grade, moisture content, inspection service, producing mill, and other qualities.
2. Mark each piece of fire retardant treated material with Underwriters Laboratory Classification mark and fire-retardant treatment for identification.
3. International Building Code (IBC):
 - a. Requirements for identification and labeling.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Preservative Treated Lumber and Plywood:

1. Base:
 - a. Hoover Treated Wood Products.
2. Optional:
 - a. Arxada.
 - b. Koppers Performance Chemicals.
 - c. Stella-Jones, Inc.
 - d. Viance, LLC.

2.2 MATERIALS

A. Dimensional Lumber and Plywood:

1. Thoroughly seasoned, non-treated, well-fabricated materials.
2. Longest practical lengths and sizes.
3. Application, except where treated types are indicated:
 - a. Non-structural framing, blocking, backing, nailers, grounds, and similar members.
 - b. Other locations where indicated.

B. Preservative Treated Lumber and Plywood:

1. Natural wood products treated to add decay and termite resistance.
2. Use appropriate materials for application by listed Manufacturers.
3. Preservatives:
 - a. Compatible with direct exposure to precipitation, sunlight, and effects of weather.
 - b. Authenticate by factory marking each piece with manufacturer's mark and applicable standards.
 - c. Acceptable treatments:
 - 1) Alkaline Copper Quaternary (ACQ).
 - 2) Copper Azole (CA).
 - 3) Wolman AG non-metallic preservative.
4. Lumber Species:
 - a. Hem-Fir.
 - b. Spruce.
 - c. Pine.
 - d. Other species meeting requirements.

5. Plywood:
 - a. Grading:
 - 1) PS1, B-C Grade.
 - 2) PS1, A-C Grade where exposed.
 - b. Veneers:
 - 1) Softwood species.
 - 2) Glue with waterproof adhesives.
6. Application:
 - a. Below grade, or in contact with earth.
 - b. Where indicated in Drawings.
- C. Adhesives for bonding furring, sleepers, sills, and similar items to concrete or masonry:
 1. Approved for indicated use by adhesive manufacturer.
 2. Comply with ASTM D3498.

2.3 FASTENERS

- A. General:
 1. Provide fasteners of size and type indicated that comply with requirements specified for material and manufacture.
 2. Where rough carpentry is exposed to weather, in contact with earth, pressure-preservative treated, or in area of high relative humidity:
 - a. Use fasteners with hot dip zinc coating complying with ASTM A153.
 - b. Use fasteners of Type 304 stainless steel.
- B. Nails, Brads, and Staples: ASTM F1667.
- C. Power-Driven Fasteners: NES NER-272.
- D. Wood Screws: ASME B18.6.1.
- E. Lag Bolts: ASME B18.2.1.
- F. Bolts: ASTM A307, Grade A steel bolts with ASTM A563 hex nuts and washers.
- G. Expansion Anchors:
 1. Tested in accordance with ASTM E488.
 2. Anchor bolt and sleeve assembly:
 - a. Masonry assemblies: Sustain load equal to 6 times load imposed when installed in unit.
 - b. Concrete assemblies: Sustain load equal to 4 times load imposed when installed in unit.
 3. Interior applications:
 - a. Carbon-steel components.
 - b. Zinc plated to comply with ASTM B633, Class Fe/Zn 5.
 4. Exterior and wet applications:
 - a. Stainless Steel components, ASTM F593 and ASTM F594 Alloy Group 1 or 2.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Examine conditions under which work is to be installed.
- B. Verify measurements, dimensions, and details before proceeding.
- C. Coordinate location of furring, nailers, blocking, grounds, and similar supports.

D. Correct unsatisfactory conditions.

3.2 INSTALLATION OF ROUGH CARPENTRY

A. Form to shapes indicated.

B. Cut and fit accurately.

C. Set work to required levels and lines, plumb and true.

D. Shim as required.

E. Provide wood grounds or nailers as required for attachment of other work and surface applied items.

F. Grounds:

1. Dressed, key beveled lumber.

2. Minimum 1-1/2-inch 38 mm wide by thickness required to bring face of ground even with finish material.

3. Remove temporary grounds when no longer required.

G. Wall Blocking:

1. Provide in-wall fire-treated wood blocking reinforcement where following items are required to be wall-mounted to interior walls:

a. Architectural casework, millwork, cabinets, shelving, wardrobes, and bookcases.

b. Handrails at stairwells.

c. Between studs at height of wall-mounted door stop, behind stop.

H. Anchor work to support applied loading.

1. Provide washers under bolt heads and nuts.

2. Fasten plywood in accordance with APA recommendations.

3. Use fasteners of size that will not penetrate members where opposite side will be exposed to view or receive finish materials.

4. Predrill holes to avoid splitting wood with fasteners.

5. Do not drive threaded friction type fasteners.

3.3 INSTALLATION OF BLOCKING AND NAILERS FOR ROOFING AND PARAPETS

A. Install in accordance with ANSI/SPRI ES-1 Wind Design Standard for Edge Systems Used with Low Slope Roofing Systems.

B. Minimum Wood Member Size: 2 by 6-inch 50 mm x 150 mm nominal.

C. Fasteners:

1. Corrosion resistant.

a. Hot dip galvanized: Comply with ASTM A153 or ASTM A653, Class G185.

b. Stainless steel: Types 304 or 316.

2. Countersink heads of fasteners.

3. Types required for substrate conditions.

4. Fasteners of diameter and spacing required to resist forces indicated.

5. Spacing:

a. Threaded anchor bolts; 3/8-inch 9.5 mm or larger:

1) Provide 5/8-inch 16 mm OD washers or larger.

2) Maximum spacing: 48 inches 1200 mm OC.

3) Stagger 1/3 nailer width.

b. Other fastener types:

- 1) Maximum Spacing:
 - a) Typical: 12 inches 300 mm OC.
 - b) Up to 16 inches 400 mm OC where necessary to match spacing of structural members.
 - 2) Stagger 1/3 nailer width.
 - 3) Install 2 fasteners and within 6 inches 150 mm of nailer ends.
6. Anchor nailers to resist minimum vertical force of 300 pounds/LF 446 kg/M in any direction.
- a. Locate fasteners approximately 4 inches 100 mm from ends but not less than 3 inches 75 mm.
 - b. Use minimum of 3 anchors for each nailer.
 - c. Where members are wider than 6 inches 150 mm, stagger fasteners from side to side to avoid splitting of the wood member.
 - d. Corner region enhancements:
 - 1) Double the above listed vertical force which must be resisted.
 - 2) Length and width of corners as prescribed by ANSI/SPRI RP-4:
 - a) 40 percent of the building height, but not less than 8-1/2 feet 2.6 M.
- D. Nailers used for perimeter securement of roofing membranes:
1. Install nailers where indicated and where required to secure perimeter of membrane roofing.
 2. Match height of nailers to adjacent insulation.
 3. Where multiple layers are required to match depth of insulation:
 - a. Attach base layer as indicated in General Requirements above.
 - b. Apply a bead of construction adhesive between laminations.
 - c. Attach subsequent layers using fastener type which is appropriate for wood-to-wood securement.
 - d. Size and locate fasteners as required to resist uplift loading indicated.
- E. Install blocking as indicated for securement of sheet metal edge flashings, parapet copings, and similar items.

END OF SECTION

This page intentionally left blank.

SECTION 07 54 25
FULLY ADHERED TPO ROOFING

PART 1 - GENERAL

1.1 SUMMARY

- A. Furnish labor, materials, tools, equipment, and services for Fully Adhered TPO Roofing in accordance with provisions of Contract Documents.
- B. Completely coordinate with work of other trades.
 - 1. Ensure materials in this Section are compatible with adhesives, sealants, and adjacent materials.

1.2 REFERENCES

- A. ASTM International (ASTM):
 - 1. ASTM C1289, Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board.
 - 2. ASTM C1303 Standard Test Method for Predicting Long-Term Thermal Resistance of Closed-Cell Foam Insulation
 - 3. ASTM D6878 .
- B. American National Standards Institute (ANSI) / Single Ply Roofing Industry (SPRI):
 - 1. ANSI/SPRI ES-1 Wind Design Standard for Edge Systems Used with Low Slope Roofing Systems
- C. National Roofing Contractors Association (NRCA):
 - 1. Roofing and Waterproofing Manual.
- D. Sheet Metal and Air Conditioning Contractors' National Association (SMACNA):
 - 1. Architectural Sheet Metal Manual.
- E. Underwriters Laboratories (UL):
 - 1. UL 790, Standard for Tests for Fire Resistance of Roof Covering Materials.
- F. Factory Mutual (FM) Research Corporation (FM):
 - 1. FM 4470 Approval Standard for Class I Roof Covers.

1.3 SUBMITTALS

- A. Product Data:
 - 1. Manufacturer standard literature for vapor barrier, insulation, and roofing system components, including adhesives and accessories indicating compliance with specification requirements.
 - 2. Manufacturer standard literature for roof coping system indicating components and accessories including anchor plate configuration.
- B. Shop Drawings:
 - 1. Roof layout showing insulation thicknesses and details.
 - 2. Indicate location of expansion joints, crickets, saddles, curbs, walkways, safety tiebacks, vents, drains and other penetrations.
 - 3. Indicate slope direction, slope amount, and key vertical elevation points.
 - 4. Profiles of flashing assemblies.
 - 5. Installation Drawings.

- C. Samples:
 - 1. Roofing manufacturer's facsimile of each sheet metal color for pre-selection.
 - 2. 3 inches x 5 inches samples of roofing manufacturer's sheet metal color for final approval.
- D. Project Information:
 - 1. Provide FM endorsed confirmation of uplift ratings utilized in roof and coping system design.
- E. Contract Closeout Information:
 - 1. Warranty.
 - 2. Maintenance Data

1.4 QUALITY ASSURANCE

- A. Manufacturer authorized roofing installer.
- B. Component products made by single manufacturer or approved for use with warranted system.
- C. Concrete Moisture Vapor Testing:
 - 1. Coordinate maximum moisture allowed in concrete deck with roofing manufacturer.
- D. Fire Resistance Rating:
 - 1. UL 790, Class A.
- E. Hail Resistance Rating:
 - 1. Certify that roof system complies with requirements of FM for Severe hail (SH) resistance.

1.5 WARRANTY

- A. 15-year warranty of weathertightness signed by roofing materials manufacturer.
 - 1. Warranty to include coverage for peak gusts of wind to:
 - a. 55 mph at 33 feet above ground.
 - 2. Warranty to include the entire system: membrane, flashings, adhesives, sealants, counterflashings, insulation, fasteners, fastener plates, fastener strips, hard rubber or metal edging, metal termination bars, sheet metal copings and edge metal, and other material authorized by manufacturer.
- B. 20-year warranty on 70 percent PVDF (Kynar 500) coatings on edge metal and copings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Fully Adhered TPO Roofing:
 - 1. Base:
 - a. Carlisle SynTec Systems.
 - 2. Optional:
 - a. Holcim Elevate
 - b. GAF
 - c. Johns Manville
 - d. Versico.
- B. Sheathing:
 - 1. Base:
 - a. Georgia-Pacific.
 - 2. Optional:
 - a. Same as Membrane Manufacturer.

- b. USG Corporation.
 - c. National Gypsum.
- C. Vapor Retarder (VR):
 - 1. Base:
 - a. Same as Membrane Manufacturer.
- D. Walkways and Pavers:
 - 1. Base:
 - a. Same as Membrane Manufacturer.
- E. Sheet Metal Coping and Edge Metal:
 - 1. Base:
 - a. Provided by manufacturer of roofing system.
- F. Other Materials:
 - 1. Manufacturers as noted.

2.2 DESIGN CRITERIA

- A. Determine per Wind Load Design Guide for Low Sloped Flexible Membrane Roofing Systems published by SPRI.
- B. Design roof system and anchorage fastener type and spacing needed to resist uplift pressures including roof covering and metal edge securement to meet design loads and satisfy requirements of applicable building codes, local amendments, and ANSI/SPRI ES-1.
- C. Wind loads: Use the greater of the following:
 - 1. Wind pressures defined by Building Code as locally adopted and amended.
- D. Requirements applicable to designated warranty.
- E. Roof height and parapet height: As indicated.
- F. Static pressure of building interior: Less than 0.5 inches water.
- G. Design Fully Adhered TPO roofing and coping system uplift pressure to comply with:
 - 1. FM ratings indicated on the drawings. Approval rating areas shall be determined per FM prescriptive requirements based on minimum ratings provided on the drawings.

2.3 MATERIALS

- A. Vapor Retarder:
 - 1. Rubberized asphalt membrane adhered to polyethylene or polyolefin top sheet.
 - 2. 30 mil thick, minimum.
 - 3. Vapor Permeance: Not exceeding 0.05 Perm.
 - 4. UV protected for 90 day exposure.
 - 5. Primer or adhesive as recommended for substrate by manufacturer.
 - 6. Base Product: Carlisle 725TR.
- B. Roof Insulation:
 - 1. Furnished by roofing manufacturer.
 - 2. UL listed for assembly indicated.
 - 3. Provide crickets and saddles as required.
 - 4. Polyisocyanurate (PISO) roof insulation:
 - a. Rigid, closed cell foam core bonded to heavy-duty glass fiber mat facers.

- b. ASTM C1289 Type II, Class 1.
 - c. R-value: 5.6 per inch in accordance with ASTM C1303, CAN/ULC S770.
 - d. Compressive Strength: 20 psi minimum per ASTM D1621, Grade 2.
 - e. Dimensional stability: 2 percent maximum linear change in seven days per ASTM D2126.
 - f. Minimum insulation thickness:
 - 1) Match existing insulation thickness
 - g. Base Product: Insulbase polyisocyanurate by Carlisle SynTec.
- C. Coverboard:
 - 1. Moisture resistant gypsum core with fiberglass mat and non-asphaltic surfacing.
 - 2. Minimum Thickness: 5/8 inches.
 - 3. Base Product: DensDeck Prime Roof Board by Georgia-Pacific.
- D. TPO Roofing Membrane:
 - 1. Material: Thermoplastic Polyolefin (TPO) single-ply roofing membrane.
 - a. Fire Retardant.
 - b. Polyester fabric reinforced.
 - 2. Color: White.
 - 3. Thickness: 60 mil thick.
 - 4. Minimum Physical Properties:
 - a. Thickness over scrim: 15 mil by ASTM D4637.
 - b. Tearing Strength: 55 pounds MIN by ASTM D751.
 - c. Breaking Strength: 225 pounds MIN by ASTM D751.
 - d. Heat Aging: retain 90 percent of original Breaking Strength and Elongation values.
 - e. Weather Resistance: 10,080 kJ/m2 by ASTM G155.
 - 5. Base Product: SureWeld by Carlisle SynTec.
- E. Membrane flashings, fasteners, adhesives, tapes, cements, and sealants:
 - 1. Roofing manufacturer's standard.
- F. Edge Metal and Coping:
 - 1. Roofing Manufacturer's pre-engineered, prefabricated system for termination of roofing membrane.
 - 2. Field fabricated components approved by roofing manufacturer for warranted system.
 - 3. Fasteners concealed from view.
 - 4. Concealed splice plates, with color matching snap-on covers.
 - 5. Anchor cleats:
 - a. Material: G90 galvanized steel.
 - b. Thickness: 20 GA.
 - 6. Snap-on cover:
 - a. Material: G90 galvanized steel.
 - b. Thickness:
 - 1) For dimensions less than 10 inches: 24 GA.
 - 2) For dimensions 10 to 24 inches: 22 GA.
 - c. Finish: 70 percent PVDF Kynar 500.
 - d. Color:
 - 1) To be selected from manufacturers standard colors by Architect.

7. Wind Rating: Design for pressure indicated for balance of roof system.
8. Coverage of these items to be included in roof system warranty.
9. Comply with applicable standards.
10. Roof Edge/Fascia:
 - a. Match profiles indicated.
 - b. Include accessories such as prefabricated inside and outside corners, Overflow and Downspout Scuppers, Edging Extensions, Fascia Sumps, and other items indicated.
 - c. Base: SecurEdge 2000 Fascia by Carlisle SynTec.
11. Coping:
 - a. Match profiles indicated.
 - b. Utilize existing coping to the greatest extent possible. Provide new coping to replace existing coping where required by roof system manufacturer.
 - c. Include accessories such as prefabricated inside and outside corners (seamed), End Caps, Saddles, Tee's, Crosses, Transition Pieces and Radiused Copings, and other items indicated.
 - d. Base Product: SecurEdge 200 Coping by Carlisle SynTec.
- G. TPO Walkway Roll:
 1. Manufacturer's standard walkway roll stock, designed to protect TPO roof membrane.
 - a. Slip-resistant surface.
 2. Nominal Thickness: 160 mil.
 3. Size: 34 inches x 50 feet roll.
 4. Secure to roof membrane by heat welding.
 5. Discontinue walkway at roof membrane seams.
 6. Color:
 - a. White.
 7. Base Product: Sure-Weld Walkway Roll by Carlisle SynTec.
- H. Nailing Strips:
 1. As detailed and required.
- I. Pipe Flashings:
 1. Provide for each pipe penetration; include clamps, adhesive and sealants.
- J. Adhesives, Cleaners, and Primers:
 1. As recommended by roofing manufacturer.
- K. Preservative Treated Wood Blocking:
 1. See Section 06 10 00.
- L. Other Materials as required by manufacturer for complete system warranty.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the entire area to be roofed for acceptability.
- B. Ensure substrate for insulation or roofing membrane is clean, smooth, dry, and free of projections or contaminants that would prevent proper application of or be incompatible with the new installation, such as fins, sharp edges, and foreign materials.
- C. Correct unsatisfactory conditions.

- D. Commencement of roofing activities constitutes acceptance of all conditions affecting installation and roofing system performance.

3.2 INSTALLATION

A. Vapor Retarder:

1. Install in largest practical widths.
2. Bond vapor retarder to substrate using approved adhesive.
3. Install continuously.
 - a. Ensure surfaces to be taped are clean and dry.
 - b. Ensure that no discontinuities occur, including at seams, penetrations, and edge terminations.
 - c. Join sections of vapor retarder and lap seams in direction of water flow.
 - d. Continuously seal roof vapor retarder to wall air and moisture retarder.
4. Seal around pipes, conduits, curbs, safety tie-backs, and other penetrations with pipe boots in accordance with manufacturer's instructions.
5. Maintain continuity of vapor retarder over expansion joints.
6. Repair holes in vapor retarder with method and material recommended by manufacturer.
7. Protect vapor retarder from damage until covered with insulation.

B. Wood Nailers:

1. Design to resist a minimum of 200 pounds/LF in any direction per SPRI Test Method RE-1.
2. Provide where indicated or required for proper securement of roofing system.
3. Install top of blocking flush with top of insulation.

C. Re-roof Areas:

1. Replace Existing Nailers which are unsound due to rot, excess moisture or deterioration.
2. Inspect existing nailers which are to remain in place for adequacy of anchorage.
 - a. Re-secure or replace nailers as required to resist 300 pounds/LF any direction.

D. Insulation:

1. Where required thickness of insulation is greater than 2 inches: Install insulation in at least 2 layers.
2. Stagger board joints in successive layers laterally and longitudinally.
3. Butt joints tightly.
4. Cut insulation neatly to fit around roof penetrations and projections.
5. Secure insulation with approved adhesive.

E. Membrane:

1. Unroll and position membrane without stretching.
 - a. Allow membrane to relax prior to bonding.
2. Position sheets to accommodate contours of roof deck.
3. Apply bonding adhesive in accordance with the manufacturer's instructions, to exposed underside of the membrane and the corresponding substrate area.
4. Protect membrane from stains/discoloring caused by adhesives.
5. Membrane Splices:
 - a. Hot air weld TPO membrane sheets using Automatic Hot Air Welding Machine or Hot Air Hand Welder in accordance with the manufacturer's hot air welding procedures.
 - b. Locate field splices away from low areas and drain sumps.
 - c. Shingle field splices to avoid bucking water.

- d. Probe seams once the hot air welds have thoroughly cooled.
 - e. Repair seam deficiencies same day they are discovered.
 - f. Apply sealant of type recommended by membrane manufacturer on cut edges of reinforced membrane where scrim reinforcement is exposed after seam probing is complete.
6. Secure membrane along the perimeter of each roof level, roof section, curb, skylight, penthouse, and other penetrations as recommended by membrane manufacturer.
7. Flashing:
- a. Follow manufacturer's typical flashing procedures for wall, curb, and penetration flashing including metal edging/coping and roof drain applications.
 - b. Flashing of parapets, curbs, expansion joints and other parts of roof must be performed using reinforced TPO membrane.
 - c. Manufacturer's standard, non-reinforced TPO membrane can be used for flashing pipe penetrations, sealant pockets, scuppers, as well as inside and outside corners when use of pre-fabricated accessories is not feasible.
 - d. Terminate base-of-wall flashings in accordance with manufacturer's approved details.
 - e. Pre-flashing at sheet metal parapet copings:
 - 1) Extend TPO membrane, flashing or both over top of parapet prior to capping with sheet metal.
 - f. Expansion Joints:
 - 1) Extend TPO membrane across roofing expansion joints.
 - 2) Include adequate slack in membrane to accommodate anticipated movement.
 - 3) See drawings for low profile expansion joint detail.
8. Hot or Cold Weather Procedures:
- a. Comply with manufacturer's instructions.

3.3 INSTALLATION - EDGE METAL AND COPING

- A. Sub-flash details with a layer of TPO membrane prior to installation of edge metal or coping system.
- B. Secure anchor cleat to blocking as recommended, using corrosion-resistant fasteners.
- C. Install splice plates and snap-on covers.

3.4 INSTALLATION – WALKWAYS

- A. Install walkways at traffic concentration points, such as roof hatches, access doors, rooftop ladders, or locations as indicated.
- B. Clean surfaces to be bonded.
- C. Secure by heat welding as recommended by membrane manufacturer.

3.5 PROTECTION

- A. When completion of flashings and terminations is not achieved by end of workday, seal system to temporarily prevent water infiltration.
- B. Remove temporary water cutoffs prior to proceeding with Work.
- C. Remove and replace wet insulation.

END OF SECTION

This page intentionally left blank.

SECTION 07 72 33

ROOF HATCHES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Roof Hatches.
 - 2. Hatch Guardrail System.
 - 3. Ladder Safety Post.
- B. Furnish labor, materials, tools, equipment, and services for Roof Hatches, Guardrail System, and Ladder Safety Post as indicated, in accordance with provisions of Contract Documents.
- C. Completely coordinate with work of other trades.

1.2 REFERENCES

- A. ASTM International (ASTM):
 - 1. ASTM A36 Standard Specification for Structural Steel
 - 2. ASTM A123 Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
- B. Occupational Safety & Health Administration (OSHA):
 - 1. 29 CFR 1910.28 Fall Protection in General Industry.

1.3 SUBMITTALS

- A. Product Data:
 - 1. Manufacturer's literature for listed materials.
- B. Shop Drawings:
 - 1. Show profiles, accessories, locations, and dimensions.
- C. Contract Closeout Information:
 - 1. Warranty.

1.4 WARRANTY

- A. Hatch:
 - 1. Manufacturer's standard 5-year warranty.
 - 2. Warranty to cover repair or replacement in event of defects in material and workmanship including leakage, materials, or construction.
- B. Guardrails:
 - 1. Manufacturer's standard 5-year warranty from defects in material and workmanship.
- C. Ladder Safety Post:
 - 1. Manufacturer's standard 5-year warranty from defects in material and workmanship.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Roof Hatches:
 - 1. Base: Bilco Company.

- 2. Optional:
 - a. Milcor.
 - b. Nystrom.
 - c. Wasco Products.
- B. Hatch Guardrail:
 - 1. Base: Bilco Company.
 - 2. Optional:
 - a. KeeHatch.
 - b. Nystrom.
- C. Ladder Safety Post:
 - 1. Base: Bilco Company.

2.2 DESIGN CRITERIA

- A. Reinforce for 40 psf live loading with a maximum deflection of 1/150th of span and 20 psf wind uplift.
- B. Controlled cover operation throughout the entire arc of opening and closing.
- C. Entire assembly and installation shall be weathertight with fully welded corner joints on cover and curb.

2.3 ROOF HATCHES

- A. Basis of Design: Subject to compliance with requirements, provide the following or approved equal by one of the optional manufacturers listed above.
 - 1. Size and Model Number:
 - a. Size: Bilco Series S; Verify size in field.
- B. Roof Hatch (Galvanized Steel Units):
 - 1. Curb and Cover Material: 0.067-inch (14 gauge) Steel sheet, galvanized, ASTM-A653 G90.
 - 2. Cover Liner Material: 0.026-inch (22 gauge) Steel sheet, galvanized, ASTM-A653 G90.
 - 3. Finish:
 - a. Shop Primer: Manufacturer's standard primer, minimum 2.0 mils dry.
 - b. Field Finish: Paint per manufacturer's specifications.
- C. Hardware:
 - 1. Self-lifting mechanism with automatic locking hold open device.
 - 2. Pintle hinges: Type 316 stainless steel.
 - 3. Slam latch with handles and padlock hasps:
 - a. Provide handles inside and outside.
 - b. Zinc-plated, chromate-sealed.
- D. Include the following at each Roof Hatch:
 - 1. Hatch Guardrail.
 - 2. Ladder Safety Post.

2.4 HATCH GUARDRAIL SYSTEM

- A. General:
 - 1. Provide at each hatch.
 - 2. Provide model to match hatch size and ladder position.

3. Base Product: Bil-Guard 2.0 by Bilco.
- B. Performance characteristics:
 1. Attach to the cap flashing of roof hatch without penetrating roofing material.
 2. Comply with OSHA 29 CFR 1910.23 and other applicable codes.
 3. Exceed OSHA strength requirements with a factor of safety of 2.
- C. Posts and Rails:
 1. 1-1/4-inch Schedule 40 pipe.
 - a. Material: 6061 T6 Aluminum.
 - b. Finish: Powder Coat.
 - c. Color: High visibility safety yellow.
- D. Hardware:
 1. Mounting brackets: 6063T5 Aluminum extrusions.
 2. Locking mechanism: Cast Aluminum.
 3. Spring Hinges: Type 316 Stainless Steel.
 4. Fasteners: Type 316 Stainless Steel.
- E. Gate:
 1. Self-closing and latching design of material matching guardrail system.
 2. Locate Gate on most safe and convenient side of each hatch (relative to ladder position) while avoiding roof obstructions.
 - a. Exception: Locations specifically indicated on Drawings.

2.5 LADDER SAFETY POST

- A. General:
 1. Furnish and install where indicated on plans ladder safety post Model LU-2. The ladder safety post shall be pre-assembled from the manufacturer.
- B. Performance characteristics:
 1. Tubular post shall lock automatically when fully extended.
 2. Safety post shall have controlled upward and downward movement.
 3. Release lever shall disengage the post to allow it to be returned to its lowered position.
 4. Post shall have adjustable mounting brackets to fit ladder rung spacing up to 14" (356mm) on center and clamp brackets to accommodate ladder rungs up to 1-3/4" (44mm) in diameter.
- C. Post: Shall be manufactured of high strength square tubing. A pull up loop shall be provided at the upper end of the post to facilitate raising the post.
- D. Material of construction: Shall be steel Model LU-2.
- E. Balancing spring: A stainless steel spring balancing mechanism shall be provided to provide smooth, easy, controlled operation when raising and lowering the safety post.
- F. Hardware: All mounting hardware shall be Type 316 stainless steel.
- G. Finishes: Factory finish shall be hot dip galvanized steel (Model LU-2).

2.6 FABRICATION

- A. Fabricate from metal sheet and plate in shop, to sizes indicated; modify if necessary to comply with requirements.
- B. Where standard hatch units are not available for sizes and types required, provide custom fabricated units.

- C. Curb:
 - 1. 12 inches high with a 3-1/2 inch flange with holes for securing curb to the roof deck.
 - 2. Integral metal cap-flashing
 - a. Same gauge and material as curb.
 - b. Fully welded corners.
- D. Cover:
 - 1. Minimum 2-1/2 inch weather flange.
- E. Insulation:
 - 1. Rigid board glass or mineral fiber, laminated between sheets of metal.
 - 2. Insulate curbs and covers with minimum 1 inch thick insulation.
- F. Gaskets:
 - 1. Tubular or fingered gaskets.
 - 2. Neoprene, PVC, or molded block design sponge neoprene.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Coordinate with decking and roofing.
- B. Verify as-built conditions and coordinate with hatch manufacturer's details.
- C. Verify that hatch rail system installation will not disrupt other trades.
- D. Report and correct defects prior to installation.
- E. Examine substrates and openings for compliance with requirements for installation tolerances and other conditions affecting performance. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Roof Hatches:
 - 1. Install wood blocking, specified in Division 06, as needed to ensure that the curb has a minimum exposure of 8 inches of vertical surface above adjacent roof insulation for proper flashing.
 - 2. Securely anchor units by bolting or welding, as appropriate.
 - 3. Flash and counter flash to provide weathertight installation.
 - 4. Touch up abraded areas with zinc rich paint.
- B. Hatch Guardrails:
 - 1. Install hatch guardrail system per the manufacturer's instructions.
 - 2. Permanently bolt guardrail assembly to vertical face of Roof Hatch curb.
 - 3. Seal per manufacturer's instructions to make penetrations watertight.
- C. Ladder Safety Post:
 - 1. Install products in strict accordance with manufacturer's instructions and approved submittals. Locate units level, plumb, and in proper alignment with adjacent work.
 - 2. Test units for proper function and adjust until proper operation is achieved.
 - 3. Repair finishes damaged during installation.
 - 4. Restore finishes so no evidence remains of corrective work.

3.3 ADJUSTING AND CLEANING

- A. Test units for proper function and adjust until proper operation is achieved.
- B. Clean exposed surfaces using methods acceptable to the manufacturer which will not damage finish.
- C. Repair finishes damaged during installation.

END OF SECTION

This page intentionally left blank.